

**SOURCE TEST REPORT
2018 SOURCE EMISSION TESTS
CASCADE STEEL ROLLING MILLS, INC.
A SCHNITZER COMPANY
STEEL SHREDDER
OAKLAND, CALIFORNIA**

Prepared For:

Schnitzer Steel
1101 Embarcadero West
Oakland, California 94607

For Submittal To:

Bay Area Air Quality Management District
San Francisco, California 94109

Prepared By:

Montrose Air Quality Services, LLC
2825 Verne Roberts Circle
Antioch, California 94509

Document Number:	005AS-452603-RT-310 (NST-5178)
Test Dates:	October 29-31, 2018
Submittal Date:	December 27, 2018

REVIEW AND CERTIFICATION

All work, calculations, and other activities and tasks performed and presented in this document were carried out by me or under my direction and supervision. I hereby certify that, to the best of my knowledge, Montrose operated in conformance with the requirements of the Montrose Quality Management System and ASTM D7036-04 during this test project.

Signature:  for R0 Date: 12/27/2018
Name: Robert Odell Title: Client Project Manager

I have reviewed, technically and editorially, details calculations, results, conclusions, and other appropriate written materials contained herein. I hereby certify that, to the best of my knowledge, the presented material is authentic, accurate, and conforms to the requirements of the Montrose Quality Management System and ASTM D7036-04.


Signature:  Date: 12/27/2018
Name: Dan Duncan Title: QA/QC Manager

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 SUMMARY OF TEST PROGRAM AND RESULTS.....	5
1.1 PROGRAM OBJECTIVES	5
1.2 PROJECT CONTACTS.....	10
2.0 SOURCE DESCRIPTION	11
2.1 FACILITY AND SOURCE DESCRIPTION	11
2.2 SAMPLING LOCATIONS AND ACCESS	11
2.3 OPERATING CONDITIONS AND PROCESS DATA.....	11
3.0 TEST METHOD DETAILS	13
3.1 LIST OF TEST METHODS.....	13
3.1.1 EPA Method 1, Traverse Points	13
3.1.2 EPA Method 2 - Velocity and Volumetric Flow Rate	13
3.1.3 Gaseous Emissions	14
3.1.4 Moisture Content.....	14
3.1.5 Total Organic Carbon.....	14
3.1.6 Precursor Organic Compounds & Benzene.....	14
3.1.7 Hexavalent Chromium (Cr6 ⁺)	15
3.1.8 Polychlorinated Biphenyl Emissions.....	15
4.0 TEST RESULTS AND OVERVIEW	16
4.1 DISCUSSION OF RESULTS	16
4.2 DEVIATIONS AND EXCEPTIONS	16
APPENDIX A CALCULATIONS	25
A.1 Hexavalent Chromium Spreadsheets	26
A.2 Benzene Spreadsheets	41
A.3 Total Organic Carbon Spreadsheets.....	46
A.4 PolyChlorinated Biphenyl Spreadsheets	51
A.5 Example Calculations	55
A.6 General Emissions Calculations	65
APPENDIX B FIELD AND COMPUTER-GENERATED DATA	71
B.1 Sampling Locations	72
B.2 Hexavalent Chromium Data Sheets.....	74
B.3 PolyChlorinated Biphenyl Data Sheets	82
B.4 CEM Data.....	90
APPENDIX C LABORATORY ANALYSIS DATA	111
C.1 Hexavalent Chromium Analyses.....	112
C.2 Benzene Analyses.....	123
C.3 Total Organic Carbon – EPA 25C Analyses	137

C.4 Total Organic Carbon – TO-12 Analyses	142
C.5 PolyChlorinated Biphenyls Analyses	151
APPENDIX D CLIENT PROCESS DATA	188
D.1 Process Data	189
APPENDIX E QUALITY ASSURANCE/QUALITY CONTROL	191
E.1 Quality Assurance Program Summary and Equipment Calibration Schedule	192
E.2 ASTM D-7036 Accreditation, ARB Certification, and QI Certificates	197
E.3 CEM Analyzer Calibration Data	207
E.4 Span Gas Certificates	212
E.5 Equipment Calibration Data	219
APPENDIX F MISCELLANEOUS INFORMATION	224
F.1 Permit Excerpts	225

1.0 SUMMARY OF TEST PROGRAM AND RESULTS

1.1 PROGRAM OBJECTIVES

Montrose Air Quality Services, LLC (Montrose) was contracted by Schnitzer Steel (Schnitzer) to perform a series of air emission tests at their facility located in Oakland, California. The tests were conducted to determine compliance with the source testing limitations of the Bay Area Air Quality Management District (BAAQMD) Permit Application No. 27762

The testing was conducted by Robert Odell, Nishad Patel, Madison Koch, and Shawn Jaworski of Montrose on October 29-31, 2018. Daniel Lee of Schnitzer Steel coordinated the testing program. The tests were conducted according to a test plan dated September 25, 2018 that was submitted to the BAAQMD and assigned NST-5178. Montrose performed the tests to measure the following emission parameters:

- Primary Parameters
 - Total POC (lb/hr and lb/ton material processed)
 - Specific TOCs (lb/hr and lb/ton material processed)
 - Hexavalent chromium (lb/hr and lb/ton material processed)
 - PCBs (lb/hr and lb/ton material processed)
- Gaseous Species as Diluent Gases
 - Oxygen and carbon dioxide (O₂ and CO₂) – % volume dry
 - Stack gas moisture content (% by volume)
 - Stack gas volumetric flow rate (dscfm)
- Facility Data
 - Feed rate of vehicles in tons per hour
 - Feed rate of light iron in tons per hour

This report presents the test results and supporting data, descriptions of the testing procedures, descriptions of the facility and sampling locations, and a summary of the quality assurance procedures used by Montrose. The average emission test results are summarized in Tables 1-1 through 1-4. Detailed results for individual test runs can be found in Section 4.0. All supporting data can be found in the appendices.

**TABLE 1-1
SUMMARY OF AVERAGE HEXAVALENT CHROMIUM EMISSIONS
SCHNITZER STEEL
SHREDDER**

Run Number:	Car Bodies Only	Light Iron Only
Process Data:		
Material Feed Rate, tph	██████████	██████████
Material Output, tph	██████████	██████████
Ventilation Fan 1 Amps	519	515
Ventilation Fan 2 Amps	544	540
Mill Water Spray Flow Rate	29	28
Pres Decay – Scrubber 1, inWG	29	29
Pres Decay – Scrubber 2, inWG	24	24
Flue Gas:		
O ₂ , % volume dry	21.0	20.9
CO ₂ , % volume dry	0.03	0.03
Moisture content, % volume	2.1	2.4
Flue gas temperature °F	65.5	69.3
Volumetric flow rate, dscfm	██████████	██████████
Hexavalent Chromium, Cr⁶⁺:		
ug/m ³	██████████	██████████
lb/hr	1.5E-05	1.1E-05
lb/ton material proc'd	██████████	██████████
Hexavalent Chromium, Cr⁶⁺ (Blank-Corrected):		
ug/m ³	██████████	██████████
lb/hr	<4.9E-06	<3.9E-06
lb/ton material proc'd	██████████	██████████

TABLE 1-2
SUMMARY OF AVERAGE TOC EMISSIONS
SCHNITZER STEEL
SHREDDER

Run Number:	Car Bodies Only	Light Iron Only
Process Data:		
Material Feed Rate, tph		
Material Output, tph		
Ventilation Fan 1 Amps	519	515
Ventilation Fan 2 Amps	544	540
Mill Water Spray Flow Rate	29	28
Pres Decay – Scrubber 1, inWG	29	29
Pres Decay – Scrubber 2, inWG	24	24
Flue Gas:		
O ₂ , % volume dry	20.9	20.9
CO ₂ , % volume dry	0.03	0.03
Moisture content, % volume	2.1	2.4
Flue gas temperature °F	69.3	69.3
Volumetric flow rate, dscfm		
Benzene:		
lb/hr	4.3E-02	< 7.5E-03
lb/ton material proc'd		
M25A - POC (TNMNEOC):		
lb/hr as CH ₄	183	86
lb/ton material proc'd		
M25C - POC (TNMNEOC):¹		
lb/hr as CH ₄	6.53	< 8.21
lb/ton material proc'd		
MTO12 - POC (TNMNEOC):¹		
lb/hr as CH ₄	5.50	3.69
lb/ton material proc'd		

1 Based on the collected data, it is speculated that the canisters collected for M25C and MTO12 analysis had a leak as the results provided were substantially less than the method 25a test. Additionally, there were elevated results of methanol and methylene chloride in the canisters, which is suspected to have come from the ambient air inside the mobile lab as those reagents were being utilized as part of the CARB 428 recovery. A retest of these methods is anticipated to occur in early January 2019. See discussion in Section 4.2 for more information.

**TABLE 1-3
SUMMARY OF AVERAGE PCB EMISSIONS
SCHNITZER STEEL
SHREDDER**

Run Number:	Car Bodies Only	Light Iron Only
Process Data:		
Material Feed Rate, tph	██████████	██████████
Material Output, tph	██████████	██████████
Ventilation Fan 1 Amps	519	515
Ventilation Fan 2 Amps	544	540
Mill Water Spray Flow Rate	29	28
Pres Decay – Scrubber 1, inWG	29	29
Pres Decay – Scrubber 2, inWG	24	24
Flue Gas:		
O ₂ , % volume dry	21.0	20.9
CO ₂ , % volume dry	0.03	0.03
Moisture content, % volume	1.6	1.1
Flue gas temperature °F	63.8	67.5
Volumetric flow rate, dscfm	██████████	██████████
Chlorobiphenyls:		
lb/hr	1.92E-05	1.71E-03
lb/ton material proc'd	██████████	██████████
Dichlorobiphenyls:		
lb/hr	2.33E-04	8.96E-03
lb/ton material proc'd	██████████	██████████
Trichlorobiphenyls:		
lb/hr	3.94E-04	8.12E-03
lb/ton material proc'd	██████████	██████████
Tetrachlorobiphenyls:		
lb/hr	1.02E-04	1.84E-03
lb/ton material proc'd	██████████	██████████
Pentachlorobiphenyls:		
lb/hr	1.05E-05	2.71E-04
lb/ton material proc'd	██████████	██████████
Hexachlorobiphenyls:		
lb/hr	2.59E-06	8.45E-05
lb/ton material proc'd	██████████	██████████

**TABLE 1-4
SUMMARY OF AVERAGE PCB EMISSIONS
SCHNITZER STEEL
SHREDDER**

Run Number:	Car Bodies Only	Light Iron Only
Process Data:		
Material Feed Rate, tph		
Material Output, tph		
Ventilation Fan 1 Amps	519	515
Ventilation Fan 2 Amps	544	540
Mill Water Spray Flow Rate	29	28
Pres Decay – Scrubber 1, inWG	29	29
Pres Decay – Scrubber 2, inWG	24	24
Flue Gas:		
O ₂ , % volume dry	21.0	20.9
CO ₂ , % volume dry	0.03	0.03
Moisture content, % volume	1.7	1.1
Flue gas temperature °F	63.8	67.5
Volumetric flow rate, dscfm		
Heptachlorobiphenyls:		
lb/hr	1.29E-06	1.24E-05
lb/ton material proc'd		
Octachlorobiphenyls:		
lb/hr	2.83E-07	2.54E-06
lb/ton material proc'd		
Nonachlorobiphenyls:		
lb/hr	< 1.76E-08	6.54E-07
lb/ton material proc'd		
Decachlorobiphenyls:		
lb/hr	< 9.59E-09	7.33E-08
lb/ton material proc'd		
Total PCBs:		
lb/hr	7.63E-04	2.10E-02
lb/ton material proc'd		

1.2 PROJECT CONTACTS

A list of project participants is included below:

Facility Information

Source Location:	Schnitzer Steel 1101 Embarcadero West Oakland, California 94607	
Project Contact:	Mr. Daniel Lee	Mr. Daniel Lee
Role:	Cascade Steel Rolling Mills, Inc., a Schnitzer Company	Cascade Steel Rolling Mills, Inc., a Schnitzer Company
Company:	(503) 434-3324	(503) 434-3324
Telephone:	dlee@schn.com	dlee@schn.com
Email:	Schnitzer Steel	Schnitzer Steel

Agency Information

Regulatory Agency: Bay Area Air Quality Management District
Agency Contact: Mr. Jerry Bovee
Telephone: (415) 749-4612
Email: jbovee@baaqmd.gov

Testing Company Information

Testing Firm:	Montrose Air Quality Services, LLC (Montrose)	
Contact:	Robert Odell	Kevin Crosby
Title:	Client Project Manager	Vice President, Technical
Telephone:	(925) 642-2776	(925) 680-4337
Email:	rodell@montrose-env.com	kcrosby@montrose-env.com

Laboratory Information

Laboratory:	Chester LabNet
City, State:	Tigard, Oregon
Analysis:	CARB 425
Laboratory:	Vista Analytical
City, State:	El Dorado Hills, California
Analysis:	CARB 428
Laboratory:	Atmospheric Analytical & Consulting
City, State:	Antioch, California
Analysis:	EPA 25C & TO-15

Montrose is qualified to conduct this test program and has established a quality management system that led to accreditation with ASTM Standard D-7036 (Standard Practice for Competence of Air Emission Testing Bodies). Montrose completed multiple functional assessments for ASTM D7036-04 which were conducted by the American Association for Laboratory Accreditation (A2LA). All testing is overseen and supervised on site by at least one Qualified Individual (QI), as defined in 40 CFR 72.2.

2.0 SOURCE DESCRIPTION

2.1 FACILITY AND SOURCE DESCRIPTION

The Schnitzer Steel facility is located at 1101 Embarcadero West, Oakland, California, 94607 at the Port of Oakland. The facility serves as a processing and loading center for scrap metal bound for marine transport. The metal shredder is composed of multiple steel alloy hammers that are rotated at speed by an electric motor and impacted against the material to be shredded. Infeed material consists primarily of automobiles that have been pre-processed to minimize the amount of hazardous fluids and non-usable metal content. A conveyor system is loaded with infeed material by manually-operated cranes, and then fed into the shredder at a known mass rate.

Water is injected into the shredder to reduce the heat generated as well as to reduce emissions of particulate matter. The emissions from the shredder are captured by an abatement system that completely encloses the shredder. The exhaust system ducts the collected air through two venturi scrubbers before being emitted to atmosphere via a vertical stack.

2.2 SAMPLING LOCATIONS AND ACCESS

Information regarding the sampling location is presented below:

Sample location ID: P-15 Exhaust Stack

Stack exit height: 62 feet

Configuration: Cylindrical, vertical

Dimensions: [REDACTED] inches I.D.

Port locations: Appx. 15 ft. (~[REDACTED] duct diameters) upstream from (below) the stack exit
Appx. 37 ft. (~[REDACTED] duct diameters) downstream from (above) the
nearest flow disturbance

Port access: Ladder to permanent platform

Traverse point information is presented below:

- Isokinetic tests - 12 points total, 6 from each of 2 ports located 90 degrees apart from one another

2.3 OPERATING CONDITIONS AND PROCESS DATA

Emission tests were performed while the source/units and air pollution control devices were operating at the conditions required by the permit. Tests were conducted under two conditions:

- Test Condition 1: Car bodies processed only
- Test Condition 2: Light Iron processed only

Plant personnel established the test conditions and collected all applicable unit-operating data. Montrose monitored the collection of process data and provided additional data collection as necessary to document operation. Process data includes:

- Ventilation fan (Cond. 26401.) amperage
- Water Sprays (A-6) flow rate
- Water flow rate and pressure decay for each Venturi Scrubber
- Hourly material processed by the shredder (lbs or tons)
- Shredder enclosure photos

3.0 TEST METHOD DETAILS

3.1 LIST OF TEST METHODS

The test procedures for this test program are summarized in Table 3-1 below. Additional information regarding specific applications or modifications to standard procedures is presented in the following sub-sections.

**TABLE 3-1
TEST PROCEDURES**

Parameter	Measurement Principle	Reference Method
Volumetric flow rate	Pitot/temperature traverse	EPA 1, 2
O ₂	Paramagnetism	EPA 3A
CO ₂	Non-dispersive infrared	EPA 3A
Moisture	Impinger weight gain	EPA 4
TOC	Flame Ionization Detector	EPA 25A
POC	Gas chromatography	EPA 25C & TO-12
Cr6 ⁺	IC/PCR	CARB 425
PCBs	Gas chromatography	CARB 428
Benzene	Gas chromatography	TO-15

3.1.1 EPA Method 1, Traverse Points

EPA Method 1 was used to assure that representative measurements of volumetric flow rate were obtained by dividing the cross-section of the stack or duct into equal areas, and then locating a traverse point within each of the equal areas. This test location met the acceptable sample location requirements and was located at least two stack or duct equivalent diameters downstream from a flow disturbance and one-half equivalent diameter upstream from a flow disturbance. An EPA Method 1 diagram is included in Appendix B.1.

- Method Deviations: None
- Method Options: None

3.1.2 EPA Method 2 - Velocity and Volumetric Flow Rate

EPA Method 2 was used to measure the gas velocity using an S-type pitot tube connected to a pressure measurement device, and to measure the gas temperature using a calibrated thermocouple connected to a thermocouple indicator. A Type S (Stausscheibe) pitot tube conforming to the geometric specifications in the test method was used, along with an inclined manometer. The measurements were made at traverse points specified by EPA Method 1. The molecular weight of the gas stream was determined from independent measurements of O₂, CO₂, and moisture. The stack gas volumetric flow rate was calculated using the measured average velocity head, the area of the duct at the measurement plane, the measured average temperature, the measured duct static pressure, the molecular weight of the gas stream, and the measured moisture.

- Method Deviations: None

- Method Options: None

3.1.3 Gaseous Emissions

Concentrations of the gaseous constituents of stack gas (O₂, CO₂) were measured using Montrose's dry extractive reference method (RM) monitor system in accordance with EPA Method 3A. This system meets the requirements of EPA methods for gaseous species. Information about the analyzers are presented in Table 3-2. Pertinent information regarding the performance of the method is presented below:

- Method Deviations: Probe was located in one position and not traversed.
- Method Options: None

TABLE 3-2
MAQS CEMS INFORMATION

Analyzer Type	Manufacturer	Model No.	Serial No.	Range
O ₂	CAI	110P	S05008	25%
CO ₂	Horiba	VIA-510	4326876001	10%
TOC	CAI	600 MHFID	B08025	1000 ppm (as propane)

3.1.4 Moisture Content

Moisture content was measured from EPA Methods 4 through CARB methods 425 and CARB 428. Pertinent information regarding the performance of the methods are presented below:

- Method Deviations: EPA Method 4 was utilized as part of the isokinetic CARB 425 & 428 tests.
- Method Options: N/A
- Target Duration: N/A
- Target Sample Volume: N/A

3.1.5 Total Organic Carbon

Concentrations of total organic carbon (TOC) were measured by flame ionization detector. Sample gas was transported wet through a heated sampling system maintained at least 350 degrees Fahrenheit. Pertinent information regarding the performance of the method is presented below:

- Method Deviations: None
- Method Options: Heated sampling system was maintained at 350 degrees Fahrenheit to prevent moisture from interfering with the FID.

3.1.6 Precursor Organic Compounds & Benzene

Emissions of precursor organic compounds (POC) and benzene were measured using EPA 25C, TO-12, and TO-15 respectively. Sample was collected into a single canister and use for

both analyses. Pertinent information regarding the performance of the methods is presented below:

- Method Deviations: Modified to follow sampling requirements of TO-15
- Specific TOCs include: Benzene
- Target and/or Minimum Required Sample Duration: 60 minutes
- Analytical Laboratory: Atmospheric Analytical & Consulting, Inc.

3.1.7 Hexavalent Chromium (Cr⁶⁺)

Emissions of hexavalent chromium were measured using CARB Method 425. Pertinent information regarding the performance of the methods are presented below.

- Method Deviations: A prescreened CARB/BiCARB solution was used in lieu the NaOH reagent. This was to aid in minimizing background chromium and in maintaining a pH of 8.0 to 10.0 during the sampling. pH was measured and logged on a field recovery data sheet onsite. The analytical lab measured, recorded, and reported the pH and temperature of the samples upon receiving them.
- Method Options: Impingers 1 and 2 will be recovered together.
- Onsite Measured pH: Approximately 9
- Lab Measured pH: Approximately 9
- Lab Measured temperature: 2.1 degrees Celsius
- Lab Analysis Dates: Cr⁶⁺: Nov. 5, 2018 & Total Cr: Nov. 13, 2018
- Target and/or Minimum Required Sample Duration: 60 minutes
- Minimum Required Sample Volume: 31.8 dscf
- Analytical Laboratory: Chester LabNet

3.1.8 Polychlorinated Biphenyl Emissions

Concentrations of polychlorinated biphenyls (PCBs) were measured using CARB Method 428. Pertinent information regarding the performance of the method is presented below. Please see appendix B for preliminary calculations for sample volume, duration, and anticipated concentration.

- Method Deviations – None
- Target Sample Duration - 60 minutes
- Minimum Required Sample Volume: 17.6 dscf (0.50 dscm)
- Analytical Laboratory - Vista Analytical Laboratory, El Dorado Hills, CA

4.0 TEST RESULTS AND OVERVIEW

4.1 DISCUSSION OF RESULTS

The average results presented in Tables 1-1 through 1-4. The results of individual compliance test runs performed are presented in Tables 4-1 through 4-8.

Additional information is included in the appendices. Appendix A presents the general and specific equations used for the emissions calculations and computer spreadsheets. Raw field data sheets and data acquisition printouts are included in Appendix B. Laboratory reports and chain of custody sheets for the samples are located in Appendix C. CEM and process data provided by the client is located in Appendix D. Appendix E presents the quality assurance information, including instrument calibration data. Additional correspondence and relevant regulatory information are located in Appendix F.

Both qualitative and quantitative factors contribute to field measurement uncertainty and should be taken into consideration when interpreting the results contained within this report. Whenever possible, Montrose Air Quality Services, LLC, (Montrose) personnel reduce the impact of these uncertainty factors using approved and validated test methods. In addition, Montrose personnel perform routine instrument and equipment calibrations and ensure that the calibration standards, instruments, and equipment used during test events meet, at a minimum, test method specifications as well as the specifications of our Quality Manual and ASTM D 7036-04. The limitations of the various methods, instruments, equipment, and materials utilized during this test have been reasonably considered, but the ultimate impact of the cumulative uncertainty of this project is not fully identified within the results of this report.

4.2 DEVIATIONS AND EXCEPTIONS

There were a couple problems with the canister sampling. No sample was collected during the first test run as the sample line and critical orifice had become plugged with moisture. The sample canisters were relocated to the mobile lab, branched off the method 25a sample line. Based on the collected data, it is speculated that the canisters had a leak at this junction point as the canisters collected substantially less than the method 25a test. Additionally, there were elevated results of methanol and methylene chloride in the canisters, which is suspected to have come from the ambient air inside the mobile lab as those reagents were being utilized as part of the CARB 428 recovery. A retest of these methods is anticipated to occur in early January 2019. As a direct result of this, the benzene results are significantly biased low and will also be retested in early January 2019.

Run 2 of the CARB 428 tests had unexpectedly low velocity numbers, especially compared to the CARB 425 test and run 1. So after Run 3 began, the problem was identified and corrected. There was a kink in the measurement line that was clear when the probe was out of stack for the leak checks but kinked while the probe was in stack. This resulted in low velocity readings for run 2 and partially run 3. As a results the overall sample volume was below anticipated volume but still exceeded the minimum sample volume required. Both tests are included in the average using the velocity measurements from the concurrent CARB 425 tests were used in lieu of the CARB 428 velocities for the purposes of calculating emission rates.

The laboratory analysis for the CARB 428 samples indicated that several of the analytes were 'outside laboratory acceptance criteria'. In this case, when the laboratory finds that the recovery

is outside of range, the signal to noise ratio must be at least 10:1, otherwise the procedure would need to be repeated according to CARB 428, Section 7.8. The analysis proved that the signal to noise ratio was greater than 10:1 for each of these analytes and are therefore acceptable results. Refer to laboratory analysis provided in Appendix C.5 for detailed information.

Run 2 of all test methods and Run 5 of CARB 425 and CARB 428 test methods were paused during the test run due to a jam in the shredder. Once the jams were cleared operation and the testing resumed. The various TOC and POC testing was completed just before the shredder had jammed during Run 5 and was not paused as it was not necessary.

TABLE 4-1
RESULTS SUMMARY HEXAVALENT CHROMIUM EMISSIONS
SCHNITZER STEEL
SHREDDER – CAR BODIES

Run Number:	1-Cr	2-Cr	3-Cr	Average
Date:	10/29/18	10/29/18	10/30/18	--
Time:	2000-2109	2235-2250, 2331-0024	0045-0157	--
Process Data:				
Material Feed Rate, tph	████	████	████	████
Material Output, tph	████	████	████	████
Ventilation Fan 1 Amps	516	521	520	519
Ventilation Fan 2 Amps	541	546	545	544
Mill Water Spray Flow Rate	28	28	30	29
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	23	24	24
Flue Gas:				
O ₂ , % volume dry	20.9	21.0	21.1	21.0
CO ₂ , % volume dry	0.04	0.03	0.03	0.03
Moisture content, % volume	2.1	2.0	2.1	2.1
Flue gas temperature °F	66.7	64.7	65.3	65.5
Volumetric flow rate, dscfm	████	████	████	████
Hexavalent Chromium, Cr⁶⁺:				
ug/m ³	████	████	████	████
lb/hr	2.2E-05	1.4E-05	1.0E-05	1.5E-05
lb/ton material proc'd	████	████	████	████
Hexavalent Chromium, Cr⁶⁺ (Blank-Corrected):				
ug/m ³	████	████	████	████
lb/hr	6.2E-06	<4.6E-06	<3.9E-06	<4.9E-06
lb/ton material proc'd	████	████	████	████

**TABLE 4-2
RESULTS SUMMARY HEXAVALENT CHROMIUM EMISSIONS
SCHNITZER STEEL
SHREDDER – LIGHT IRON**

Run Number:	4-Cr	5-Cr	6-Cr	Average
Date:	10/30/18	10/30/18	10/31/18	--
Time:	2114-2224	2028-2146	0020-0120, 0153-0208	--
Process Data:				
Material Feed Rate, tph	████	████	████	████
Material Output, tph	████	████	████	████
Ventilation Fan 1 Amps	515	516	515	515
Ventilation Fan 2 Amps	540	540	540	540
Mill Water Spray Flow Rate	28	27	28	28
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	24	24	24
Flue Gas:				
O ₂ , % volume dry	21.1	20.7	21.0	20.9
CO ₂ , % volume dry	0.01	0.04	0.03	0.03
Moisture content, % volume	2.4	2.3	2.4	2.4
Flue gas temperature °F	69.5	68.8	69.6	69.3
Volumetric flow rate, dscfm	████	████	████	████
Hexavalent Chromium, Cr⁶⁺:				
ug/m ³	████	████	████	████
lb/hr	1.1E-05	1.2E-05	1.1E-05	1.1E-05
lb/ton material proc'd	████	████	████	████
Hexavalent Chromium, Cr⁶⁺ (Blank-Corrected):				
ug/m ³	████	████	████	████
lb/hr	<3.9E-06	<3.7E-06	<4.0E-06	<3.9E-06
lb/ton material proc'd	████	████	████	████

**TABLE 4-3
RESULTS SUMMARY POC EMISSIONS
SCHNITZER STEEL
SHREDDER – CAR BODIES**

Run Number:	1-TOC	2-TOC	3-TOC	Average
Date:	10/29/18	10/29/18	10/30/18	--
Time:	2000-2109	2235-2250, 2331-0024	0045-0157	--
Process Data:				
Material Feed Rate, tph	████	████	████	████
Material Output, tph	████	████	████	████
Ventilation Fan 1 Amps	516	521	520	519
Ventilation Fan 2 Amps	541	546	545	544
Mill Water Spray Flow Rate	28	28	30	29
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	23	24	24
Flue Gas:				
O ₂ , % volume dry	21.1	20.7	21.0	20.9
CO ₂ , % volume dry	0.01	0.04	0.03	0.03
Moisture content, % volume	2.1	2.0	2.1	2.1
Flue gas temperature °F	69.5	68.8	69.6	69.3
Volumetric flow rate, dscfm	████	████	████	████
Benzene:				
lb/hr	N/A	3.7E-02	4.8E-02	4.3E-02
lb/ton material processed	████	████	████	████
M25A - POC (TNMNEOC):				
lb/hr as CH ₄	N/A	212	154	183
lb/ton material proc'd	████	████	████	████
M25C - POC (TNMNEOC):				
lb/hr as CH ₄	N/A	5.40	7.67	6.53
lb/ton material proc'd	████	████	████	████
MTO12 - POC (TNMNEOC):				
lb/hr as CH ₄	N/A	4.22	6.77	5.50
lb/ton material proc'd	████	████	████	████

**TABLE 4-4
RESULTS SUMMARY POC EMISSIONS
SCHNITZER STEEL
SHREDDER – LIGHT IRON**

Run Number:	4-TOC	5-TOC	6-TOC	Average
Date:	10/30/18	10/30/18	10/31/18	--
Time:	2114-2214	2253-2353	0020-0120	--
Process Data:				
Material Feed Rate, tph	████	████	████	████
Material Output, tph	████	████	████	████
Ventilation Fan 1 Amps	515	516	515	515
Ventilation Fan 2 Amps	540	540	540	540
Mill Water Spray Flow Rate	28	27	28	28
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	24	24	24
Flue Gas:				
O ₂ , % volume dry	21.1	20.7	21.0	20.9
CO ₂ , % volume dry	0.01	0.04	0.03	0.03
Moisture content, % volume	2.4	2.3	2.4	2.4
Flue gas temperature °F	69.5	68.8	69.6	69.3
Volumetric flow rate, dscfm	████	████	████	████
Benzene:				
lb/hr	1.4E-02	5.1E-03	< 3.5E-03	< 7.5E-03
lb/ton material proc'd	████	████	████	████
M25A - POC (TNMNEOC):				
lb/hr as CH ₄	81	84	93	86
lb/ton material proc'd	████	████	████	████
M25C - POC (TNMNEOC):				
lb/hr as CH ₄	14.5	7.98	< 2.15	< 8.21
lb/ton material proc'd	████	████	████	████
MTO12 - POC (TNMNEOC):				
lb/hr as CH ₄	7.15	2.66	1.24	3.69
lb/ton material proc'd	████	████	████	████

**TABLE 4-5
RESULTS SUMMARY PCB EMISSIONS
SCHNITZER STEEL
SHREDDER – CAR BODIES**

Run Number:	1-PCB	2-PCB	3-PCB	Average
Date:	10/29/18	10/29/18	10/30/18	--
Time:	2000-2108	2235-2250, 2331-0023	0045-0158	--
Process Data:				
Material Feed Rate, tph	████	████	████	████
Material Output, tph	████	████	████	████
Ventilation Fan 1 Amps	516	521	520	519
Ventilation Fan 2 Amps	541	546	545	544
Mill Water Spray Flow Rate	28	28	30	29
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	23	24	24
Flue Gas:				
O ₂ , % volume dry	20.9	21.0	21.1	21.0
CO ₂ , % volume dry	0.04	0.03	0.03	0.03
Moisture content, % volume	1.7	1.9	1.1	1.6
Flue gas temperature °F	66.0	62.8	62.7	63.8
Volumetric flow rate, dscfm	████	████	████	████
Chlorobiphenyls:				
lb/hr	2.98E-05	1.69E-05	1.10E-05	1.92E-05
lb/ton material proc'd	████	████	████	████
Dichlorobiphenyls:				
lb/hr	3.23E-04	2.05E-04	1.72E-04	2.33E-04
lb/ton material proc'd	████	████	████	████
Trichlorobiphenyls:				
lb/hr	6.18E-04	3.32E-04	2.31E-04	3.94E-04
lb/ton material proc'd	████	████	████	████
Tetrachlorobiphenyls:				
lb/hr	1.48E-04	8.04E-05	7.69E-05	1.02E-04
lb/ton material proc'd	████	████	████	████
Pentachlorobiphenyls:				
lb/hr	1.49E-05	9.39E-06	7.36E-06	1.05E-05
lb/ton material proc'd	████	████	████	████
Hexachlorobiphenyls:				
lb/hr	4.63E-06	1.98E-06	1.16E-06	2.59E-06
lb/ton material proc'd	████	████	████	████

**TABLE 4-6
RESULTS SUMMARY PCB EMISSIONS
SCHNITZER STEEL
SHREDDER – CAR BODIES**

Run Number:	1-PCB	2-PCB	3-PCB	Average
Date:	10/29/18	10/29/18	10/30/18	--
Time:	2000-2108	2235-2250, 2331-0023	0045-0158	--
Process Data:				
Material Feed Rate, tph	████	████	████	████
Material Output, tph	████	████	████	████
Ventilation Fan 1 Amps	516	521	520	519
Ventilation Fan 2 Amps	541	546	545	544
Mill Water Spray Flow Rate	28	28	30	29
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	23	24	24
Flue Gas:				
O ₂ , % volume dry	20.9	21.0	21.1	21.0
CO ₂ , % volume dry	0.04	0.03	0.03	0.03
Moisture content, % volume	1.7	1.9	1.1	1.7
Flue gas temperature °F	66.0	62.8	62.7	63.8
Volumetric flow rate, dscfm	████	████	████	████
Heptachlorobiphenyls:				
lb/hr	3.02E-06	6.75E-07	1.74E-07	1.29E-06
lb/ton material proc'd	████	████	████	████
Octachlorobiphenyls:				
lb/hr	7.31E-07	7.61E-08	4.13E-08	2.83E-07
lb/ton material proc'd	████	████	████	████
Nonachlorobiphenyls:				
lb/hr	< 1.76E-08	< 2.27E-08	< 1.26E-08	< 1.76E-08
lb/ton material proc'd	████	████	████	████
Decachlorobiphenyls:				
lb/hr	< 1.69E-08	< 5.52E-09	< 6.37E-09	< 9.59E-09
lb/ton material proc'd	████	████	████	████
Total PCBs:				
lb/hr	1.14E-03	6.44E-04	5.00E-04	7.63E-04
lb/ton material proc'd	████	████	████	████

**TABLE 4-7
RESULTS SUMMARY PCB EMISSIONS
SCHNITZER STEEL
SHREDDER – LIGHT IRON**

Run Number:	4-PCB	5-PCB	6-PCB	Average
Date:	10/30/18	10/30/18	10/31/18	--
Time:	2114-2224	2253-0002	0020-0117, 0153-0208	--
Process Data:				
Material Feed Rate, tph	████	████	████	████
Material Output, tph	████	████	████	████
Ventilation Fan 1 Amps	515	516	515	515
Ventilation Fan 2 Amps	540	540	540	540
Mill Water Spray Flow Rate	28	27	28	28
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	24	24	24
Flue Gas:				
O ₂ , % volume dry	21.1	20.7	21.0	20.9
CO ₂ , % volume dry	0.01	0.04	0.03	0.03
Moisture content, % volume	0.9	0.6	1.7	1.1
Flue gas temperature °F	68.1	67.2	67.2	67.5
Volumetric flow rate, dscfm	████	████	████	████
Chlorobiphenyls:				
lb/hr	1.32E-03	1.56E-03	2.23E-03	1.71E-03
lb/ton material proc'd	████	████	████	████
Dichlorobiphenyls:				
lb/hr	6.21E-03	8.42E-03	1.22E-02	8.96E-03
lb/ton material proc'd	████	████	████	████
Trichlorobiphenyls:				
lb/hr	4.86E-03	8.21E-03	1.13E-02	8.12E-03
lb/ton material proc'd	████	████	████	████
Tetrachlorobiphenyls:				
lb/hr	1.16E-03	2.08E-03	2.27E-03	1.84E-03
lb/ton material proc'd	████	████	████	████
Pentachlorobiphenyls:				
lb/hr	3.50E-04	2.95E-04	1.67E-04	2.71E-04
lb/ton material proc'd	████	████	████	████
Hexachlorobiphenyls:				
lb/hr	1.30E-04	9.20E-05	3.10E-05	8.45E-05
lb/ton material proc'd	████	████	████	████

**TABLE 4-8
RESULTS SUMMARY PCB EMISSIONS
SCHNITZER STEEL
SHREDDER – LIGHT IRON**

Run Number:	4-PCB	5-PCB	6-PCB	Average
Date:	10/30/18	10/30/18	10/31/18	--
Time:	2114-2224	2253-0002	0020-0117, 0153-0208	--
Process Data:				
Material Feed Rate, tph				
Material Output, tph				
Ventilation Fan 1 Amps	515	516	515	515
Ventilation Fan 2 Amps	540	540	540	540
Mill Water Spray Flow Rate	28	27	28	28
Pres Decay – Scrubber 1, inWG	29	29	29	29
Pres Decay – Scrubber 2, inWG	24	24	24	24
Flue Gas:				
O ₂ , % volume dry	21.1	20.7	21.0	20.9
CO ₂ , % volume dry	0.01	0.04	0.03	0.03
Moisture content, % volume	0.9	0.6	1.7	1.1
Flue gas temperature °F	68.1	67.2	67.2	67.5
Volumetric flow rate, dscfm				
Heptachlorobiphenyls:				
lb/hr	1.54E-05	1.59E-05	5.85E-06	1.24E-05
lb/ton material proc'd				
Octachlorobiphenyls:				
lb/hr	1.63E-06	4.02E-06	1.98E-06	2.54E-06
lb/ton material proc'd				
Nonachlorobiphenyls:				
lb/hr	3.12E-07	1.17E-06	4.85E-07	6.54E-07
lb/ton material proc'd				
Decachlorobiphenyls:				
lb/hr	3.89E-08	1.31E-07	5.03E-08	7.33E-08
lb/ton material proc'd				
Total PCBs:				
lb/hr	1.41E-02	2.07E-02	2.82E-02	2.10E-02
lb/ton material proc'd				

APPENDIX A CALCULATIONS

Appendix A.1

Hexavalent Chromium Spreadsheets

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel	*	Test Number.....	1-Cr
Unit / Location.....	Steel Shredder	*	Date.....	10/29/18
Test Method.....	CARB 425	*	Start / Stop Time.....	2000-2109
Meter Box Number.....	CB-22	*	Barometric Press (in Hg).....	30.12
Meter Calibration (Yd).....	0.9890	*	Meter Volume (acf).....	34.613
Stack Area (square feet).....		*	Liquid Volume (ml).....	24.2
Reference Temperature (°F)....	70	*	Meter Temperature (°F).....	62.1
Sample Time (Minutes).....	60	*	Meter Pressure (iwg).....	1.161
Pitot Coefficient	0.8400	*	Velocity Head (iwg).....	1.7016
Nozzle Diameter (in).....	0.160	*	Static Pressure (iwg).....	-0.71
Process Feed, tph.....		*	Stack Temperature (°F).....	66.7
Fuel "HHV" (Btu/scf).....	N/A	*	Stack O ₂ (%).....	20.9
Fuel "F" Factor (dscf/MMBtu)	N/A	*	Stack CO ₂ (%).....	0.0
a Standard Sample Volume (dscf).....				35.08
b Water Vapor Volume (scf).....				1.145
Measured moisture fraction, nondimensional.....				0.032
Theoretical maximum moisture fraction, nondimensional.....				0.021
c Calculated Moisture Fraction (nondimensional).....				0.021
d ₁ Stack Gas Molecular Weight (dry).....				28.841
d ₂ Stack Gas Molecular Weight (wet).....				28.614
e Absolute Stack Pressure (in Hg).....				30.068
f Stack Gas Velocity (ft/sec).....				
g Stack Flow Rate (acfm).....				
h ₁ Stack Flow Rate (dscfm).....				
h ₂ Stack Flow Rate (wscfm).....				
i Isokinetic Ratio (%).....				96.4

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel	*	Test Number.....	2-Cr
Unit / Location.....	Steel Shredder	*	Date.....	10/29/18
Test Method.....	CARB 425	*	Start / Stop Time.....	2235-2250, 2331-0024
Meter Box Number.....	CB-22	*	Barometric Press (in Hg).....	30.12
Meter Calibration (Yd).....	0.9890	*	Meter Volume (acf).....	35.276
Stack Area (square feet).....	████	*	Liquid Volume (ml).....	19.1
Reference Temperature (°F)....	70	*	Meter Temperature (°F).....	61.3
Sample Time (Minutes).....	60	*	Meter Pressure (iwg).....	1.178
Pitot Coefficient	0.8400	*	Velocity Head (iwg).....	1.7261
Nozzle Diameter (in).....	0.160	*	Static Pressure (iwg).....	-0.67
Process Feed, tph.....	████	*	Stack Temperature (°F).....	64.7
Fuel "HHV" (Btu/scf).....	N/A	*	Stack O ₂ (%).....	21.0
Fuel "F" Factor (dscf/MMBtu)	N/A	*	Stack CO ₂ (%).....	0.0
a Standard Sample Volume (dscf).....				35.81
b Water Vapor Volume (scf).....				0.904
Measured moisture fraction, nondimensional.....				0.025
Theoretical maximum moisture fraction, nondimensional.....				0.020
c Calculated Moisture Fraction (nondimensional).....				0.020
d ₁ Stack Gas Molecular Weight (dry).....				28.845
d ₂ Stack Gas Molecular Weight (wet).....				28.628
e Absolute Stack Pressure (Hg).....				30.071
f Stack Gas Velocity (ft/sec).....				████
g Stack Flow Rate (acfm).....				████
h ₁ Stack Flow Rate (dscfm).....				████
h ₂ Stack Flow Rate (wscfm).....				████
i Isokinetic Ratio (%).....				97.4

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel	*	Test Number.....	3-Cr
Unit / Location.....	Steel Shredder	*	Date.....	10/30/18
Test Method.....	CARB 425	*	Start / Stop Time.....	0045-0157
Meter Box Number.....	CB-22	*	Barometric Press (in Hg).....	30.12
Meter Calibration (Yd).....	0.9890	*	Meter Volume (acf).....	35.639
Stack Area (square feet).....		*	Liquid Volume (ml).....	19.4
Reference Temperature (°F)....	70	*	Meter Temperature (°F).....	64.4
Sample Time (Minutes).....	60	*	Meter Pressure (iwg).....	1.173
Pitot Coefficient	0.8400	*	Velocity Head (iwg).....	1.7187
Nozzle Diameter (in).....	0.160	*	Static Pressure (iwg).....	-0.66
Process Feed, tph.....		*	Stack Temperature (°F).....	65.3
Fuel "HHV" (Btu/scf).....	N/A	*	Stack O ₂ (%).....	21.1
Fuel "F" Factor (dscf/MMBtu)	N/A	*	Stack CO ₂ (%).....	0.0
a Standard Sample Volume (dscf).....				35.96
b Water Vapor Volume (scf).....				0.918
Measured moisture fraction, nondimensional.....				0.025
Theoretical maximum moisture fraction, nondimensional.....				0.021
c Calculated Moisture Fraction (nondimensional).....				0.021
d ₁ Stack Gas Molecular Weight (dry).....				28.847
d ₂ Stack Gas Molecular Weight (wet).....				28.619
e Absolute Stack Pressure (Hg).....				30.071
f Stack Gas Velocity (ft/sec).....				
g Stack Flow Rate (acfm).....				
h ₁ Stack Flow Rate (dscfm).....				
h ₂ Stack Flow Rate (wscfm).....				
i Isokinetic Ratio (%).....				98.2

TOTAL AND HEXAVALENT CHROMIUM
EMISSIONS SUMMARY
Schnitzer Steel
Steel Shredder

REFERENCE TEMP (F):			70			TEST METHOD:			CARB 425		
DETECTION LIMIT:			0.02 ug/L for Total Cr			ANALYTICAL			IC/PCR for Cr(VI);		
			4.0 ug/L for Cr (VI)			METHOD:			IC/PMS for Total Cr		
						LABORATORY:			Curtis & Tompkins		

Test No.	Fractions		Results								lb/hr	lb/ton
	ug/sample	Blank, ug	ug/train	O ₂ , %	CO ₂ , %	H ₂ O, %	Vmstd, dscf	Qsd, dscfm	ug/m ³			

HEXAVALENT CHROMIUM																	
1-Cr-probe/impingers	[REDACTED]	[REDACTED]	[REDACTED]	20.89	0.04	2.10	[REDACTED]	[REDACTED]	[REDACTED]	7.94E-06							
1-Cr-impingers				20.89	0.04	2.10					1.39E-05						
											2.18E-05		[REDACTED]				
2-Cr-probe/impingers				21.03	0.03	2.00					7.24E-06						
2-Cr-impingers				21.03	0.03	2.00					6.62E-06						
											1.39E-05		[REDACTED]				
3-Cr-probe/impingers				21.07	0.03	2.10					4.87E-06						
3-Cr-impingers				21.07	0.03	2.10					5.59E-06						
											1.05E-05		[REDACTED]				
FB-Cr-probe/impingers				ND<						21.00	0.03	2.07			ND<	1.17E-05	ND<
FB-Cr-impingers										21.00	0.03	2.07				3.62E-06	
Method Blank				ND<												1.54E-05	
AVERAGE (Total):											1.54E-05	[REDACTED]					

Per CARB 425 Non-detects are not included in the calculations

CALCULATIONS:

ug/m³ = ug/train * 35.31/Vmstd

lb/hr = ug/train * lb/454*10⁶ ug * Qsd/Vmstd * 60 min/hr

TOTAL AND HEXAVALENT CHROMIUM
EMISSIONS SUMMARY
Schnitzer Steel
Steel Shredder

Test No.:	1-Cr	2-Cr	3-Cr	Average	FB-Cr
Date:	10/29/18	10/29/18	10/30/18	--	10/29/18
Time:	2250, 2000-2109 2331-0024 0045-0157			--	
Flow Rate, dscfm					--
Sample Volume, dscf	35.08	35.81	35.96	35.62	--
Temperature, °F	66.7	64.7	65.3	65.5	--
O ₂ , % volume dry	20.9	21.0	21.1	21.0	--
CO ₂ , % volume dry	0.04	0.03	0.03	0.03	--
Moisture Content, %	2.1	2.0	2.1	2.1	--
Hexavalent Chromium, Cr ⁶⁺					
ug/m3					
lb/hr	2.2E-05	1.4E-05	1.0E-05	1.5E-05	1.5E-05
lb/ton					

Note: Results have not been blank corrected.

< Species not detected at or below the detection limit.

TOTAL AND HEXAVALENT CHROMIUM (BLANK CORRECTED)**EMISSIONS SUMMARY****Schnitzer Steel****Steel Shredder**

REFERENCE TEMP (F):				70				TEST METHOD:				CARB 425				
DETECTION LIMIT:				0.02 ug/L for Total Cr				ANALYTICAL				IC/PCR for Cr(VI);				
				4.0 ug/L for Cr (VI)				METHOD:				IC/PMS for Total Cr;				
								LABORATORY:				Curtis & Tompkins				
				Results												
Test No.	ug/L	L/sample	Blank, ug	ug/train	O ₂ , %	CO ₂ , %	H ₂ O, %	Vmstd, dscf	Qsd, dscfm	ug/m ³		lb/hr	lb/ton			
<u>HEXAVALENT CHROMIUM</u>																
1-Cr-probe/impingers	ND<	[REDACTED]	[REDACTED]		20.89	0.04	3.16	[REDACTED]								
1-Cr-impingers					20.89	0.04	3.16									
2-Cr-probe/impingers					21.03	0.03	2.46	[REDACTED]								
2-Cr-impingers					21.03	0.03	2.46		<		< 4.60E-06	<				
3-Cr-probe/impingers					21.07	0.03	2.49	[REDACTED]								
3-Cr-impingers					21.07	0.03	2.49		<		< 3.91E-06	<				
FB-Cr-probe/impingers					21.00	0.03	2.70	[REDACTED]								
FB-Cr-impingers					21.00	0.03	2.70									
Method Blank																
AVERAGE (Total):										<		< 4.92E-06	<			

Per CARB 425 Non-detects are not included in the calculations

CALCULATIONS:

ug/m³ = ug/train * 35.31/Vmstdlb/hr = ug/train * lb/454*10⁶ ug * Qsd/Vmstd * 60 min/hr

TOTAL AND HEXAVALENT CHROMIUM (BLANK CORRECTED)
EMISSIONS SUMMARY
Schnitzer Steel
Steel Shredder

Test No.:	1-Cr	2-Cr	3-Cr	Average
Date:	10/29/18	10/29/18	10/30/18	--
Time:	2250, 2000-2109 2331-0024 0045-0157			--
Flow Rate, dscfm				
Sample Volume, dscf	35.08	35.81	35.96	35.62
Temperature, °F	66.7	64.7	65.3	65.5
O ₂ , % volume dry	20.9	21.0	21.1	21.0
CO ₂ , % volume dry	0.04	0.03	0.03	0.03
Moisture Content, %	3.2	2.5	2.5	2.7
Hexavalent Chromium, Cr ⁶⁺				
ug/m3				
lb/hr	6.2E-06	< 4.6E-06	< 3.9E-06	< 4.9E-06
lb/ton				

Note: Results have been blank corrected.

< Species not detected at or below the detection limit.

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel	*	Test Number.....	4-Cr
Unit / Location.....	Steel Shredder	*	Date.....	10/30/18
Test Method.....	CARB 425	*	Start / Stop Time.....	2114-2224
Meter Box Number.....	CB-22	*	Barometric Press (in Hg).....	30.09
Meter Calibration (Yd).....	0.9890	*	Meter Volume (acf).....	35.935
Stack Area (square feet).....		*	Liquid Volume (ml).....	23.0
Reference Temperature (°F)....	70	*	Meter Temperature (°F).....	62.6
Sample Time (Minutes).....	60	*	Meter Pressure (iwg).....	1.193
Pitot Coefficient	0.8400	*	Velocity Head (iwg).....	1.6923
Nozzle Diameter (in).....	0.160	*	Static Pressure (iwg).....	-0.61
Process Feed, tph.....		*	Stack Temperature (°F).....	69.5
Fuel "HHV" (Btu/scf).....	N/A	*	Stack O ₂ (%).....	21.1
Fuel "F" Factor (dscf/MMBtu)	N/A	*	Stack CO ₂ (%).....	0.0
a Standard Sample Volume (dscf).....				36.36
b Water Vapor Volume (scf).....				1.089
Moisture Fraction (nondimensional).....				0.0291
Theoretical maximum moisture fraction, nondimensional.....				0.0240
c Calculated Moisture Fraction (nondimensional).....				0.0240
d ₁ Stack Gas Molecular Weight (dry).....				28.844
d ₂ Stack Gas Molecular Weight (wet).....				28.584
e Absolute Stack Pressure (in Hg).....				30.045
f Stack Gas Velocity (ft/sec).....				
g Stack Flow Rate (acfm).....				
h ₁ Stack Flow Rate (dscfm).....				
h ₂ Stack Flow Rate (wscfm).....				
i Isokinetic Ratio (%).....				100.7

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel	*	Test Number.....	5-Cr
Unit / Location.....	Steel Shredder	*	Date.....	10/30/18
Test Method.....	CARB 425	*	Start / Stop Time.....	2028-2146
Meter Box Number.....	CB-22	*	Barometric Press (in Hg).....	30.09
Meter Calibration (Yd).....	0.9890	*	Meter Volume (acf).....	35.503
Stack Area (square feet).....	████	*	Liquid Volume (ml).....	18.1
Reference Temperature (°F)....	70	*	Meter Temperature (°F).....	67.1
Sample Time (Minutes).....	60	*	Meter Pressure (iwg).....	1.161
Pitot Coefficient	0.8400	*	Velocity Head (iwg).....	1.6440
Nozzle Diameter (in).....	0.160	*	Static Pressure (iwg).....	-0.61
Process Feed, tph.....	████	*	Stack Temperature (°F).....	68.8
Fuel "HHV" (Btu/scf).....	N/A	*	Stack O ₂ (%).....	20.7
Fuel "F" Factor (dscf/MMBtu)	N/A	*	Stack CO ₂ (%).....	0.0
a Standard Sample Volume (dscf).....				35.61
b Water Vapor Volume (scf).....				0.857
Moisture Fraction (nondimensional).....				0.0235
Theoretical maximum moisture fraction, nondimensional.....				0.0230
c Calculated Moisture Fraction (nondimensional).....				0.0230
d ₁ Stack Gas Molecular Weight (dry).....				28.836
d ₂ Stack Gas Molecular Weight (wet).....				28.586
e Absolute Stack Pressure (Hg).....				30.045
f Stack Gas Velocity (ft/sec).....				████
g Stack Flow Rate (acfm).....				████
h ₁ Stack Flow Rate (dscfm).....				████
h ₂ Stack Flow Rate (wscfm).....				████
i Isokinetic Ratio (%).....				99.9

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel	*	Test Number.....	6-Cr
Unit / Location.....	Steel Shredder	*	Date.....	10/31/18
Test Method.....	CARB 425	*	Start / Stop Time.....	0020-0120, 0153-0208
Meter Box Number.....	CB-22	*	Barometric Press (in Hg).....	30.09
Meter Calibration (Yd).....	0.9890	*	Meter Volume (acf).....	36.499
Stack Area (square feet).....		*	Liquid Volume (ml).....	21.6
Reference Temperature (°F)....	70	*	Meter Temperature (°F).....	66.6
Sample Time (Minutes).....	60	*	Meter Pressure (iwg).....	1.172
Pitot Coefficient	0.8400	*	Velocity Head (iwg).....	1.6614
Nozzle Diameter (in).....	0.160	*	Static Pressure (iwg).....	-0.61
Process Feed, tph.....		*	Stack Temperature (°F).....	69.6
Fuel "HHV" (Btu/scf).....	N/A	*	Stack O ₂ (%).....	21.0
Fuel "F" Factor (dscf/MMBtu)	N/A	*	Stack CO ₂ (%).....	0.0
a Standard Sample Volume (dscf).....				36.65
b Water Vapor Volume (scf).....				1.022
Moisture Fraction (nondimensional).....				0.0271
Theoretical maximum moisture fraction, nondimensional.....				0.0240
c Calculated Moisture Fraction (nondimensional).....				0.0240
d ₁ Stack Gas Molecular Weight (dry).....				28.845
d ₂ Stack Gas Molecular Weight (wet).....				28.584
e Absolute Stack Pressure (Hg).....				30.045
f Stack Gas Velocity (ft/sec).....				
g Stack Flow Rate (acfm).....				
h ₁ Stack Flow Rate (dscfm).....				
h ₂ Stack Flow Rate (wscfm).....				
i Isokinetic Ratio (%).....				102.4

TOTAL AND HEXAVALENT CHROMIUM
EMISSIONS SUMMARY
Schnitzer Steel
Steel Shredder

REFERENCE TEMP (F):			70			TEST METHOD:			CARB 425		
DETECTION LIMIT:			0.02 ug/L for Total Cr 4.0 ug/L for Cr (VI)			ANALYTICAL METHOD:			IC/PCR for Cr(VI); IC/PMS for Total Cr		
						LABORATORY:			Curtis & Tompkins		

Test No.	Fractions		Results									
	ug/sample	Blank, ug	ug/train	O ₂ , %	CO ₂ , %	H ₂ O, %	Vmstd, dscf	Qsd, dscfm	ug/m ³	lb/hr	lb/ton	

HEXAVALENT CHROMIUM																		
1-Cr-probe/impingers	[REDACTED]	[REDACTED]	[REDACTED]	21.06	0.01	2.40	[REDACTED]	[REDACTED]	[REDACTED]	5.15E-06	[REDACTED]							
1-Cr-impingers				21.06	0.01	2.40				6.15E-06								
										1.13E-05		[REDACTED]						
2-Cr-probe/impingers				20.72	0.04	2.30				[REDACTED]		5.29E-06	[REDACTED]					
2-Cr-impingers				20.72	0.04	2.30				[REDACTED]		7.06E-06	[REDACTED]					
												1.24E-05	[REDACTED]					
3-Cr-probe/impingers				21.01	0.03	2.40				[REDACTED]		5.75E-06	[REDACTED]					
3-Cr-impingers				21.01	0.03	2.40				[REDACTED]		4.77E-06	[REDACTED]					
												1.05E-05	[REDACTED]					
FB-Cr-probe/impingers				ND<	[REDACTED]	[REDACTED]				20.93		0.03	2.37	[REDACTED]	ND<	1.13E-05	ND<	[REDACTED]
FB-Cr-impingers				[REDACTED]	[REDACTED]	[REDACTED]				20.93		0.03	2.37	[REDACTED]		3.49E-06		[REDACTED]
Method Blank				ND<	[REDACTED]	[REDACTED]								[REDACTED]		1.48E-05		[REDACTED]
AVERAGE (Total):										[REDACTED]		1.14E-05	[REDACTED]					

Per CARB 425 Non-detects are not included in the calculations

CALCULATIONS:

ug/m³ = ug/train * 35.31/Vmstd

lb/hr = ug/train * lb/454*10⁶ ug * Qsd/Vmstd * 60 min/hr

TOTAL AND HEXAVALENT CHROMIUM
EMISSIONS SUMMARY
Schnitzer Steel
Steel Shredder

Test No.:	4-Cr	5-Cr	6-Cr	Average	FB-Cr
Date:	10/30/18	10/30/18	10/31/18	--	10/29/18
Time:	2114-2224	2028-2146	120, 015	--	
Flow Rate, dscfm					--
Sample Volume, dscf	36.36	35.61	36.65	36.20	--
Temperature, °F	69.5	68.8	69.6	69.3	--
O₂, % volume dry	21.1	20.7	21.0	20.9	--
CO₂, % volume dry	0.01	0.04	0.03	0.03	--
Moisture Content, %	2.4	2.3	2.4	2.4	--
Hexavalent Chromium, Cr⁶⁺					
ug/m3					
lb/hr	1.1E-05	1.2E-05	1.1E-05	1.1E-05	1.5E-05
lb/ton					

Note: Results have not been blank corrected.

< Species not detected at or below the detection limit.

TOTAL AND HEXAVALENT CHROMIUM (BLANK CORRECTED)**EMISSIONS SUMMARY****Schnitzer Steel****Steel Shredder**

REFERENCE TEMP (F):				70				TEST METHOD:				CARB 425			
DETECTION LIMIT:				0.02 ug/L for Total Cr				ANALYTICAL				IC/PCR for Cr(VI);			
				4.0 ug/L for Cr (VI)				METHOD:				IC/PMS for Total Cr			
								LABORATORY:				Curtis & Tompkins			
				Results											
Test	ug/	L/	Blank,	ug/	O ₂ ,	CO ₂ ,	H ₂ O,	Vmstd,	Qsd,	ug/m ³		lb/hr		lb/ton	
No.	L	sample	ug	train	%	%	%	dscf	dscfm						
<u>HEXAVALENT CHROMIUM</u>															
1-Cr-probe/impingers					21.06	0.01	2.91								
1-Cr-impingers					21.06	0.01	2.91								
											<	3.85E-06	<		
2-Cr-probe/impingers					20.72	0.04	2.35								
2-Cr-impingers					20.72	0.04	2.35								
											<	3.75E-06	<		
3-Cr-probe/impingers					21.01	0.03	2.71								
3-Cr-impingers					21.01	0.03	2.71								
											<	4.01E-06	<		
FB-Cr-probe/impingers					20.93	0.03	2.66								
FB-Cr-impingers					20.93	0.03	2.66								
Method Blank												1.48E-05			
AVERAGE (Total):										<		<	3.87E-06	<	

Per CARB 425 Non-detects are not included in the calculations

CALCULATIONS:

ug/m³ = ug/train * 35.31/Vmstdlb/hr = ug/train * lb/454*10⁶ ug * Qsd/Vmstd * 60 min/hr

OTAL AND HEXAVALENT CHROMIUM (BLANK CORRECTED)
EMISSIONS SUMMARY
Schnitzer Steel
Steel Shredder

Test No.:	4-Cr	5-Cr	6-Cr	Average
Date:	10/30/18	10/30/18	10/31/18	--
Time:	2114-2224	2028-2146	120, 015	--
Flow Rate, dscfm	████████	████████	████████	████████
Sample Volume, dscf	36.36	35.61	36.65	36.20
Temperature, °F	69.5	68.8	69.6	69.3
O₂, % volume dry	21.1	20.7	21.0	20.9
CO₂, % volume dry	0.01	0.04	0.03	0.03
Moisture Content, %	2.9	2.3	2.7	2.7
Hexavalent Chromium, Cr⁶⁺				
ug/m3	████████	████████	████████	████████
lb/hr	< 3.9E-06	< 3.7E-06	< 4.0E-06	< 3.9E-06
lb/ton	██			

Note: Results have been blank corrected.

< Species not detected at or below the detection limit.

Appendix A.2 Benzene Spreadsheets

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel
Unit / Location.....	Shredder
Stack area, square feet.....	██████
Reference temperature, °F.....	70

Test number.....	1-TO15	2-TO15	3-TO15	Average
Date.....	10/29/18	10/29/18	10/30/18	--
Start / Stop time.....	2000-2100	2235-2251,2331-0014	0045-0145	--

Feed Rate, tons/hour.....	████	████	████	████
---------------------------	------	------	------	------

SAMPLE TRAIN DATA

Meter box number/ID.....	CB-22	CB-22	CB-22	--
Sample time, minutes.....	60.0	60.0	60.0	60.0
Pitot coefficient	0.84	0.84	0.84	0.84
Meter calibration, Yd.....	0.989	0.989	0.989	0.989
Barometric pressure, in Hg.....	30.12	30.12	30.12	30.12
Meter box volume, acf.....	34.613	35.276	35.639	35.176
Impinger liquid volume, ml.....	24.2	19.1	19.4	20.9
Meter temperature, °F.....	62.1	61.3	64.4	62.6
Meter pressure, (Delta H) iwg.....	1.16	1.18	1.17	1.17
Velocity head, (Delta P) iwg.....	1.702	1.726	1.719	1.715
Static pressure, iwg.....	-0.71	-0.67	-0.66	-0.68
Stack temperature, °F.....	66.7	64.7	65.3	65.5

ANALYZER DATA

O ₂ % volume dry.....	20.9	21.0	21.1	21.0
CO ₂ % volume dry.....	0.04	0.03	0.03	0.03

VOLUMETRIC FLOW RATE

Standard sample volume, dscf.....	35.082	35.810	35.964	35.619
Water vapor volume, scf.....	1.145	0.904	0.918	0.9892
Measured moisture fraction, nondimensional...	0.032	0.025	0.025	0.027
Theoretical maximum moisture fraction, nondir	0.021	0.020	0.021	0.021
Calculated Moisture Fraction (nondimensional)	0.021	0.020	0.021	0.021
Moisture fraction %.....	2.1%	2.0%	2.1%	2.1%
Stack gas molecular weight, dry.....	28.841	28.845	28.847	28.845
Stack gas molecular weight, wet.....	28.614	28.628	28.619	28.620
Absolute stack pressure, in Hg.....	30.068	30.071	30.071	30.070
Stack gas velocity, ft/sec.....	████	████	████	████
Stack flow rate, acfm.....	████	████	████	████
Stack flow rate, wscfm.....	████	████	████	████
Stack flow rate, dscfm - from CR runs.....	████	████	████	████

Emissions Results

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel
Unit / Location.....	Shredder
Stack area, square feet.....	██████
Reference temperature, °F.....	70

Test number.....	1-TO15	2-TO15	3-TO15	Average
Date.....	10/29/18	10/29/18	10/30/18	--
Start / Stop time.....	2000-2100	2235-2251,2331-0014	0045-0145	--

Benzene

ppm.....	████	████	████	████
lb/hr.....	N/A	0.037	0.048	0.043
lb/ton.....	████	██████	██████	██████

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel
Unit / Location.....	Shredder
Stack area, square feet.....	██████████
Reference temperature, °F.....	70

Test number.....	4-TO15	5-TO15	6-TO15	Average
Date.....	10/30/18	10/30/18	10/31/18	--
Start / Stop time.....	2114-2214	2253-2353	0020-0120	--

Feed Rate, tons/hour.....	████	████	████	████
---------------------------	------	------	------	------

SAMPLE TRAIN DATA

Meter box number/ID.....	CB-22	CB-22	CB-22	--
Sample time, minutes.....	60.0	60.0	60.0	60.0
Pitot coefficient	0.84	0.84	0.84	0.84
Meter calibration, Yd.....	0.989	0.989	0.989	0.989
Barometric pressure, in Hg.....	30.09	30.09	30.09	30.09
Meter box volume, acf.....	35.935	35.503	36.499	35.979
Impinger liquid volume, ml.....	23.0	18.1	21.6	20.9
Meter temperature, °F.....	62.6	67.1	66.6	65.4
Meter pressure, (Delta H) iwg.....	1.19	1.16	1.17	1.18
Velocity head, (Delta P) iwg.....	1.692	1.644	1.661	1.666
Static pressure, iwg.....	-0.61	-0.61	-0.61	-0.61
Stack temperature, °F.....	69.5	68.8	69.6	69.3

ANALYZER DATA

O ₂ % volume dry.....	21.1	20.7	21.0	20.9
CO ₂ % volume dry.....	0.01	0.04	0.03	0.03

VOLUMETRIC FLOW RATE

Standard sample volume, dscf.....	36.357	35.607	36.645	36.203
Water vapor volume, scf.....	1.089	0.857	1.022	0.9892
Measured moisture fraction, nondimensional...	0.029	0.023	0.027	0.027
Theoretical maximum moisture fraction, nondir	0.024	0.023	0.024	0.024
Calculated Moisture Fraction (nondimensional)	0.024	0.023	0.024	0.024
Moisture fraction %.....	2.4%	2.3%	2.4%	2.4%
Stack gas molecular weight, dry.....	28.844	28.836	28.845	28.841
Stack gas molecular weight, wet.....	28.584	28.586	28.584	28.585
Absolute stack pressure, in Hg.....	30.045	30.045	30.045	30.045
Stack gas velocity, ft/sec.....	████	████	████	████
Stack flow rate, acfm.....	████	████	████	████
Stack flow rate, wscfm.....	████	████	████	████
Stack flow rate, dscfm - from CR runs.....	████	████	████	████

Emissions Results

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel
Unit / Location.....	Shredder
Stack area, square feet.....	██████████
Reference temperature, °F.....	70

Test number.....	4-TO15	5-TO15	6-TO15	Average
Date.....	10/30/18	10/30/18	10/31/18	--
Start / Stop time.....	2114-2214	2253-2353	0020-0120	--

Benzene						
ppm.....	██████████	██████████	█	██████████	█	██████████
lb/hr.....	1.4E-02	5.1E-03	<	3.5E-03	<	7.5E-03
lb/ton.....	██████████	██████████	█	██████████	█	██████████

Appendix A.3

Total Organic Carbon Spreadsheets

SOURCE TEST DATA SUMMARY				
Client.....	Schnitzer Steel			
Unit / Location.....	Shredder			
Stack area, square feet.....	70			
Reference temperature, °F.....	70			
Test number.....	1-TO15	2-TO15	3-TO15	Average
Date.....	10/29/18	10/29/18	10/30/18	--
Start / Stop time.....	2000-2100	2235-2251,2331-0014	0045-0145	--
Feed Rate, tons/hour.....				
SAMPLE TRAIN DATA				
Meter box number/ID.....	CB-22	CB-22	CB-22	--
Nozzle diameter, inches.....	0.160	0.160	0.160	0.160
Sample time, minutes.....	60.0	60.0	60.0	60.0
Pitot coefficient	0.84	0.84	0.84	0.84
Meter calibration, Yd.....	0.989	0.989	0.989	0.989
Barometric pressure, in Hg.....	30.12	30.12	30.12	30.12
Meter box volume, acf.....	34.613	35.276	35.639	35.176
Impinger liquid volume, ml.....	24.2	19.1	19.4	20.9
Meter temperature, °F.....	62.1	61.3	64.4	62.6
Meter pressure, (Delta H) iwg.....	1.16	1.18	1.17	1.17
Velocity head, (Delta P) iwg.....	1.702	1.726	1.719	1.715
Static pressure, iwg.....	-0.71	-0.67	-0.66	-0.68
Stack temperature, °F.....	66.7	64.7	65.3	65.5
ANALYZER DATA				
O ₂ % volume dry.....	20.9	21.0	21.1	21.0
CO ₂ % volume dry.....	0.04	0.03	0.03	0.03
THC, ppmv wet as Propane.....				
SUMMA CANISTER DATA				
M25C:TNMOC, ppmvd as C.....				
TO-12M: TNMNEOC, ppmvd as C.....				
Methane, ppmvd as C.....				
Ethane, ppmvd.....				
VOLUMETRIC FLOW RATE				
Standard sample volume, dscf.....	35.082	35.810	35.964	35.619
Water vapor volume, scf.....	1.145	0.904	0.918	0.9892
Measured moisture fraction, nondimensional.....	0.032	0.025	0.025	0.027
Theoretical maximum moisture fraction, nondimen.....	0.021	0.020	0.021	0.021
Calculated Moisture Fraction (nondimensional).....	0.021	0.020	0.021	0.021
Moisture fraction %.....	2.1%	2.0%	2.1%	2.1%
Stack gas molecular weight, dry.....	28.841	28.845	28.847	28.845
Stack gas molecular weight, wet.....	28.614	28.628	28.619	28.620
Absolute stack pressure, in Hg.....	30.068	30.071	30.071	30.070
Stack gas velocity, ft/sec.....				
Stack flow rate, acfm.....				
Stack flow rate, wscfm.....				
Stack flow rate, dscfm - from CR runs.....				

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel			
Unit / Location.....	Shredder			
Stack area, square feet.....	70			
Reference temperature, °F.....	70			

Test number.....	1-TO15	2-TO15	3-TO15	Average
Date.....	10/29/18	10/29/18	10/30/18	--
Start / Stop time.....	2000-2100	2235-2251,2331-0014	0045-0145	--

Emissions Results

M25A: POC

ppmvd as CH4.....	█	█	█	█
lb/hr.....	186	212	154	184
lb/ton.....	█	█	█	█

M25A: NMOC

ppmvd as CH4.....	█	█	█	█
lb/hr.....	N/A	212	154	183
lb/ton.....	█	█	█	█

M25A: NMNEOC

ppmvd as CH4.....	█	█	█	█
lb/hr.....	N/A	212	154	183
lb/ton.....	█	█	█	█

M25C: NMOC

ppmvd as CH4.....	█	█	█	█
lb/hr.....	N/A	5.40	7.68	6.54
lb/ton.....	█	█	█	█

M25C: NMNEOC

ppmvd as CH4.....	█	█	█	█
lb/hr.....	N/A	5.40	7.67	6.53
lb/ton.....	█	█	█	█

TO-12: NMNEOC

ppmvd as CH4.....	█	█	█	█
lb/hr.....	N/A	4.22	6.77	5.50
lb/ton.....	█	█	█	█

SOURCE TEST DATA SUMMARY				
Client.....	Schnitzer Steel			
Unit / Location.....	Shredder			
Stack area, square feet.....	██████████			
Reference temperature, °F.....	70			
Test number.....	4-VOC	5-VOC	6-VOC	Average
Date.....	10/30/18	10/30/18	10/31/18	--
Start / Stop time.....	2114-2214	2253-2353	0020-0120	--
Feed Rate, tons/hour.....	████	████	████	████
<u>SAMPLE TRAIN DATA</u>				
Meter box number/ID.....	CB-22	CB-22	CB-22	--
Sample time, minutes.....	60.0	60.0	60.0	60.0
Pitot coefficient	0.84	0.84	0.84	0.84
Meter calibration, Yd.....	0.989	0.989	0.989	0.989
Barometric pressure, in Hg.....	30.09	30.09	30.09	30.09
Meter box volume, acf.....	35.935	35.503	36.499	35.979
Impinger liquid volume, ml.....	23.0	18.1	21.6	20.9
Meter temperature, °F.....	62.6	67.1	66.6	65.4
Meter pressure, (Delta H) iwg.....	1.19	1.16	1.17	1.18
Velocity head, (Delta P) iwg.....	1.692	1.644	1.661	1.666
Static pressure, iwg.....	-0.61	-0.61	-0.61	-0.61
Stack temperature, °F.....	69.5	68.8	69.6	69.3
<u>ANALYZER DATA</u>				
O ₂ , % volume dry.....	21.1	20.7	21.0	20.9
CO ₂ , % volume dry.....	0.01	0.04	0.03	0.03
THC, ppmv wet as Propane.....	████	████	████	████
<u>SUMMA CANISTER DATA</u>				
M25C:TNMOC, ppmvd as C.....	████	████	████	████
TO-12M: TNMNEOC, ppmvd as C.....	████	████	████	████
Methane, ppmvd as C..... <	████	████	████	████
Ethane, ppmvd.....	████	████	████	████
<u>VOLUMETRIC FLOW RATE</u>				
Standard sample volume, dscf.....	36.357	35.607	36.645	36.203
Water vapor volume, scf.....	1.089	0.857	1.022	0.9892
Measured moisture fraction, nondimensional..	0.029	0.023	0.027	0.027
Theoretical maximum moisture fraction, nondir	0.024	0.023	0.024	0.024
Calculated Moisture Fraction (nondimensional)	0.024	0.023	0.024	0.024
Moisture fraction %.....	2.4%	2.3%	2.4%	2.4%
Stack gas molecular weight, dry.....	28.844	28.836	28.845	28.841
Stack gas molecular weight, wet.....	28.584	28.586	28.584	28.585
Absolute stack pressure, in Hg.....	30.045	30.045	30.045	30.045
Stack gas velocity, ft/sec.....	████	████	████	████
Stack flow rate, acfm.....	████	████	████	████
Stack flow rate, wscfm.....	████	████	████	████
Stack flow rate, dscfm - from CR runs.....	████	████	████	████

SOURCE TEST DATA SUMMARY

Client.....	Schnitzer Steel
Unit / Location.....	Shredder
Stack area, square feet.....	70
Reference temperature, °F.....	70

Test number.....	4-VOC	5-VOC	6-VOC	Average
Date.....	10/30/18	10/30/18	10/31/18	--
Start / Stop time.....	2114-2214	2253-2353	0020-0120	--

Emissions Results

M25A: POC

ppmvd as CH4.....	81	84	93	86
lb/hr.....				
lb/ton.....				

M25A: NMOC

ppmvd as CH4.....	81	84	93	86
lb/hr.....				
lb/ton.....				

M25A: NMNEOC

ppmvd as CH4.....	81	84	93	86
lb/hr.....				
lb/ton.....				

M25C: NMOC

ppmvd as CH4.....					
lb/hr.....	14.55	8.01	<	2.17	<
lb/ton.....					

M25C: NMNEOC

ppmvd as CH4.....					
lb/hr.....	14.5	7.98	<	2.15	<
lb/ton.....					

TO-12: NMNEOC

ppmvd as CH4.....				
lb/hr.....	7.15	2.66	1.24	3.69
lb/ton.....				

Appendix A.4

PolyChlorinated Biphenyl Spreadsheets

SOURCE TEST DATA SUMMARY					
Client.....	Schnitzer Steel				
Unit / Location.....	Shredder				
Stack area, square feet.....	[REDACTED]				
Regulation District.....	Bay Area				
Reference temperature, °F.....	70				
Test number.....	Method Blank	1-PCB	2-PCB	3-PCB	Average
Date.....	--	10/29/18	10/29/18	10/30/18	--
Start / Stop time.....	--	2000-2108	2235-2250,2331-0023	0045-0158	--
Feed Rate, tons/hour ¹	--	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
SAMPLE TRAIN DATA					
Meter box number/ID.....	--	CB-14	CB-14	CB-14	--
Nozzle diameter, inches.....	--	0.160	0.160	0.160	0.160
Sample time, minutes.....	--	60.0	60.0	60.0	60.0
Pitot coefficient	--	0.84	0.84	0.84	0.8400
Meter calibration, Yd.....	--	1.0140	1.0140	1.0140	1.0140
Barometric pressure, in Hg.....	--	30.12	30.12	30.12	30.12
Meter box volume, acf.....	--	34.193	27.873	30.880	30.982
Impinger liquid volume, mL.....	--	12.9	14.2	7.8	11.63
Meter temperature, °F.....	--	57.5	56.5	55.9	56.6
Meter pressure, (Delta H) iwg.....	--	1.16	0.78	0.98	0.975
Velocity head, (Delta P) iwg.....	--	1.710	1.144	1.418	1.4243
Static pressure, iwg.....	--	-0.73	-0.67	-0.66	-0.69
Stack temperature, °F.....	--	66.0	62.8	62.7	63.8
ANALYZER DATA					
O ₂ % volume dry.....	--	20.9	21.0	21.1	21.0
CO ₂ % volume dry.....	--	0.04	0.03	0.03	0.03
VOLUMETRIC FLOW RATE					
1a Standard sample volume, dscf.....	--	35.852	29.252	32.460	32.521
1b Water vapor volume, scf.....	--	0.611	0.672	0.369	0.5506
Measured Moisture fraction, nondimensional.....	--	0.017	0.022	0.011	0.0168
Theoretical maximum moisture fraction, nondimensional.....	--	0.021	0.019	0.019	0.0197
1c Calculated Moisture Fraction (nondimensional).....	--	0.017	0.019	0.011	0.0157
Moisture fraction %.....	--	1.7%	1.9%	1.1%	1.6%
1d Stack gas molecular weight, dry.....	--	28.841	28.845	28.847	28.845
1e Stack gas molecular weight, wet.....	--	28.660	28.639	28.725	28.675
1f Absolute stack pressure, in Hg.....	--	30.066	30.071	30.071	30.070
1g Stack gas velocity, ft/sec.....	--	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
1h Stack flow rate, acfm.....	--	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
1i Stack Flow Rate (wscfm).....	--	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
1j Stack flow rate - based on pitot, dscfm.....	--	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Stack flow rate - based on pitot, dscfm (Runs 5 & 6 from Cr Tests).....	--	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Isokinetic Ratio (%).....	--	97.8	97.5	96.5	97.3
LAB RESULTS					
Chlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Dichlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Trichlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Tetrachlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Pentachlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Hexachlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Heptachlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Octachlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Nonachlorobiphenyls, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Decachlorobiphenyl, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
Total PCBs, ng.....	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

SOURCE TEST DATA SUMMARY					
Client.....	Schnitzer Steel				
Unit / Location.....	Shredder				
Stack area, square feet.....	■				
Regulation District.....	Bay Area				
Reference temperature, °F.....	70				
Test number.....	Method Blank	1-PCB	2-PCB	3-PCB	Average
Date.....	--	10/29/18	10/29/18	10/30/18	--
Start / Stop time.....	--	2000-2108	2235-2250,2331-0023	0045-0158	--
EMISSIONS					
Chlorobiphenyls, ng/m3.....	■	■	■	■	■
Chlorobiphenyls, lb/hr.....	< 6.97E-09	2.98E-05	1.69E-05	1.10E-05	1.92E-05
Chlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Dichlorobiphenyls, ng/m3.....	■	■	■	■	■
Dichlorobiphenyls, lb/hr.....	< 2.16E-08	3.23E-04	2.05E-04	1.72E-04	2.33E-04
Dichlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Trichlorobiphenyls, ng/m3.....	■	■	■	■	■
Trichlorobiphenyls, lb/hr.....	< 5.42E-09	6.18E-04	3.32E-04	2.31E-04	3.94E-04
Trichlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Tetrachlorobiphenyls, ng/m3.....	■	■	■	■	■
Tetrachlorobiphenyls, lb/hr.....	< 7.24E-09	1.48E-04	8.04E-05	7.69E-05	1.02E-04
Tetrachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Pentachlorobiphenyls, ng/m3.....	■	■	■	■	■
Pentachlorobiphenyls, lb/hr.....	< 1.18E-08	1.49E-05	9.39E-06	7.36E-06	1.05E-05
Pentachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Hexachlorobiphenyls, ng/m3.....	■	■	■	■	■
Hexachlorobiphenyls, lb/hr.....	< 8.58E-09	4.63E-06	1.98E-06	1.16E-06	2.59E-06
Hexachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Heptachlorobiphenyls, ng/m3.....	■	■	■	■	■
Heptachlorobiphenyls, lb/hr.....	< 3.89E-09	3.02E-06	6.75E-07	1.74E-07	1.29E-06
Heptachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Octachlorobiphenyls, ng/m3.....	■	■	■	■	■
Octachlorobiphenyls, lb/hr.....	< 5.74E-09	7.31E-07	7.61E-08	4.13E-08	2.83E-07
Octachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Nonachlorobiphenyls, ng/m3.....	■	■	■	■	■
Nonachlorobiphenyls, lb/hr.....	< 4.59E-09	< 1.76E-08	< 2.27E-08	< 1.26E-08	< 1.76E-08
Nonachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Decachlorobiphenyls, ng/m3.....	■	■	■	■	■
Decachlorobiphenyls, lb/hr.....	< 3.07E-09	< 1.69E-08	< 5.52E-09	< 6.37E-09	< 9.59E-09
Decachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Total PCBs, ng/m3.....	■	■	■	■	■
Total PCBs, lb/hr.....	< 2.16E-08	1.14E-03	6.44E-04	5.00E-04	7.63E-04
Total PCBs, lb/ton of material processed.....	■	■	■	■	■

SOURCE TEST DATA SUMMARY					
Client.....	Schnitzer Steel				
Unit / Location.....	Shredder				
Stack area, square feet.....					
Regulation District.....	Bay Area				
Reference temperature, °F.....	70				
Test number.....	Method Blank	4-PCB	5-PCB	6-PCB	Average
Date.....	--	10/30/18	10/30/18	10/31/18	--
Start / Stop time.....	--	2114-2224	2253-0002	0020-0117,0153-0208	--
Feed Rate, tons/hour ¹	--				
SAMPLE TRAIN DATA					
Meter box number/ID.....	--	CB-14	CB-14	CB-14	--
Nozzle diameter, inches.....	--	0.160	0.160	0.160	0.160
Sample time, minutes.....	--	60.0	60.0	60.0	60.0
Pitot coefficient	--	0.84	0.84	0.84	0.8400
Meter calibration, Yd.....	--	1.0140	1.0140	1.0140	1.0140
Barometric pressure, in Hg.....	--	30.09	30.09	30.09	30.09
Meter box volume, acf.....	--	34.019	34.121	35.220	34.453
Impinger liquid volume, mL.....	--	7.1	4.9	13.6	8.53
Meter temperature, °F.....	--	57.7	59.1	57.6	58.1
Meter pressure, (Delta H) iwg.....	--	1.19	1.21	1.23	1.208
Velocity head, (Delta P) iwg.....	--	1.693	1.717	1.742	1.7174
Static pressure, iwg.....	--	-0.61	-0.61	-0.61	-0.61
Stack temperature, °F.....	--	68.1	67.2	67.2	67.5
ANALYZER DATA					
O ₂ % volume dry.....	--	21.1	20.7	21.0	20.9
CO ₂ % volume dry.....	--	0.01	0.04	0.03	0.03
VOLUMETRIC FLOW RATE					
1a Standard sample volume, dscf.....	--	35.619	35.631	36.887	36.045
1b Water vapor volume, scf.....	--	0.336	0.232	0.644	0.4039
Measured Moisture fraction, nondimensional.....	--	0.009	0.006	0.017	0.0110
Theoretical maximum moisture fraction, nondimensional.....	--	0.023	0.022	0.022	0.0223
1c Calculated Moisture Fraction (nondimensional).....	--	0.009	0.006	0.017	0.011
Moisture fraction %.....	--	0.9%	0.6%	1.7%	1.1%
1d Stack gas molecular weight, dry.....	--	28.844	28.836	28.845	28.841
1e Stack gas molecular weight, wet.....	--	28.743	28.765	28.659	28.722
1f Absolute stack pressure, in Hg.....	--	30.045	30.045	30.045	30.045
1g Stack gas velocity, ft/sec.....	--				
1h Stack flow rate, acfm.....	--				
1i Stack Flow Rate (wscfm).....	--				
Stack flow rate - based on pitot, dscfm.....	--				
Isokinetic Ratio (%).....	--	97.3	96.3	99.9	97.9
LAB RESULTS					
Chlorobiphenyls, ng.....					
Dichlorobiphenyls, ng.....					
Trichlorobiphenyls, ng.....					
Tetrachlorobiphenyls, ng.....					
Pentachlorobiphenyls, ng.....					
Hexachlorobiphenyls, ng.....					
Heptachlorobiphenyls, ng.....					
Octachlorobiphenyls, ng.....					
Nonachlorobiphenyls, ng.....					
Decachlorobiphenyl, ng.....					
Total PCBs, ng.....					

SOURCE TEST DATA SUMMARY					
Client.....	Schnitzer Steel				
Unit / Location.....	Shredder				
Stack area, square feet.....	■				
Regulation District.....	Bay Area				
Reference temperature, °F.....	70				
Test number.....	Method Blank	4-PCB	5-PCB	6-PCB	Average
Date.....	--	10/30/18	10/30/18	10/31/18	--
Start / Stop time.....	--	2114-2224	2253-0002	0020-0117,0153-0208	--
EMISSIONS					
Chlorobiphenyls, ng/m3.....	■	■	■	■	■
Chlorobiphenyls, lb/hr.....	< 6.43E-09	1.32E-03	1.56E-03	2.23E-03	1.71E-03
Chlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Dichlorobiphenyls, ng/m3.....	■	■	■	■	■
Dichlorobiphenyls, lb/hr.....	< 1.99E-08	6.21E-03	8.42E-03	1.22E-02	8.96E-03
Dichlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Trichlorobiphenyls, ng/m3.....	■	■	■	■	■
Trichlorobiphenyls, lb/hr.....	< 5.01E-09	4.86E-03	8.21E-03	1.13E-02	8.12E-03
Trichlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Tetrachlorobiphenyls, ng/m3.....	■	■	■	■	■
Tetrachlorobiphenyls, lb/hr.....	< 6.69E-09	1.16E-03	2.08E-03	2.27E-03	1.84E-03
Tetrachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Pentachlorobiphenyls, ng/m3.....	■	■	■	■	■
Pentachlorobiphenyls, lb/hr.....	< 1.09E-08	3.50E-04	2.95E-04	1.67E-04	2.71E-04
Pentachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Hexachlorobiphenyls, ng/m3.....	■	■	■	■	■
Hexachlorobiphenyls, lb/hr.....	< 7.93E-09	1.30E-04	9.20E-05	3.10E-05	8.45E-05
Hexachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Heptachlorobiphenyls, ng/m3.....	■	■	■	■	■
Heptachlorobiphenyls, lb/hr.....	< 3.59E-09	1.54E-05	1.59E-05	5.85E-06	1.24E-05
Heptachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Octachlorobiphenyls, ng/m3.....	■	■	■	■	■
Octachlorobiphenyls, lb/hr.....	< 5.30E-09	1.63E-06	4.02E-06	1.98E-06	2.54E-06
Octachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Nonachlorobiphenyls, ng/m3.....	■	■	■	■	■
Nonachlorobiphenyls, lb/hr.....	< 4.24E-09	3.12E-07	1.17E-06	4.85E-07	6.54E-07
Nonachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Decachlorobiphenyls, ng/m3.....	■	■	■	■	■
Decachlorobiphenyls, lb/hr.....	< 2.84E-09	3.89E-08	1.31E-07	5.03E-08	7.33E-08
Decachlorobiphenyls, lb/ton of material processed.....	■	■	■	■	■
Total PCBs, ng/m3.....	■	■	■	■	■
Total PCBs, lb/hr.....	< 1.99E-08	1.41E-02	2.07E-02	2.82E-02	2.10E-02
Total PCBs, lb/ton of material processed.....	■	■	■	■	■

Appendix A.5 Example Calculations

EXAMPLE CALCULATIONS STACK GAS VOLUMETRIC FLOW RATE

Project name: Schnitzer Steel Project number: 452603
 Computed by: Katie Resch Calculation date: 12/18/18
 Run number: 4-Cr

SAMPLE TRAIN DATA

Meter calibration factor, Y_d	<u>0.989</u>	Y
Stack area, square feet		A_s
Pitot Coefficient	<u>0.84</u>	C_p
Barometric pressure, in Hg	<u>30.09</u>	P_{bar}
Meter box volume, acf	<u>35.935</u>	V_m
Impinger liquid volume, g	<u>23.0</u>	V_{lc}
Meter temperature, °R	<u>522.6</u>	$T_m = (°F \text{ plus } 460)$
Meter pressure, (delta H) iwg	<u>1.193</u>	ΔH
Velocity head, (delta P) iwg	<u>1.6923</u>	ΔP
Static pressure, iwg	<u>-0.61</u>	P_{sg}
Stack temperature, °R	<u>529.5</u>	$T_s = (°F \text{ plus } 460)$
Stack O ₂ , % volume dry	<u>21.1</u>	O ₂
Stack CO ₂ , % volume dry	<u>0</u>	CO ₂
Stack N ₂ , % volume dry	<u>78.9</u>	$N_2 = (100 - \% O_2 - \% CO_2)$
Nozzle area, square feet	<u>—</u>	$A_n = \pi \left(\frac{D_n}{2} \right)^2 \left(\frac{1 \text{ ft}}{12 \text{ in}} \right)^2$
PM sampling time, minutes	<u>60</u>	Θ
Reference temperature, °R	<u>530</u>	$T_{std} (°F \text{ plus } 460)$

Note: The results calculated in the pages that follow may differ slightly from the results presented in the final report. This difference can be attributed to "significant digit round-off errors" common when comparing computer spreadsheets results with those derived from using a calculator.

1. VOLUMETRIC FLOW RATE

a. Standard sample gas volume, dscf

$$V_{m\ std} = (V_m)(Y) \frac{(T_{std}) \left[P_{bar} + \left(\frac{\Delta H}{13.6} \right) \right]}{(T_m)(P_{std})}$$

$$V_{m\ std} = (35.935)(0.989) \frac{(530) \left[30.09 + \left(\frac{1.193}{13.6} \right) \right]}{(522.6)(29.92)}$$

$$V_{m\ std} = \underline{36.353} \text{ dscf}$$

b. Water vapor volume, scf

$$V_{w\ std} = (0.04715)(V_{lc}) \left(\frac{T_{std}}{528} \right)$$

$$V_{w\ std} = (0.04715)(23.0) \left(\frac{530}{528} \right)$$

$$V_{w\ std} = \underline{1.089} \text{ scf}$$

c. Moisture content, non-dimensional

$$B_{ws} = \left(\frac{V_{w\ std}}{V_{m\ std} + V_{w\ std}} \right)$$

$$B_{ws} = \left(\frac{1.089}{36.353 + 1.089} \right)$$

$$B_{ws} = \underline{0.0291} \text{ moisture content (multiply by 100 for \% by volume)}$$

used theoretical moisture

$$\underline{0.0240}$$

d. Stack gas molecular weight, lb/lb mole (dry)

$$MW_{dry} = [0.44(\%CO_2)] + [0.32(\%O_2)] + [0.28(\%N_2)]$$

$$MW_{dry} = [0.44(0)] + [0.32(21.1)] + [0.28(78.9)]$$

$$MW_{dry} = \underline{28.844} \text{ lb/lb mole}$$

e. Stack gas molecular weight, lb/lb mole (wet)

$$MW_{wet} = [MW_{dry}(1 - B_{ws})] + [18(B_{ws})]$$

$$MW_{wet} = [28.844(1 - 0.0240)] + [18(0.0240)]$$

$$MW_{wet} = \underline{28.584} \text{ lb/lb mole}$$

f. Absolute stack pressure, in Hg

$$P_s = P_{bar} + \left(\frac{P_{sg}}{13.6} \right)$$

$$P_s = 30.09 + \left(\frac{-0.61}{13.6} \right)$$

$$P_s = \underline{30.045} \text{ in. Hg}$$

g. Stack velocity, ft/sec

$$v_s =$$

$$v_s =$$

$$v_s = \text{ } \text{ft/sec}$$

h. Actual stack flow rate, acfm $Q =$ $Q =$ $Q =$ **i. Standard stack gas flow rate, wscfm** $Q_{ws} =$ $Q_{ws} =$ $Q_{ws} =$ **j. Standard stack gas flow rate, dscfm** $Q_{ds} =$ $Q_{ds} =$ $Q_{ds} =$

EXAMPLE CALCULATIONS

HEXAVALENT CHROMIUM EMISSIONS

Project name: Schnitzer Steel Project number: 452603
 Computed by: Katie Resch Calculation date: 12/18/18
 Run number: 41-Cr Organic Compound: Cr

EMISSIONS DATA

Mass of measured hexavalent chromium in sample, ug/sample F_t
 Dry stack gas flow rate at standard conditions, dscfm Q_{ds}
 Standard volume of gas sampled, dscf 36.36 $V_{m, std}$
 Reference Temperature, °R 530 T_r
 Stack O₂, % volume dry 21.1 O_2
 Molecular Weight g/gmol 51.996 MW
 Material Processed, ton/hr A

3. HEXAVALENT CHROMIUM EMISSIONS

a. Mass emissions of hexavalent chromium, lb/hr

$$M = \left(\frac{F_t \times Q_{ds}}{V_{m, std}} \right) \left(\frac{1 lb}{454 g} \right) \left(\frac{1 g}{10^6 ug} \right) \left(\frac{60 min}{hour} \right)$$

$M =$

$M =$

Note: The results calculated on this page and the pages that follow may differ slightly from the results presented in the final report. This difference can be attributed to "significant digit round-off errors" common when comparing computer spreadsheets results with those derived from using a calculator.

b. Concentration of hexavalent chromium, ppm

$$C = \left(\frac{F_t}{V_{m,std}} \right) \left(\frac{T_r}{520} \right) \left(\frac{1g}{10^6 \mu g} \right) \left(\frac{1lb}{454g} \right) \left(\frac{379.5 dscf}{lb \cdot mol} \right) \left(\frac{lb \cdot mol}{MWg / gmol} \right) 10^6$$

$$C = \left(\frac{\quad}{\quad} \right) \left(\frac{\quad}{520} \right) \left(\frac{379.5}{\quad \times 454} \right)$$

$$C = \quad \text{ppm}$$

c. Mass emissions of hexavalent chromium, lb/ton

$$E = \left(\frac{M}{A} \right)$$

$$E =$$

$$E =$$

Note: The results calculated on this page and the pages that follow may differ slightly from the results presented in the final report. This difference can be attributed to "significant digit round-off errors" common when comparing computer spreadsheets results with those derived from using a calculator.

EXAMPLE CALCULATIONS TRACE SPECIES EMISSIONS

Project name: Schnitzer SteelProject number: 452603Computed by: Katie ReschCalculation date: 12/18/18Run number: 1 PCB

TOTAL PCBs

EMISSIONS DATA

Mass of measured compound in sample, mg/sample

 F_t (2187 ng)

Dry stack gas flow rate at standard conditions, dscfm

 Q_{ds}

Standard volume of gas sampled, dscf

35.852 $V_{m, std}$

Reference Temperature, °R

530 T_r Stack O₂, % volume dry20.9 O_2 ~~Molecular Weight g/gmol~~~~MW~~

Material Processed, ton/hr

 A

3. TRACE SPECIES EMISSIONS

a. Mass emissions, lb/hr

 $M =$ $M =$ $M =$

Note: The results calculated on this page and the pages that follow may differ slightly from the results presented in the final report. This difference can be attributed to "significant digit round-off errors" common when comparing computer spreadsheets results with those derived from using a calculator.

b. Concentration, ppm

$$C = \left(\frac{F_t}{V_{m,std}} \right) \left(\frac{T_r}{520} \right) \left(\frac{1g}{10^3 mg} \right) \left(\frac{1lb}{454 g} \right) \left(\frac{379.5 dscf}{lb \bullet mol} \right) \left(\frac{lb \bullet mol}{MWg / gmol} \right) 10^6$$

$$C = \left(\frac{\quad}{\quad} \right) \left(\frac{\quad}{520} \right) \left(\frac{1g}{10^3 mg} \right) \left(\frac{379.5}{\quad \times 454} \right) 10^6$$

$$C = \quad \text{ppm}$$

c. Emission rate, lb/ton

E =

E =

E =

Appendix A.6

General Emissions Calculations

EMISSION CALCULATIONS

1. Volumetric Flow and Isokinetics

- a. Standard sample gas volume, dscf

$$V_{mstd} = (V_m)(Y) \frac{(T_{std} + 460) \left(P_{bar} + \frac{\Delta H}{13.6} \right)}{(T_m + 460)(P_{std})}$$

- b. Water vapor volume, scf

$$V_{wstd} = (0.04715)(V_{lc}) \left(\frac{T_{std} + 460}{528} \right)$$

- c. Moisture content, non-dimensional

$$B_{ws} = \frac{V_{wstd}}{(V_{mstd} + V_{wstd})}$$

- d. Stack gas molecular weight, lb/lb mole (dry)

$$MW_{dry} = [0.44(\%CO_2)] + [0.32(\%O_2)] + [0.28(\%N_2)]$$

- e. Stack gas molecular weight, lb/lb mole (wet)

$$MW_{wet} = [MW_{dry}(1 - B_{ws})] + [18(B_{ws})]$$

- f. Absolute stack pressure, in Hg

$$P_s = P_{bar} + \left(\frac{P_{sg}}{13.6} \right)$$

- g. Stack velocity, ft/sec

$$v_s = (85.49)(C_p)(\sqrt{\Delta P}) \sqrt{\frac{T_s}{(P_s)(MW_{wet})}}$$

- h. Actual stack flow rate, acfm

$$Q = (v_s)(A_s)(60 \text{ min/hr})$$

- i. Standard stack gas flow rate, wscfm

$$Q_{ws} = (v_s)(A_s)(60 \text{ min/hr}) \left(\frac{T_{std} + 460}{T_s + 460} \right) \left(\frac{P_s}{P_{std}} \right)$$

- j. Standard stack gas flow rate, dscfm

$$Q_{ds} = (v_s)(A_s)(60 \text{ min/hr})(1 - B_{ws}) \left(\frac{T_{std} + 460}{T_s + 460} \right) \left(\frac{P_s}{P_{std}} \right)$$

- k. Percent isokinetic

$$I = \frac{(T_s)(V_{mstd})(P_{std})(100)}{(T_{std} + 460)(v_s)(\theta)(A_n)(P_s)(60)(1 - B_{ws})}$$

2. Gaseous Emissions

- a. Concentration, ppm volume wet (i.e. to calculate wet ppm from dry ppm)

$$C_w = (C)(1 - B_{ws})$$

- b. Concentration, ppm @ 3% O
- ₂
- dry

$$C_3 = (C) \left[\frac{(20.9 - 3.0)}{(20.9 - \% O_2)} \right]$$

- c. Concentration, ppm @ 12% CO
- ₂
- dry

$$C_{12} = (C) \left(\frac{12.0}{\% CO_2} \right)$$

- d. Concentration, ppm volume dry (i.e. to calculate dry ppm from wet ppm)

$$C = \left[\frac{C_w}{(1 - B_{ws})} \right]$$

- e. Mass emission rate, lb/hr

$$M = (C)(CF)(Q_{ds})(60 \text{ min/hr})$$

where,

CF = conversion factor from ppm to lb/scf:

$$CF_{NOx} = 1.194 \times 10^{-7} \left(\frac{\text{lb/scf}}{\text{ppm}} \right)$$

$$CF_{SO2} = 1.660 \times 10^{-7} \left(\frac{\text{lb/scf}}{\text{ppm}} \right)$$

$$CF_X = CF_{NOx} \left(\frac{MW_X}{MW_{NOx}} \right) \text{ for other compounds (x)}$$

- f. Emission rate, lb/MMBtu

$$E = (C)(CF)(F_d) \left(\frac{20.9}{20.9 - \% O_2} \right)$$

- g. Mass emission rate, grams/bhp-hr

$$M_j = (M) \left(\frac{453.59 \text{ g/lb}}{J} \right)$$

3. Particulate Emissions

- a. Grain loading, gr/dscf

$$G = (0.0154) \left(\frac{G_m}{V_{m\ std}} \right)$$

- b. Grain loading corrected to 12% CO
- ₂
- , gr/dscf @ 12% CO
- ₂

$$G_{12} = (G) \left(\frac{12.0}{\% CO_2} \right)$$

- c. Mass emission rate, lb/hr

$$M = (G)(Q_{ds}) \left(\frac{60\ min/hr}{7,000\ gr/lb} \right)$$

- d. Emission rate, lb/MMBtu

$$E = (G) \left(\frac{1\ lb}{7,000\ gr} \right) (F_d) \left(\frac{20.9}{20.9 - \% O_2} \right)$$

4. Fuel Factor "F"

- a. Choice #1 – use the values for F_d provided in Method 19, Table 19-1
 Choice #2 – if you have fuel ultimate and proximate analysis, calculate F_d
 (need fuel weight %CHONS, HHV)

Stoichiometric fuel factor at 68 °F, dscf/MMBtu at 0% O₂:

$$F_d = \frac{(10^6)[3.64(\% H) + 1.53(\% C) + 0.14(\% N) + 0.57(\% S) - 0.46(\% O)]}{HHV, Btu/lb}$$

- b. Fuel factor at 60 °F (use if all your volumes and flows are at 60 °F)

$$F_{d\ 60} = F_d \left(\frac{520^\circ R}{528^\circ R} \right)$$

5. Miscellaneous Equations

- a. Standard stack gas flow rate, calculated from fuel flow and F factor, dscfm

Note: Q_f and HHV need to be in units of either lb/hr and Btu/lb, or scf/hr and Btu/scf.
Do not mix units!

(calculation based on stack %O₂)

$$Q_{ds} = (Q_f)(HHV)(10^{-6})(F_d) \left(\frac{20.9}{20.9 - \% O_2} \right) / (60 \text{ min/hr})$$

or (calculation based on stack %CO₂ – see EPA Method 19 for values of F_c)

$$Q_{ds} = (Q_f)(HHV)(10^{-6})(F_c) \left(\frac{100}{\% CO_2} \right) / (60 \text{ min/hr})$$

- b. Destruction efficiency of emission control device, %

$$EFF = \left(\frac{C_{in} - C_{out}}{C_{in}} \right) (100\%) \quad \text{based on concentrations}$$

or

$$EFF = \left(\frac{M_{in} - M_{out}}{M_{in}} \right) (100\%) \quad \text{based on mass emission rates}$$

- c. Cylinder gas audit, % accuracy

$$A_c = \left(\frac{C_m - C_a}{C_a} \right) (100\%)$$

Nomenclature:

A_c	=	accuracy of CEMS during cylinder gas audit (CGA), % difference
A_n	=	nozzle area, in ² (πr^2), where $\pi = 3.1416$ and r = radius ($\frac{1}{2}$ diameter) in inches
A_s	=	stack area, ft ² (πr^2), where $\pi = 3.1416$ and r = radius ($\frac{1}{2}$ diameter) in feet
B_{ws}	=	flue gas moisture content (multiply by 100 for % by volume)
C	=	concentration of gaseous species, ppm volume dry
C_a	=	concentration of audit gas, ppm (for CGA, equation 5c)
C_m	=	concentration measured by CEMS, ppm (for CGA, equation 5c)
C_p	=	calibration factor for pitot tube, dimensionless
C_w	=	concentration of gaseous species, ppm volume wet
C_3	=	corrected concentration of gaseous species, ppm @ 3% O ₂ dry
C_{12}	=	corrected concentration of gaseous species, ppm @ 12% CO ₂ dry
E	=	mass emission rate, lb/MMBtu
EFF	=	destruction or removal efficiency of emission control device, % efficiency
F_c	=	stoichiometric "F" factor of fuel based on CO ₂ , dscf/MMBtu @ 100% CO ₂
F_d	=	stoichiometric "F" factor of fuel based on O ₂ , dscf/MMBtu @ 0% O ₂
G	=	particulate matter grain loading, grains/dscf
G_{12}	=	corrected particulate matter grain loading, grains/dscf @ 12% CO ₂
G_m	=	mass of collected particulate matter, mg
HHV	=	higher heating value, Btu/cubic foot
I	=	% isokinetic sampling rate, %
J	=	brake horsepower, bhp
M_j	=	mass emission rate of measured species (s), g/hp-hr
M	=	mass emission rate, lb/hr
MW_{dry}	=	molecular weight of stack gas, dry basis
MW_{wet}	=	molecular weight of stack gas, wet basis
MW_s	=	molecular weight of gaseous species (s), lb/lb mole:
		CO: 28.01 (can use 28) NO _x as NO ₂ : 46.01 (can use 46)
		SO _x as SO ₂ : 64.06 (can use 64) Hydrocarbons as C: 12.01 (can use 12)
		Hydrocarbons as CH ₄ : 16.04 (can use 16) Hydrocarbons as C ₃ H ₈ : 44.10 (can use 44)
		NH ₃ : 17.03 (can use 17)
N_2	=	nitrogen content of stack gas, % volume dry
P_{bar}	=	barometric pressure, in. Hg
P_s	=	stack absolute pressure, in. Hg
P_{sg}	=	stack static pressure, inches of water, gauge (iwg)
Q	=	wet stack gas flow rate at actual conditions, acfm
Q_f	=	fuel flow rate, scfh or lb/hr (be careful of units)
Q_{ds}	=	dry stack gas flow rate at standard conditions, dscfm
Q_{ws}	=	wet stack gas flow rate at standard conditions, wscfm
SV	=	specific molar volume of an ideal gas at standard conditions, ft ³ /lb mole
T_m	=	meter temperature, °R
T_{std}	=	reference temperature, °R
T_s	=	stack gas temperature, °R
v_s	=	stack gas velocity, ft/sec
V_{lc}	=	volume of liquid collected in impingers, ml
V_m	=	dry meter volume uncorrected, acf
$V_{m\ std}$	=	dry meter volume corrected to standard conditions, dscf
$V_{w\ std}$	=	volume of water vapor at standard conditions, scf
Y	=	meter calibration coefficient, dimensionless
ΔH	=	average pressure differential across meter, inches water
ΔP	=	average velocity head of stack gas, inches water
Θ	=	sampling time, minutes

APPENDIX B FIELD AND COMPUTER-GENERATED DATA


Appendix B.1 Sampling Locations

Schnitzer Steel - Outlet


TRAVERSE POINT LAYOUT (PARTICULATE)

CIRCULAR STACKS OVER 24 INCHES

Stack diameter: inches
 Upstream diameter (A): 180.0 inches
 Downstream diameter (B): 444.0 inches
 Port length: 6.50 inches
 Number of ports being used: 2 see note
 Equivalent upstream diameter (A): Pass
 Equivalent downstream diameter (B): Pass
 All points at least 1.0" from stack wall: Pass
 Total points: 20
 Points per port: 10




DUCT AREA = ft²



Point	% Diameter	Inside wall Distance (in)	Outside port Distance (in)
1	 	2.0	8.5
2	 	6.3	12.8
3	 	11.2	17.7
4	 	17.3	23.8
5	 	26.2	32.7
6	 	50.3	56.8
7	 	59.2	65.7
8	 	65.3	71.8
9	 	70.2	76.7
10	 	74.5	81.0
N/A	#N/A	#N/A	#N/A
N/A	#N/A	#N/A	#N/A

Note: No traverse point shall be within 1.0" of the stack walls (see Sections 11.3.1)

Duct diameters upstream from flow disturbance or stack exit (Distance A)



Appendix B.2

Hexavalent Chromium Data Sheets

Project Information

Client / Facility SCHNITZER STEEL

Page 1 of 1

Source / Location Main stack

Method CARB 425

Pollutant(s) Cr Date 10/29-10/31/08

Operator / Assistant RO, WP, MK, SS Project No. 005AS-452603

Ambient Conditions (Mobile Lab)

Relative humidity, % _____

Temperature, °F _____

Mobile lab no. Trailer 9

Balance Audit

Standard set ID: W-1 Field balance ID: 21-11B-04H

Standard mass, g 500.0 500.0 500.0

Field balance mass, g 500.1 500.0 500.0

Field balance must be within 0.5g of standard weight mass

Sampling Equipment Materials

Nozzle type quartz glass steel titanium inconel

Nozzle 1 diameters 0.160 D₁ 0.160 D₂ 0.160 D₃ 0.160 average

Nozzle 2 diameters D₁ D₂ D₃ average

Nozzle 3 diameters D₁ D₂ D₃ average

Probe type heated non-heated air-cooled water-cooled

Probe liner quartz glass steel Teflon®

Front-half filter yes no

Size, mm 47 90 110 125

Filter media glass fiber quartz fiber Teflon®

Support steel glass frit Teflon® frit

Gasket Viton® silicone other

Back-half filter yes no

Tared yes no

Filter media quartz fiber glass fiber Teflon®

Recovery Procedure

Purge required no yes gas type _____ purge cyl. ID _____ flow rate, lpm _____

Purge start/stop times Run 1 _____ Run 2 _____ Run 3 _____

202 CPM filter temp., °F _____

Container levels marked yes Sample labels complete yes

Blanks/spikes required reagent blanks field blank spike other

Sample Observations

	Run 1	2	Run 3	4	Run 5	6	Run _____
Front-half filter appearance	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	
Condensate appearance	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	
Back-half filter appearance	<u>Visible Rings</u>	<u>Visible Rings</u>	<u>Visible Rings</u>	<u>Visible Rings</u>	<u>Rings</u>	<u>Rings</u>	
Condensate pH	<u>9.0</u>	<u>9.0</u>	<u>9.0</u>	<u>9.0</u>	<u>9.0</u>	<u>9.0</u>	
Trap appearance	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	

Reagent Use and Quality

Water	Type I	Type II (DI)	Other	Lot ID
Acetone	Grade	Notes		Lot ID
Hexane	Grade	Notes		Lot ID
<u>0.1N NaHCO₃</u>	<u>✓</u>	<u>Grade</u>	<u>Notes</u>	<u>Cluster Lab 226.29.24</u>
<u>0.1N NaHCO₃</u>	<u>✓</u>	<u>Grade</u>	<u>Notes</u>	<u>Cluster Lab 226.29.10</u>
<u>1.0N NaHCO₃</u>	<u>✓</u>	<u>Grade</u>	<u>Notes</u>	<u>Cluster Lab 226.29.10</u>
		Grade	Notes	Lot ID

Glassware Preparation

Impinger Cleaning Procedure Detergent and water Acetone rinse Hexane rinse
Acid soak and DI rinse Triple solvent rinses (for PAH, PCDD/DF)
Other

If this information is not accurate for all runs, note all exceptions:

2 filters utilized for each ft run

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: Mal-Stacky Car body Method: CARB 425
Run no. 1-CR Date: 10/29/18 Operator / Assistant: MR Project No: 00545-452603

Equipment Identification		Calibration		Equipment Checks	
Meter console ID	<u>CB-22</u>	Meter Yd	<u>0.989</u>	Meter: cfm @ in. Hg	<u>0.004 @ 15</u> <u>0.003 @ 5.0</u>
Stack TC ID	<u>161-SP-4</u>	Meter ΔH@0.75cfm	<u>1.850</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.9</u> <u>✓ @ 3.7</u>
Probe/pitot ID	<u>161-SP-4</u>	Pitot tube Cp	<u>0.84</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.8</u> <u>✓ @ 3.4</u>
Nozzle ID	<u>373-160-18</u>	Nozzle diameter, in.	<u>0.160</u>	Pitot visual:	<u>aligned / damaged</u> <u>aligned / damaged</u>
Imp. outlet TC ID	<u>GSN-20</u>	ALT-011 TC Check (see bottom of page)		Nozzle visual:	<u>intact / damaged</u> <u>intact / damaged</u>
Filter TC ID	<u>-</u>	Std. TC ID	<u>SEE RUN 3</u>	Other:	
Micromanometer ID	<u>CB-22</u>	Std. TC temp., °F	<u>3</u>		
Sensitivity, in. H ₂ O	<u>0.05</u>	Continuity Check	☐		
Test / Sampling Parameters		Ambient / Stack Gas Conditions			
Run duration, min.	<u>60</u>	Baro. press., in. Hg	<u>30.12</u>		
No. of traverse pts.	<u>20</u>	Ambient temp., °F	<u>-</u>		
No. of ports	<u>4</u>	Static (P _g), in. H ₂ O	<u>-0.71</u>		
Points per port	<u>5</u>	O ₂ conc., % dry vol.	<u>20.89</u>		
Time per point, min.	<u>3</u>	CO ₂ conc., % dry vol.	<u>0.034</u>		
Probe/filter range, °F	<u>248.525</u>	Wet bulb temp., °F	<u>-</u>		
Imp. outlet max., °F	<u>248.68</u>				
K Factor: ΔH = <u>0.68</u> x ΔP or dwell time = <u> </u> x √ΔP					

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (V _m), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F		Vaccum in. Hg
										Inlet	Outlet	
1	3	20:00	263.362	1.55	1.05	66	249		53		59	3.85
2		20:03	265.03	1.6	1.09	67	250		47		59	3.5
3		20:06	246.72	1.65	1.12	67	248		46		60	3.5
4		20:09	268.45	1.65	1.12	66	247		46		60	3.5
5		20:12	270.14	1.5	1.02	67	249		46		60	3.5
PC	-	20:15	271.777									
1	3	20:17	271.777	1.7	1.16	67	250		47		61	4.0
2		20:20	273.51	1.8	1.22	68	248		47		61	4.5
3		20:23	275.28	1.9	1.29	65	247		48		61	4.55.0
4		20:26	277.08	1.95	1.33	65	247		49		62	5.5
5		20:29	278.90	1.6	1.09	64	247		50		62	5.0
PC	-	20:32	280.624									
1	3	20:34	280.624	1.75	1.19	59	248		51		62	6.0
2		20:37	282.36	1.95	1.33	63	250		51		63	8.5
3		20:40	284.11	2.1	1.43	68	247		51		63	10.5
4		20:43	285.96	2.05	1.39	68	249		52		63	14.0
5		20:46	287.82	1.9	1.29	68	247		52		64	17.5
PC	-	20:49	289.506									
1	3	20:54	289.649	1.5	1.02	69	249		54		64	3.0
2		20:57	291.36	1.5	1.02	69	249		53		64	3.0
3		21:00	293.03	1.6	1.09	69	247		52		64	3.5
4		21:03	294.74	1.55	1.05	69	249		52		65	3.0
5		21:06	296.41	1.35	0.92	69	248		52		65	3.0
END	-	21:09	297.975									

ALT-011

Comments: Between 3rd and 4th port, changed out in train filter (because of high vacuum). Leak check = 0.008 @ 16

Project Information

Client / Facility SCHNITZER STEEL Page 1 of 1
Source / Location Exhaust Stack Method CARB 425
Run no. 2-CR Date 10/29/18 Operator / Assistant ML Project No. 005AS-452603

Equipment Identification		Calibration		Equipment Checks	
Meter console ID	<u>CR-22</u>	Meter Yd	<u>0.989</u>	Meter: cfm @ in. Hg	<u>0.006 @ 15</u> <u>0.003 @ 6.0</u>
Stack TC ID	<u>161-SP-4</u>	Meter ΔH@0.75cfm	<u>1.850</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.7</u> <u>✓ @ 3.6</u>
Probe/pitot ID	<u>161-SP-4</u>	Pitot tube Cp	<u>0.84</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.6</u> <u>✓ @ 3.5</u>
Nozzle ID	<u>373-100-A</u>	Nozzle diameter, in.	<u>0.100</u>	Pitot visual:	<u>aligned / damaged</u> <u>aligned / damaged</u>
Imp. outlet TC ID	<u>ASN-20</u>	ALT-011 TC Check (see bottom of page)		Nozzle visual:	<u>intact / damaged</u> <u>intact / damaged</u>
Filter TC ID	<u>-</u>	Std. TC	<u>SEE RUN 3</u>	Other:	
Micromanometer ID	<u>CR-22</u>	Std. TC temp., °F	<u>3</u>	Impingers	Initial, g Final, g Difference
Sensitivity, in. H ₂ O	<u>0.05</u>	Continuity Check	☐	0.1N NaHCO ₃	<u>635.4</u> <u>634.7</u> <u>671.1</u> <u>35.7</u>
Test / Sampling Parameters		Ambient / Stack Gas Conditions		0.1N NaHCO ₃	<u>659.6</u> <u>660.1</u> <u>0.5</u>
Run duration, min.	<u>60</u>	Baro. press., in. Hg	<u>30.12</u>	EMPTY	<u>535.6</u> <u>535.8</u> <u>0.2</u>
No. of traverse pts.	<u>20</u>	Ambient temp., °F	<u>-</u>	SILICA GEL	<u>958.1</u> <u>965.8</u> <u>7.7</u>
No. of ports	<u>4</u>	Static (P _g), in. H ₂ O	<u>-0.67</u>		
Points per port	<u>5</u>	O ₂ conc., % dry vol.	<u>21.03</u>		
Time per point, min.	<u>3</u>	CO ₂ conc., % dry vol.	<u>0.025</u>		
Probe/filter range, °F	<u>248 ± 25</u>	Wet bulb temp., °F			
Imp. outlet max., °F	<u>608</u>			Tared Line Rinse	<u>25</u> <u>0.25</u> <u>-25</u>
K Factor: ΔH = <u>0.68</u> x ΔP or dwell time = <u> </u> x √ΔP				Total impinger weight gain, g	<u>19.1</u>
				Filter ID	<u>-</u>

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F inlet outlet	Vaccum in. Hg
1	3	22:35	298.721	1.55	1.05	68	247		51	60	3.0
2		22:38	300.45	1.6	1.09	68	247		47	60	3.5
3		22:41	302.14	1.55	1.05	67	249		45	60	3.5
4		22:44	303.79	1.55	1.05	67	248		45	61	4.0
5	↓	22:47	305.46	1.45	0.99	67	247		45	61	4.0
PC	-	22:50	307.084								
PAUSED @ PC											
1	3	23:31	307.084	1.75	1.19	61	249		50	59	5.0
2		23:34	308.88	1.95	1.33	61	248		46	59	6.5
3		23:37	310.71	2.1	1.43	63	249		44	60	8.0
4		23:40	312.58	2.1	1.43	63	249		44	60	10.0
5	↓	23:43	314.48	2.0	1.36	63	249		44	60	12.5
PC	-	23:46	316.344								
* Wavy line											
1	3	23:51	316.415	1.75	1.19	64	249		49	60	3.5
2		23:54	318.25	1.9	1.29	65	248		46	61	3.5
3		23:57	320.10	1.9	1.29	64	249		46	61	3.5
4		24:00	321.95	2.0	1.36	64	248		47	62	4.0
5	↓	24:03	323.89	1.7	1.16	64	248		47	63	3.5
PC	-	24:06	325.661								
Wavy line											
1	3	24:08	325.661	1.55	1.05	65	249		50	63	3.5
2		24:11	327.35	1.6	1.09	65	248		49	63	3.5
3		24:14	329.08	1.6	1.09	65	247		48	64	3.5
4		24:17	330.78	1.65	1.12	65	250		48	64	4.0
5	↓	24:20	332.52	1.4	0.95	65	247		48	65	4.0
		24:23	334.003								

ALT-011

Comments: * switched out in train filter between 2nd and 3rd ports.
Leak check = 0.004 @ 15 in

SAMPLE TRAIN DATA

Project Information

Client / Facility SCHNITZER STEEL Page 1 of 1
Source / Location Exhaust Stack Method CARB 425
Run no. 3-CR Date 10/30/18 Operator / Assistant ML Project No. 005AS-452603

Equipment Identification		Calibration		Equipment Checks	
Meter console ID	<u>LB-22</u>	Meter Yd	<u>0.989</u>	Meter: cfm @ in. Hg	<u>0.005 @ 15</u>
Stack TC ID	<u>161-584</u>	Meter ΔH@0.75cfm	<u>1.850</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.5</u>
Probe/pitot ID	<u>161-584</u>	Pitot tube Cp	<u>0.84</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.4</u>
Nozzle ID	<u>333-160-A</u>	Nozzle diameter, in.	<u>0.160</u>	Pitot visual:	<u>aligned / damaged</u>
Imp. outlet TC ID	<u>65N-20</u>	ALT-011 TC Check (see bottom of page)		Nozzle visual:	<u>intact / damaged</u>
Filter TC ID	<u>-</u>	Std. TC ID	<u>MEG444</u>	Other:	
Micromanometer ID	<u>CB-22</u>	Std. TC temp., °F	<u>62.1</u>	Impingers	Initial, g Final, g Difference
Sensitivity, in. H ₂ O	<u>0.05</u>	Continuity Check	<u>4</u>	0.1N NaHCO ₃	<u>658.7</u> <u>693.8</u> <u>35.1</u>
Test / Sampling Parameters		Ambient / Stack Gas Conditions		0.1N NaHCO ₃	<u>651.0</u> <u>656.2</u> <u>0.2</u>
Run duration, min.	<u>60</u>	Baro. press., in. Hg	<u>30.12</u>	EMPTY	<u>556.3</u> <u>557.3</u> <u>1.0</u>
No. of traverse pts.	<u>20</u>	Ambient temp., °F	<u>-</u>	SILICA GEL	<u>960.3</u> <u>968.4</u> <u>8.1</u>
No. of ports	<u>4</u>	Static (P _g), in. H ₂ O	<u>-0.66</u>		
Points per port	<u>5</u>	O ₂ conc., % dry vol.	<u>21.07</u>		
Time per point, min.	<u>3</u>	CO ₂ conc., % dry vol.	<u>0.529</u>		
Probe/filter range, °F	<u>248 ± 25</u>	Wet bulb temp., °F	<u>-</u>	Tared Line Rinse	<u>25</u> <u>25.8</u> <u>-25</u>
Imp. outlet max., °F	<u>68</u>	K Factor: ΔH = <u>x ΔP</u> or dwell time = <u>x √ΔP</u>		Total Impinger weight gain, g	<u>19.4</u>
				Filter ID	<u>ML</u>

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F inlet outlet	Vacuum in. Hg
1	3	0:45	334.689	1.55	1.05	66	249		56		3.0
2		0:48	336.40	1.6	1.09	66	247		45		3.0
3		0:51	338.11	1.6	1.09	66	249		45		3.0
4		0:54	339.78	1.6	1.09	66	248		43		3.0
5		0:57	341.47	1.4	0.95	65	249		43		3.0
PC	-	1:00	343.085								
1	3	1:02	343.085	1.75	1.19	66	250		45		3.5
2		1:05	344.90	1.85	1.26	65	248		44		4.0
3		1:08	346.76	1.9	1.29	66	249		44		4.0
4		1:11	348.61	1.95	1.33	65	247		45		4.0
5		1:14	350.50	1.8	1.22	65	248		45		4.0
PC	-	1:17	352.319								
1	3	1:25	352.356	1.8	1.22	65	244		50		4.0
2		1:28	354.16	1.95	1.33	65	247		47		4.5
3		1:31	356.03	2.1	1.43	65	247		47		4.5
4		1:34	358.01	2.15	1.46	65	249		46		4.5
5		1:37	360.02	1.85	1.24	65	240		47		4.0
PC	-	1:40	361.837								
1	3	1:42	361.837	1.5	1.02	65	249		48		3.5
2		1:45	363.54	1.55	1.05	65	247		48		3.5
3		1:48	365.23	1.6	1.09	65	247		49		3.5
4		1:51	366.96	1.55	1.05	64	249		49		3.5
5		1:54	368.67	1.45	0.99	65	247		49		3.5
END	-	1:57	370.328								

ALT-011 62 150 - 48 - 64

Comments: changed out in-train filter Std. 142.3 148.4 50.0 62.7
between 2nd and 3rd ports. Leak check = 0.005 @ 15 in.

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: Smelter Exhaust Stack Method: CARB 425
Run no. 4-CR Date: 10/20/18 Operator / Assistant: MC Project No.: 005AS-452603

Equipment Identification Meter console ID: <u>CB-22</u> Stack TC ID: <u>161-SP-4</u> Probe/pitot ID: <u>161-SP-4</u> Nozzle ID: <u>333-160-A</u> Imp. outlet TC ID: <u>GSEN-20</u> Filter TC ID: <u>-</u> Micromanometer ID: <u>CB-22</u> Sensitivity, in. H ₂ O: <u>0.05</u>	Calibration Meter Yd: <u>0.989</u> Meter ΔH@0.75cfm: <u>1.850</u> Pitot tube Cp: <u>0.84</u> Nozzle diameter, in.: <u>0.160</u> ALT-011 TC Check (see bottom of page) Std. TC ID: <u>SEE RUN</u> Std. TC temp., °F: <u>3</u> Continuity Check: ☐	Equipment Checks <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th></th> <th>Pre</th> <th>Post</th> </tr> <tr> <td>Meter: cfm @ in. Hg</td> <td><u>0.005 @ 15</u></td> <td><u>0.003 @ 5.0</u></td> </tr> <tr> <td>Pitot (+): in. H₂O @ in. H₂O</td> <td><u>✓ @ 3.9</u></td> <td><u>✓ @ 3.7</u></td> </tr> <tr> <td>Pitot (-): in. H₂O @ in. H₂O</td> <td><u>✓ @ 3.8</u></td> <td><u>✓ @ 3.6</u></td> </tr> <tr> <td>Pitot visual:</td> <td><u>aligned / damaged</u></td> <td><u>aligned / damaged</u></td> </tr> <tr> <td>Nozzle visual:</td> <td><u>intact / damaged</u></td> <td><u>intact / damaged</u></td> </tr> <tr> <td>Other:</td> <td></td> <td></td> </tr> </table> <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>Impingers</th> <th>Initial, g</th> <th>Final, g</th> <th>Difference</th> </tr> <tr> <td>0.1N NaHCO₃</td> <td><u>719.0</u></td> <td><u>758.8</u></td> <td><u>39.8</u></td> </tr> <tr> <td>0.1N NaHCO₃</td> <td><u>660.0</u></td> <td><u>661.1</u></td> <td><u>1.1</u></td> </tr> <tr> <td>EMPTY</td> <td><u>561.6</u></td> <td><u>561.7</u></td> <td><u>0.1</u></td> </tr> <tr> <td>SILICA GEL</td> <td><u>931.9</u></td> <td><u>938.7</u></td> <td><u>7.0</u></td> </tr> <tr> <td></td> <td><u>/</u></td> <td><u>/</u></td> <td><u>/</u></td> </tr> <tr> <td></td> <td><u>/</u></td> <td><u>/</u></td> <td><u>/</u></td> </tr> <tr> <td>Tared Line Rinse</td> <td><u>25</u></td> <td><u>250</u></td> <td><u>-25</u></td> </tr> <tr> <td>Total impinger weight gain, g</td> <td></td> <td></td> <td><u>23.0</u></td> </tr> </table>		Pre	Post	Meter: cfm @ in. Hg	<u>0.005 @ 15</u>	<u>0.003 @ 5.0</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.9</u>	<u>✓ @ 3.7</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.8</u>	<u>✓ @ 3.6</u>	Pitot visual:	<u>aligned / damaged</u>	<u>aligned / damaged</u>	Nozzle visual:	<u>intact / damaged</u>	<u>intact / damaged</u>	Other:			Impingers	Initial, g	Final, g	Difference	0.1N NaHCO ₃	<u>719.0</u>	<u>758.8</u>	<u>39.8</u>	0.1N NaHCO ₃	<u>660.0</u>	<u>661.1</u>	<u>1.1</u>	EMPTY	<u>561.6</u>	<u>561.7</u>	<u>0.1</u>	SILICA GEL	<u>931.9</u>	<u>938.7</u>	<u>7.0</u>		<u>/</u>	<u>/</u>	<u>/</u>		<u>/</u>	<u>/</u>	<u>/</u>	Tared Line Rinse	<u>25</u>	<u>250</u>	<u>-25</u>	Total impinger weight gain, g			<u>23.0</u>
	Pre	Post																																																									
Meter: cfm @ in. Hg	<u>0.005 @ 15</u>	<u>0.003 @ 5.0</u>																																																									
Pitot (+): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.9</u>	<u>✓ @ 3.7</u>																																																									
Pitot (-): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.8</u>	<u>✓ @ 3.6</u>																																																									
Pitot visual:	<u>aligned / damaged</u>	<u>aligned / damaged</u>																																																									
Nozzle visual:	<u>intact / damaged</u>	<u>intact / damaged</u>																																																									
Other:																																																											
Impingers	Initial, g	Final, g	Difference																																																								
0.1N NaHCO ₃	<u>719.0</u>	<u>758.8</u>	<u>39.8</u>																																																								
0.1N NaHCO ₃	<u>660.0</u>	<u>661.1</u>	<u>1.1</u>																																																								
EMPTY	<u>561.6</u>	<u>561.7</u>	<u>0.1</u>																																																								
SILICA GEL	<u>931.9</u>	<u>938.7</u>	<u>7.0</u>																																																								
	<u>/</u>	<u>/</u>	<u>/</u>																																																								
	<u>/</u>	<u>/</u>	<u>/</u>																																																								
Tared Line Rinse	<u>25</u>	<u>250</u>	<u>-25</u>																																																								
Total impinger weight gain, g			<u>23.0</u>																																																								
Test / Sampling Parameters Run duration, min.: <u>60</u> No. of traverse pts.: <u>20</u> No. of ports: <u>4</u> Points per port: <u>5</u> Time per point, min.: <u>3</u> Probe/filter range, °F: <u>248 ± 25</u> Imp. outlet max., °F: <u>68</u> K Factor: ΔH = <u>0.7</u> x ΔP or dwell time = <u> </u> x √ΔP																																																											

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP		ΔH		Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F		Vaccum in. Hg
				ln. H ₂ O	ln. H ₂ O	Inlet	outlet							
1	3	21:14	370.949	1.45	1.02	69	249		51		59		3.0	
2	↓	21:17	372.05	1.5	1.05	70	247		40		59		3.5	
3	↓	21:20	374.34	1.55	1.09	70	247		45		59		3.5	
4	↓	21:23	376.04	1.5	1.05	71	247		45		59		3.5	
5	↓	21:26	377.71	1.35	0.95	71	248		45		59		3.0	
PC	-	21:29	379.320											
1	3	21:31	379.320	1.8	1.26	71	247		47		60		4.0	
2	↓	21:34	381.13	1.95	1.37	71	248		45		60		4.0	
3	↓	21:37	383.02	2.1	1.47	70	249		45		61		4.5	
4	↓	21:40	384.97	2.1	1.47	70	247		45		61		4.5	
5	↓	21:43	386.96	1.85	1.30	70	247		46		62		4.0	
PC	-	21:46	388.860											
1	3	21:52	388.915	1.7	1.19	71	247		49		63		3.5	
2	↓	21:55	390.75	1.85	1.30	70	247		47		63		3.5	
3	↓	21:58	392.61	1.95	1.37	70	248		46		63		4.0	
4	↓	22:01	394.53	2.0	1.4	69	249		46		64		4.0	
5	↓	22:04	396.51	1.75	1.23	68	247		46		65		3.5	
PC	-	22:07	398.389											
1	3	22:09	398.389	1.55	1.09	68	247		49		66		3.5	
2	↓	22:12	400.02	1.50	1.05	68	248		48		66		3.5	
3	↓	22:15	401.79	1.55	1.09	68	248		47		67		3.5	
4	↓	22:18	403.50	1.6	1.12	67	249		47		67		3.5	
5	↓	22:21	405.23	1.4	0.98	68	247		47		68		3.0	
END	-	22:24	406.884											

in train ALT-011
 Comments: changed out filter between 2nd and 3rd port.
 Leak check = 0.004 @ 15 in.

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: Main Stack Car with Tanks Method: CARB 425
Run no. 5-CR Date: 10/30/18 Operator / Assistant: _____ Project No. 005AS-452603

Equipment Identification		Calibration		Equipment Checks	
Meter console ID	<u>CR-22</u>	Meter Yd	<u>0.989</u>	Meter: cfm @ in. Hg	<u>0.003 @ 15</u> <u>0.003 @ 6.0</u>
Stack TC ID	<u>161-SP-4</u>	Meter ΔH@0.75cfm	<u>1.850</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.4</u> <u>✓ @ 3.7</u>
Probe/pitot ID	<u>161-SP-4</u>	Pitot tube Cp	<u>0.84</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.6</u> <u>✓ @ 3.9</u>
Nozzle ID	<u>333-100-A</u>	Nozzle diameter, in.	<u>0.110</u>	Pitot visual:	<u>aligned / damaged</u> <u>aligned / damaged</u>
Imp. outlet TC ID	<u>45N-20</u>	ALT-011 TC Check (see bottom of page)		Nozzle visual:	<u>intact / damaged</u> <u>intact / damaged</u>
Filter TC ID	<u>-</u>	Std. TC ID	<u>SEE RUN</u>	Other:	
Micromanometer ID	<u>CD-22</u>	Std. TC temp., °F	<u>-</u>	Impingers	Initial, g Final, g Difference
Sensitivity, in. H ₂ O	<u>0.05</u>	Continuity Check	<u>6</u> ☐	0.1N NaHCO ₃	<u>661.1</u> <u>635.2</u> <u>694.4</u> <u>33.3</u>
Test / Sampling Parameters		Ambient / Stack Gas Conditions		0.1N NaHCO ₃	<u>651.5</u> <u>652.8</u> <u>1.1</u>
Run duration, min.	<u>60</u>	Baro. press., in. Hg	<u>30.09</u>	EMPTY	<u>557.3</u> <u>558.0</u> <u>0.7</u>
No. of traverse pts.	<u>20</u>	Ambient temp., °F	<u>-</u>	SILICA GEL	<u>968.4</u> <u>976.2</u> <u>7.8</u>
No. of ports	<u>4</u>	Static (P _g), in. H ₂ O	<u>-0.41</u>		
Points per port	<u>5</u>	O ₂ conc., % dry vol.	<u>20.92</u>		
Time per point, min.	<u>3</u>	CO ₂ conc., % dry vol.	<u>0.012</u>		
Probe/filter range, °F	<u>248 ± 25</u>	Wet bulb temp., °F	<u>-</u>		
Imp. outlet max., °F	<u>65</u>			Tared Line Rinse	<u>25</u> <u>285</u> <u>-25</u>
K Factor: ΔH = <u>0.70</u> x ΔP or dwell time = _____ x √ΔP				Total impinger weight gain, g	<u>18.1</u>
				Filter ID	

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (m)	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F		Vaccum in. Hg
										inlet	outlet	
1	3	22:43	407.642	1.35	0.95	66	248		51		65	3.0
2		22:56	409.72	1.45	1.02	66	248		49		65	3.5
3		22:59	411.38	1.5	1.05	67	249		46		65	3.5
4		23:02	413.09	1.5	1.05	68	248		44		66	3.5
5		23:05	414.82	1.4	0.98	68	249		44		66	3.0
PC	-	23:08	416.461									
1	3	23:10	416.461	1.75	1.23	69	248		45		66	4.0
2		23:13	418.25	1.9	1.33	68	247		44		66	4.5
3		23:16	420.12	1.9	1.33	69	249		44		67	4.5
4		23:19	422.02	1.85	1.30	70	248		44		67	4.5
5		23:22	423.90	1.8	1.24	70	249		45		67	4.0
PC	-	23:25	425.703									
1	3	23:36	425.815	1.8	1.26	69	247		48		67	3.5
2		23:33	427.69	1.95	1.37	69	248		47		67	4.0
3		23:36	429.62	2.1	1.47	69	249		45		68	4.0
4		23:39	431.61	2.1	1.47	70	247		45		68	4.0
5		23:42	433.59	1.95	1.37	70	249		45		68	4.0
PC	-	23:45	435.532									
1	3	23:47	435.533	1.35	0.95	69	249		48		68	3.0
2		23:50	437.19	1.4	0.98	70	247		47		69	3.0
3		23:53	438.81	1.35	0.95	69	249		47		69	3.0
4		23:56	440.42	1.4	0.98	70	248		47		69	3.0
5		23:59	442.04	1.3	0.91	69	247		47		69	3.0
END	-	24:02	443.627									

ALT-011

Comments: changed in-train filter between 2nd and 3rd ports.
Leak check = 0.004 @ 15

SAMPLE TRAIN DATA

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: Main Stack Method: CARB 425
Run no. 6-CR Date: 10/31/18 Operator / Assistant: ME Project No. 405AS-452603

Equipment Identification		Calibration		Equipment Checks	
Meter console ID	<u>CB-22</u>	Meter Yd	<u>0.984</u>	Meter: cfm @ in. Hg	<u>0.005 @ 15</u> <u>0.003 @ 5.0</u>
Stack TC ID	<u>161-SP-4</u>	Meter ΔH@0.75cfm	<u>1.850</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.2</u> <u>✓ @ 3.1</u>
Probe/pitot ID	<u>161-SP-4</u>	Pitot tube Cp	<u>0.84</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>✓ @ 3.4</u> <u>✓ @ 3.3</u>
Nozzle ID	<u>393-160-1</u>	Nozzle diameter, in.	<u>0.160</u>	Pitot visual:	<u>aligned / damaged</u> <u>aligned / damaged</u>
Imp. outlet TC ID	<u>05N-20</u>	ALT-011 TC Check (see bottom of page)		Nozzle visual:	<u>intact / damaged</u> <u>intact / damaged</u>
Filter TC ID	<u>-</u>	Std. TC ID	<u>MEG-H-4</u>	Other:	
Micromanometer ID	<u>CB-22</u>	Std. TC temp., °F	<u>61.2</u>	Impingers	
Sensitivity, in. H ₂ O	<u>0.05</u>	Continuity Check	<u>+</u>	0.1N NaHCO ₃	<u>66722.5</u> <u>761.6</u> <u>39.1</u>
Test / Sampling Parameters		Ambient / Stack Gas Conditions		0.1N NaHCO ₃	<u>661.8</u> <u>662.0</u> <u>0.2</u>
Run duration, min.	<u>60</u>	Baro. press., in. Hg	<u>30.09</u>	EMPTY	<u>561.7</u> <u>561.8</u> <u>0.1</u>
No. of traverse pts.	<u>20</u>	Ambient temp., °F	<u>-</u>	SILICA GEL	<u>966.5</u> <u>973.7</u> <u>7.2</u>
No. of ports	<u>4</u>	Static (P _g), in. H ₂ O	<u>-0.61</u>		
Points per port	<u>5</u>	O ₂ conc., % dry vol.	<u>21.01</u>		
Time per point, min.	<u>3</u>	CO ₂ conc., % dry vol.	<u>0.122</u>		
Probe/filter range, °F	<u>249 ± 25</u>	Wet bulb temp., °F	<u>-</u>		
Imp. outlet max., °F	<u>68</u>			Tared Line Rinse	<u>25</u> <u>250</u> <u>-25</u>
K Factor: ΔH = <u>0.70</u> x ΔP or dwell time = <u>-</u> x √ΔP				Total impinger weight gain, g	<u>21.6</u>
				Filter ID	<u>-</u>

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time	Meter Reading (V _m), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F inlet	Meter temp., °F outlet	Vacuum in. Hg
1	3	12:20	444.343	1.45	1.02	69	249		51		66	3.0
2		12:23	446.04	1.4	0.98	70	248		49		66	3.0
3		12:26	447.67	1.4	0.98	70	247		47		66	3.0
4		12:29	449.28	1.45	1.02	71	248		46		67	3.0
5		12:32	450.98	1.35	0.99	72	247		45		67	3.0
PC	-	12:35	452.559									
1	3	0:40	452.559	1.75	1.23	71	248		48		66	4.0
2		0:43	454.45	1.95	1.37	72	248		46		67	4.0
3		0:46	456.39	2.05	1.44	73	249		46		67	4.5
4		0:49	458.38	2.1	1.47	72	249		47		67	4.5
5		0:52	460.40	1.9	1.33	71	247		48		68	4.0
PC	-	0:55	462.243									
1	3	1:05	462.913	1.75	1.23	72	248		51		67	4.0
2		1:08	464.78	1.8	1.26	71	247		49		67	4.0
3		1:11	466.67	1.9	1.33	71	246		49		68	4.0
4		1:14	468.59	1.95	1.37	70	249		48		68	4.5
5		1:17	470.53	1.7	1.19	71	248		48		69	4.0
PC	-	1:20	472.371									
		PAUSE										
1	3	1:53	472.371	1.45	1.02	63	247		51		65	3.5
2		1:56	474.08	1.55	1.09	65	248		50		65	3.5
3		1:59	475.81	1.6	1.12	66	249		49		65	4.0
4		2:02	477.54	1.55	1.09	66	247		48		65	3.5
5		2:05	479.25	1.35	0.95	67	247		48		65	3.0
PC	-	2:08	480.842									

ALT-011 628 102 - 61 - 64
Std. 61.0 101.1 60.3 62.2

Comments:

Switched out in-train filter between 2nd and 3rd ports.

Leak check = 0.003 @ 15

Appendix B.3

PolyChlorinated Biphenyl Data Sheets

Project Information

Client / Facility SCHNITZER STEEL Page 1 of 1
Source / Location Main Stack Method CARB 428
Pollutant(s) PCB Date 10/29-10/31/18 Operator / Assistant RO, NP, MK, ST Project No. 005AS-452603

Ambient Conditions (Mobile Lab)

Relative humidity, % _____
Temperature, °F _____
Mobile lab no. Trailer 9

Balance Audit

Standard set ID: W-1 Field balance ID: Z1-AB-01A
Standard mass, g 500.0 500.0 500.0
Field balance mass, g 500.1 500.0 500.0

Field balance must be within 0.5g of standard weight mass

Sampling Equipment Materials

Nozzle type quartz glass steel titanium inconel
Nozzle 1 diameters 0.160 D₁ 0.160 D₂ 0.160 D₃ 0.160 average
Nozzle 2 diameters D₁ D₂ D₃ average
Nozzle 3 diameters D₁ D₂ D₃ average
Probe type heated non-heated air-cooled water-cooled
Probe liner quartz glass steel Teflon®

Front-half filter yes no
Size, mm 47 90 110 125
Filter media glass fiber quartz fiber Teflon® Solvent Treated
Support steel glass frit Teflon® frit
Gasket Viton® silicone other

Back-half filter yes no
Tared yes no
Filter media quartz fiber glass fiber Teflon®

Recovery Procedure

Purge required no yes gas type _____ purge cyl. ID _____ flow rate, lpm _____
Purge start/stop times Run 1 _____ Run 2 _____ Run 3 _____
202 CPM filter temp., °F _____
Container levels marked yes Sample labels complete yes
Blanks/spikes required reagent blanks field blank spike other

Sample Observations

	Run 1	Run 2	Run 3	Run 4	Run 5	Run 6	Run 7
Front-half filter appearance	<u>Tan</u>	<u>Tan</u>	<u>Tan</u>	<u>Tan</u>	<u>Tan</u>	<u>Tan</u>	<u>Tan</u>
Condensate appearance	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>
Back-half filter appearance	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>
Condensate pH							
Trap appearance	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>	<u>Intact</u>

Reagent Use and Quality

Organic	Type I	Type II (DI)	Other	Lot ID
Water	<u>X</u>			<u>R000379</u>
Acetone				
Hexane				
<u>Methanol</u>	<u>✓</u>			<u>R000040</u>
<u>Toluene</u>	<u>✓</u>			<u>R000328</u>
<u>MeCl₂</u>	<u>✓</u>			<u>R000341</u>
<u>Hex</u>	<u>✓</u>			<u>R000380</u>

Glassware Preparation

Impinger Cleaning Procedure _____ Detergent and water _____ Acetone rinse _____ Hexane rinse _____
_____ Acid soak and DI rinse ✓ Triple solvent rinses (for PAH, PCDD/DF) PCB
_____ Other _____

If this information is not accurate for all runs, note all exceptions:

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: EXHAUST Method: CARB 428
Run no. 1-PCB Date: 10/29/18 Operator / Assistant: Samuel Project No. 005AS-452603

Equipment Identification Meter console ID: <u>CB-14</u> Stack TC ID: <u>162-SP-4</u> Probe/pitot ID: <u>162-SP-4</u> Nozzle ID: <u>39-160-A</u> Imp. outlet TC ID: <u>GSN-12</u> Filter TC ID: <u>CB-5</u> Micromanometer ID: <u>20.1</u> Sensitivity, in. H ₂ O: <u>203-14</u>	Calibration Meter Yd: <u>1.014</u> Meter ΔH@0.75cfm: <u>1.756</u> Pitot tube Cp: <u>0.84</u> Nozzle diameter, in.: <u>0.160</u> ALT-011 TC Check (see bottom of page) Std. TC ID: <u>/</u> Std. TC temp., °F: <u>/</u> Continuity Check: ☒	Equipment Checks <table style="width:100%;"> <tr> <th></th> <th>Pre</th> <th>Post</th> </tr> <tr> <td>Meter: cfm @ in. Hg</td> <td><u>.008 @ 15</u></td> <td><u>.006 @ 6</u></td> </tr> <tr> <td>Pitot (+): in. H₂O @ in. H₂O</td> <td><u>0 @ 5</u></td> <td><u>0 @ 3</u></td> </tr> <tr> <td>Pitot (-): in. H₂O @ in. H₂O</td> <td><u>0 @ 3</u></td> <td><u>0 @ 3</u></td> </tr> <tr> <td>Pitot visual:</td> <td><u>aligned / damaged</u></td> <td><u>aligned / damaged</u></td> </tr> <tr> <td>Nozzle visual:</td> <td><u>intact / damaged</u></td> <td><u>intact / damaged</u></td> </tr> <tr> <td>Other:</td> <td></td> <td></td> </tr> </table> <table style="width:100%;"> <tr> <th>Impingers</th> <th>Initial, g</th> <th>Final, g</th> <th>Difference</th> </tr> <tr> <td>EMPTY</td> <td><u>498.0</u></td> <td><u>498.5</u></td> <td><u>0.5</u></td> </tr> <tr> <td>ORGANIC FREE H₂O</td> <td><u>648.5</u></td> <td><u>647.7</u></td> <td><u>(0.8)</u></td> </tr> <tr> <td>EMPTY</td> <td><u>548.3</u></td> <td><u>548.8</u></td> <td><u>0.5</u></td> </tr> <tr> <td>SILICA GEL</td> <td><u>954.1</u></td> <td><u>966.0</u></td> <td><u>12.7</u></td> </tr> <tr> <td>Tared Line Rinse</td> <td></td> <td></td> <td><u>12.9</u></td> </tr> <tr> <td>Total impinger weight gain, g</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Filter ID</td> <td><u>PIA</u></td> <td></td> <td></td> </tr> </table>		Pre	Post	Meter: cfm @ in. Hg	<u>.008 @ 15</u>	<u>.006 @ 6</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>0 @ 5</u>	<u>0 @ 3</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u>	<u>0 @ 3</u>	Pitot visual:	<u>aligned / damaged</u>	<u>aligned / damaged</u>	Nozzle visual:	<u>intact / damaged</u>	<u>intact / damaged</u>	Other:			Impingers	Initial, g	Final, g	Difference	EMPTY	<u>498.0</u>	<u>498.5</u>	<u>0.5</u>	ORGANIC FREE H ₂ O	<u>648.5</u>	<u>647.7</u>	<u>(0.8)</u>	EMPTY	<u>548.3</u>	<u>548.8</u>	<u>0.5</u>	SILICA GEL	<u>954.1</u>	<u>966.0</u>	<u>12.7</u>	Tared Line Rinse			<u>12.9</u>	Total impinger weight gain, g				Filter ID	<u>PIA</u>		
	Pre	Post																																																					
Meter: cfm @ in. Hg	<u>.008 @ 15</u>	<u>.006 @ 6</u>																																																					
Pitot (+): in. H ₂ O @ in. H ₂ O	<u>0 @ 5</u>	<u>0 @ 3</u>																																																					
Pitot (-): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u>	<u>0 @ 3</u>																																																					
Pitot visual:	<u>aligned / damaged</u>	<u>aligned / damaged</u>																																																					
Nozzle visual:	<u>intact / damaged</u>	<u>intact / damaged</u>																																																					
Other:																																																							
Impingers	Initial, g	Final, g	Difference																																																				
EMPTY	<u>498.0</u>	<u>498.5</u>	<u>0.5</u>																																																				
ORGANIC FREE H ₂ O	<u>648.5</u>	<u>647.7</u>	<u>(0.8)</u>																																																				
EMPTY	<u>548.3</u>	<u>548.8</u>	<u>0.5</u>																																																				
SILICA GEL	<u>954.1</u>	<u>966.0</u>	<u>12.7</u>																																																				
Tared Line Rinse			<u>12.9</u>																																																				
Total impinger weight gain, g																																																							
Filter ID	<u>PIA</u>																																																						
Test / Sampling Parameters Run duration, min.: <u>60</u> No. of traverse pts.: <u>20</u> No. of ports: <u>4</u> Points per port: <u>5</u> Time per point, min.: <u>3</u> Probe/filter range, °F: <u>248 ± 25</u> Imp. outlet max., °F: <u>68</u> K Factor: ΔH = <u>0.68</u> × ΔP or dwell time = <u>x ΔP</u>																																																							

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F		Aux	Vaccum in. Hg
										Inlet	outlet		
5	0	20:00	358.090	1.6	1.09	65	244	243	48		58	37	1.0
4	3	20:03	359.98	1.6	1.09	65	240	242	46		57	36	1.0
3	6	20:06	361.02	1.6	1.09	65	240	242	48		57	35	1.0
2	9	20:09	362.42	1.6	1.09	65	242	242	48		57	34	1.0
1	12	20:12	364.68	1.5	1.02	65	249	252	48		57	34	1.0
PC	15	20:15	366.235										
5	15	20:17	366.235	1.8	1.23	65	244	243	47		57	37	1.0
4	18	20:20	367.04	1.9	1.29	66	246	243	45		57	35	1.0
3	21	20:23	369.92	2.1	1.43	65	242	239	44		57	35	1.0
2	24	20:26	371.75	2.0	1.36	66	239	236	45		57	35	1.0
1	27	20:29	373.60	1.9	1.29	66	235	235	45		57	35	1.0
PC	30	20:32	375.434										
5	30	20:34	376.28	1.7	1.16	66	240	240	45		57	35	1.0
4	33	20:37	377.29	1.8	1.23	66	242	240	44		57	35	1.0
3	36	20:40	378.94	1.9	1.29	66	240	245	42		58	35	1.0
2	39	20:43	380.82	1.9	1.29	66	243	244	41		58	35	2.0
1	42	20:46	382.62	1.6	1.09	66	244	243	40		58	35	2.0
PC	45	20:49	384.244										
5	45	20:53	384.244	1.6	1.09	67	234	239	45		56	35	2.0
4	48	20:56	385.85	1.6	1.09	67	241	242	45		58	35	2.0
3	51	20:59	387.47	1.6	1.09	67	243	241	46		58	35	2.0
2	54	21:02	389.09	1.6	1.09	67	245	246	43		58	35	2.0
1	57	21:05	390.71	1.4	0.95	68	245	245	46		60	35	2.0
END	60	21:08	392.283										

ALT-011

Comments:

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: Exhaust Stack Method: CARB 428
Run no. 2-PCB Date: 10-29-18 Operator / Assistant: Tavoraki Project No. 005AS-452603

Equipment Identification
Meter console ID: CB-14
Stack TC ID: 160-SF-4
Probe/pitot ID: 160-SF-4
Nozzle ID: 39-160-A
Imp. outlet TC ID: 655-12
Filter TC ID: 08-5
Micromanometer ID: 20-1
Sensitivity, in. H₂O: 5 CB-M

Calibration
Meter Yd: 1.014
Meter ΔH@0.75cfm: 1.756
Pitot tube Cp: 0.84
Nozzle diameter, in.: 0.160
ALT-011 TC Check (see bottom of page)
Std. TC ID: /
Std. TC temp., °F: /
Continuity Check: ☒

Equipment Checks

	Pre	Post
Meter: cfm @ in. Hg	<u>0.12 @ 5</u>	<u>0.04 @ 5</u>
Pitot (+): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u>	<u>0 @ 3</u>
Pitot (-): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u>	<u>0 @ 3</u>
Pitot visual:	<u>aligned / damaged</u>	<u>aligned / damaged</u>
Nozzle visual:	<u>intact / damaged</u>	<u>intact / damaged</u>
Other:		

Test / Sampling Parameters
Run duration, min.: 60
No. of traverse pts.: 20
No. of ports: 4
Points per port: 5
Time per point, min.: 3
Probe/filter range, °F: 248
Imp. outlet max., °F: 668

Ambient / Stack Gas Conditions
Baro. press., in. Hg: 30.12
Ambient temp., °F: 61
Static (P_g), in. H₂O: -0.07
O₂ conc., % dry vol.: 21.03
CO₂ conc., % dry vol.: 0.025
Wet bulb temp., °F: -

Impingers	Initial, g	Final, g	Difference
EMPTY	<u>500.8</u>	<u>501.0</u>	<u>0.2</u>
ORGANIC FREE H ₂ O	<u>646.6</u>	<u>646.6</u>	<u>0.0</u>
EMPTY	<u>554.3</u>	<u>553.8</u>	<u>(0.5)</u>
SILICA GEL	<u>1000.7</u>	<u>1015.2</u>	<u>14.5</u>
Tared Line Rinse			
Total Impinger weight gain, g			<u>14.2</u>

K Factor: ΔH = 0.68 x ΔP or dwell time = x ΔP

Filter ID: MA

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F		Aux	Vaccum in. Hg
										Inlet	Outlet		
S	6	22:35	392.429	1.95	0.65	66	237	247	50		57	35	1.0
4	3	22:38	393.69	1.00	0.68	65	247	249	48		57	35	1.0
3	6	22:41	395.03	1.00	0.68	65	242	242	48		57	35	1.0
2	9	22:44	396.32	1.10	0.75	65	238	248	52		59	35	1.0
1	12	22:47	397.41	1.10	0.75	64	253	250	53		58	35	1.0
PC	15	22:50	399.096										
PC													
S	15	23:31	399.096	1.10	0.75	59	252	246	50		56	35	1.0
24	18	23:34	400.48	1.20	0.82	60	248	254	49		57	35	1.0
SS 10-29-18	3	23:37	401.92	1.30	0.88	61	249	250	48		56	35	1.0
2	24	23:40	403.35	1.40	0.95	61	248	249	47		57	35	1.0
1	27	23:43	404.89	1.36	0.88	60	250	248	46		56	35	1.0
PC	30	23:46	406.359										
PC													
S	30	23:51	406.359	1.20	0.82	62	254	247	48		56	35	1.0
4	33	23:54	407.78	1.30	0.88	62	250	248	46		56	35	1.0
3	36	23:57	409.28	1.30	0.88	62	251	258	44		56	35	1.0
2	39	24:00	411.76	1.50	1.02	62	252	258	44		56	35	1.0
1	42	0:03	412.50	1.40	0.95	63	250	250	43		56	35	1.0
PC	45	0:06	413.26	0.9									
PC													
S	45	0:08	413.26	0.95	0.65	63	253	260	45		56	35	1.0
SS 10-29-18	4	0:11	415.16	0.95	0.65	64	252	257	54		56	35	1.0
3	51	0:14	416.40	0.98	0.67	64	251	247	47		56	3.5	1.0
2	54	0:17	417.70	1.00	0.68	64	251	243	44		56	3.5	1.0
1	57	0:20	419.00	0.98	0.67	64	250	244	45		56	3.5	1.0
END	60	0:23	420.302										

ALT-011

Comments:

SAMPLE TRAIN DATA

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: main stack Method: CARB 428
Run no. 3-PCB Date: 10-30-18 Operator / Assistant: Javorshi Project No. 005AS-452603

Equipment Identification

Meter console ID: CB-14
Stack TC ID: 102-SP-4
Probe/pitot ID: 102-SP-4
Nozzle ID: 39-100-A
Imp. outlet TC ID: 42N-10
Filter TC ID: 08-5
Micromanometer ID: 20.1
Sensitivity, in. H₂O: 0.08-14

Test / Sampling Parameters

Run duration, min.: 60
No. of traverse pts.: 20
No. of ports: 4
Points per port: 5
Time per point, min.: 3
Probe/filter range, °F: 248
Imp. outlet max., °F: 668

Calibration

Meter Yd: 1.014
Meter ΔH@0.75cfm: 1.756
Pitot tube Cp: 0.84
Nozzle diameter, in.: 0.160
ALT-011 TC Check (see bottom of page)
Std. TC ID: 7M12644
Std. TC temp., °F: 62.1
Continuity Check: ☒

Ambient / Stack Gas Conditions

Baro. press., in. Hg: 30.12
Ambient temp., °F: 59
Static (P_g), in. H₂O: -0.460
O₂ conc., % dry vol.: 21.57
CO₂ conc., % dry vol.: 0.024
Wet bulb temp., °F: —

Equipment Checks

Pre Post
Meter: cfm @ in. Hg: 0.004 @ 4 0.003 @ 3.0
Pitot (+): in. H₂O @ in. H₂O: 0 @ 3 0 @ 3.1
Pitot (-): in. H₂O @ in. H₂O: 0 @ 3 0 @ 3.2
Pitot visual: aligned / damaged aligned / damaged
Nozzle visual: in tact / damaged in tact / damaged
Other: —

Impingers

	Initial, g	Final, g	Difference
EMPTY	<u>504.0</u>	<u>502.7</u>	<u>(1.3)</u>
ORGANIC FREE H ₂ O	<u>650.1</u>	<u>648.2</u>	<u>(1.9)</u>
EMPTY	<u>558.8</u>	<u>558.4</u>	<u>(0.4)</u>
SILICA GEL	<u>957.5</u>	<u>968.9</u>	<u>11.4</u>

Tared Line Rinse: —
Total impinger weight gain, g: 7.6
Filter ID: —

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F		Aux	Vacuum in. Hg
										inlet	outlet		
5	0	0:45	420.404	0.98	0.63	63	262	237	45	55	35	35	1.0
4	3	0:48	421.75	0.98	0.67	63	261	254	40	57	35	35	1.0
3	6	0:51	423.03	1.00	0.68	63	257	255	41	55	35	35	1.0
2	9	0:54	424.32	1.00	0.68	63	253	254	43	55	35	35	1.0
1	12	0:57	425.61	1.00	0.68	63	249	254	44	55	35	35	1.0
PC	15	1:00	426.912										
5	18	1:02	428.912	1.10	0.75	63	250	245	45	56	35	35	1.0
4	21	1:05	428.29	1.20	0.82	63	248	266	44	56	35	35	1.0
3	24	1:08	429.71	1.40	0.95	63	250	263	41	56	35	35	1.0
2	27	1:11	431.28	1.50	1.02	63	249	235	41	56	35	35	1.0
1	30	1:14	432.84	1.40	0.95	63	250	256	40	56	35	35	1.0
PC	30	1:17	434.42	1.80	1.22	63	251	252	42	55	35	35	1.0
5	33	1:20	434.42	1.80	1.22	63	251	252	42	55	35	35	1.0
4	36	1:23	436.10	1.90	1.29	63	247	248	39	55	35	35	1.0
3	39	1:26	437.90	1.90	1.29	63	249	244	43	55	35	35	1.0
2	42	1:29	439.64	1.90	1.29	63	250	247	38	57	35	35	1.0
1	45	1:32	441.40	1.70	1.16	61	250	248	37	56	35	35	1.0
PC	48	1:35	443.112										
5	51	1:38	443.112	1.60	1.09	62	243	246	40	55	35	35	1.0
4	54	1:41	444.75	1.60	1.09	62	243	242	38	56	35	35	1.0
3	57	1:44	446.39	1.70	1.16	63	243	250	38	56	35	35	1.0
2	60	1:47	448.04	1.60	1.09	62	247	250	38	56	35	35	1.0
1	63	1:50	449.68	1.50	1.02	62			38	57	35	35	1.0
END	60	1:58	451.284										

ALT-011 63 121 42 63

Comments:

02 122 42 02

SAMPLE TRAIN DATA

Project Information

Client / Facility SCHNITZER STEEL

Page 1 of 1

Source / Location Main Stack

Method CARB 428

Run no. 4-PCB

Date 10-30-18

Operator / Assistant Salvatore

Project No. 005AS-452603

Equipment Identification

Meter console ID CB-14
Stack TC ID 160-SP-4
Probe/pitot ID 160-SP-4
Nozzle ID 39-160-A
Imp. outlet TC ID 65N-12
Filter TC ID 08-5
Micromanometer ID 20-1
Sensitivity, in. H₂O 0.03-14

Calibration

Meter Yd 1.014
Meter ΔH@0.75cfm 1.756
Pitot tube Cp 0.84
Nozzle diameter, in. ALT-011 TC Check (see bottom of page)
Std. TC ID ALT-011 TC Check (see bottom of page)
Std. TC temp., °F ALT-011 TC Check (see bottom of page)
Continuity Check ☐

Equipment Checks

Pre Post
Meter: cfm @ in. Hg 0.006 @ 5 4 @ 6
Pitot (+): in. H₂O @ in. H₂O 0 @ 3 0 @ 3
Pitot (-): in. H₂O @ in. H₂O 0 @ 3 0 @ 3
Pitot visual: aligned / damaged aligned / damaged
Nozzle visual: intact / damaged intact / damaged
Other: intact / damaged

Test / Sampling Parameters

Run duration, min. 60
No. of traverse pts. 20
No. of ports 4
Points per port 5
Time per point, min. 3
Probe/filter range, °F 248
Imp. outlet max., °F 668

Ambient / Stack Gas Conditions

Baro. press., in. Hg 30.09
Ambient temp., °F 54
Static (P_g), in. H₂O -0.41
O₂ conc., % dry vol. 21.06
CO₂ conc., % dry vol. 0.011
Wet bulb temp., °F -

Impingers Initial, g Final, g Difference
EMPTY 499.4 499.8 0.4
ORGANIC FREE H₂O 654.6 653.6 (1.0)
EMPTY 553.7 554.4 0.7
SILICA GEL 966.6 973.6 7.0
Tared Line Rinse 7.1
Total impinger weight gain, g 7.1
Filter ID -

K Factor: ΔH = 0.7 x ΔP or dwell time = - x √ΔP

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp.	Imp. outlet	Meter temp., °F		Aux	Vaccum in. Hg
								°F	°F	inlet	outlet		
5	0	21:24	451.359	1.5	1.05	66	246	243	43		55	34	1.0
4	3	21:17	452.02	1.5	1.05	78	251	243	40		64	35	1.0
3	6	21:20	454.71	1.6	1.12	67	235	243	44		59	35	1.0
2	9	21:23	456.32	1.5	1.05	67	260	243	43		55	35	1.0
1	12	21:26	457.96	1.4	0.98	69	255	244	43		56	35	1.0
PC	15	21:29	459.430										
5	15	21:31	459.430	1.7	1.19	68	265	243	42		56	35	1.0
4	18	21:34	461.11	1.9	1.33	69	267	243	43		56	35	1.0
3	21	21:37	462.86	2.0	1.40	68	270	242	41		58	35	1.0
2	24	21:40	464.67	1.9	1.33	70	267	246	40		57	35	1.0
1	27	21:43	466.50	1.7	1.19	70	270	244	41		57	35	1.0
PC	30	21:46	468.281										
5	30	21:52	468.281	1.9	1.33	69	263	244	44		57	35	1.0
4	33	21:55	470.04	2.0	1.40	68	262	243	44		57	35	1.0
3	36	21:58	471.95	2.1	1.47	68	264	241	42		57	35	1.0
2	39	22:01	473.86	2.0	1.40	67	264	243	43		58	35	1.0
1	42	22:04	475.65	1.7	1.19	68	265	241	48		58	35	1.0
PC	45	22:07	477.370										
5	45	22:09	477.370	1.6	1.12	66	266	244	44		58	35	1.0
4	48	22:12	479.21	1.6	1.12	66	268	242	44		59	35	1.0
3	51	22:15	480.70	1.5	1.05	66	267	242	44		59	35	1.0
2	54	22:18	482.29	1.6	1.12	64	268	242	45		59	35	1.0
1	57	22:21	483.87	1.3	0.91	65	238	240	44		59	35	1.0
END	60	22:24	485.378										

ALT-011

Comments:

Project Information

Client / Facility SCHNITZER STEEL Page 1 of 1
Source / Location Main Stack Method CARB 428
Run no. 5-PCB Date 10-30-18 Operator / Assistant Jarvis Project No. 005AS-452603

Equipment Identification		Calibration		Equipment Checks	
Meter console ID	<u>CB-14</u>	Meter Yd	<u>1.014</u>	Meter: cfm @ in. Hg	<u>.004 @ 5</u>
Stack TC ID	<u>162-SP-4</u>	Meter ΔH@0.75cfm	<u>1.756</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u>
Probe/pitot ID	<u>162-SP-4</u>	Pitot tube Cp	<u>0.84</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u>
Nozzle ID	<u>39-160-A</u>	Nozzle diameter, in.	<u>0.140</u>	Pitot visual:	<u>aligned / damaged</u>
Imp. outlet TC ID	<u>45N-12</u>	ALT-011 TC Check (see bottom of page)		Nozzle visual:	<u>intact / damaged</u>
Filter TC ID	<u>08-5</u>	Std. TC ID		Other:	
Micromanometer ID	<u>20.1</u>	Std. TC temp., °F		Impingers	Initial, g Final, g Difference
Sensitivity, in. H ₂ O	<u>CB-14</u>	Continuity Check	☒	EMPTY	<u>502.0</u> <u>504.5</u> <u>2.5</u>
Test / Sampling Parameters		Ambient / Stack Gas Conditions		ORGANIC FREE H ₂ O	<u>671.3</u> <u>668.6</u> <u>(2.7)</u>
Run duration, min.	<u>60</u>	Baro. press., in. Hg	<u>30.09</u>	EMPTY	<u>557.5</u> <u>558.5</u> <u>1.0</u>
No. of traverse pts.	<u>20</u>	Ambient temp., °F	<u>60</u>	SILICA GEL	<u>1015.2</u> <u>1019.3</u> <u>4.1</u>
No. of ports	<u>4</u>	Static (P _g), in. H ₂ O	<u>-0.41</u>		
Points per port	<u>5</u>	O ₂ conc., % dry vol.	<u>20.72</u>		
Time per point, min.	<u>3</u>	CO ₂ conc., % dry vol.	<u>0.042</u>		
Probe/filter range, °F	<u>248</u>	Wet bulb temp., °F	<u>-</u>		
Imp. outlet max., °F	<u><68</u>			Tared Line Rinse	
K Factor: ΔH = <u>0.7</u> x ΔP or dwell time = <u> </u> x √ΔP				Total impinger weight gain, g	<u>4.9</u>
				Filter ID	<u> </u>

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP	ΔH	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F		Aux	Vaccum in. Hg
				in. H ₂ O	in. H ₂ O					inlet	outlet		
5	0	22:43	485.495	1.5	1.05	64	269	243	52		58	35	1.0
4	3	22:56	487.10	1.5	1.05	68	270	241	50		60	35	1.0
3	6	22:59	488.71	1.6	1.12	68	267	242	50		64	35	1.0
2	9	23:02	490.32	1.5	1.05	66	268	245	51		60	35	1.0
1	12	23:05	491.91	1.3	0.91	65	268	248	50		60	35	1.0
PC	15	23:08	493.357										
5	15	23:10	493.387	1.8	1.26	66	268	248	50		63	35	1.0
4	18	23:13	494.94	2.1	1.47	66	268	237	56		58	35	2.0
3	21	23:16	497.00	2.1	1.47	66	267	249	47		58	35	2.0
2	24	23:19	498.87	2.0	1.40	67	268	253	42		58	35	2.0
1	27	23:22	500.80	1.8	1.26	68	268	240	41		58	35	2.0
PC	30	23:25	502.574										
5	30	23:30	502.574	1.9	1.33	68	269	245	46		56	35	2.0
4	33	23:33	504.38	2.0	1.40	67	267	242	40		58	35	2.0
3	36	23:36	506.21	1.9	1.33	67	268	242	41		58	35	2.0
2	39	23:39	508.01	1.9	1.33	69	267	241	40		58	35	2.0
1	42	23:42	509.79	1.6	1.12	66	267	243	40		58	35	2.0
PC	45	23:45	511.430										
5	45	23:47	511.430	1.6	1.12	67	263	242	43		58	35	1.0
4	48	23:50	513.08	1.7	1.19	66	270	243	46		58	35	1.0
3	51	23:53	514.74	1.7	1.19	72	269	243	41		61	35	1.0
2	54	23:56	516.44	1.6	1.12	67	265	240	42		59	35	1.0
1	57	23:59	518.08	1.4	0.98	67	260	240	42		61	35	1.0
END	60	0:02	519.616										

ALT-011

Comments:

SAMPLE TRAIN DATA

Project Information

Client / Facility: SCHNITZER STEEL Page: 1 of 1
Source / Location: Main Stack Method: CARB 428
Run no. 6-PCB Date: 10-31-18 Operator / Assistant: Jaworski Project No. 11518-452603

Equipment Identification		Calibration		Equipment Checks	
Meter console ID	<u>CB-14</u>	Meter Yd	<u>1.014</u>	Meter: cfm @ in. Hg	<u>0.012 @ 5</u> <u>0.008 @ 3.0</u>
Stack TC ID	<u>102-SP-4</u>	Meter ΔH@0.75cfm	<u>1.756</u>	Pitot (+): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u> <u>0 @ 3</u>
Probe/pitot ID	<u>102-SP-4</u>	Pitot tube Cp	<u>0.84</u>	Pitot (-): in. H ₂ O @ in. H ₂ O	<u>0 @ 3</u> <u>0 @ 3</u>
Nozzle ID	<u>39-10A</u>	Nozzle diameter, in.	<u>0.10</u>	Pitot Visual:	<u>aligned / damaged</u> <u>aligned / damaged</u>
Imp. outlet TC ID	<u>630-12</u>	ALT-011 TC Check (see bottom of page)		Nozzle visual:	<u>intact / damaged</u> <u>intact / damaged</u>
Filter TC ID	<u>05-5</u>	Std. TC ID	<u>mech 44</u>	Other:	
Micromanometer ID	<u>20.1</u>	Std. TC temp., °F	<u>61</u>	Impingers	Initial, g Final, g Difference
Sensitivity, in. H ₂ O	<u>0.0014</u>	Continuity Check	☒	EMPTY	<u>504.1</u> <u>508.8</u> <u>4.7</u>
Test / Sampling Parameters		Ambient / Stack Gas Conditions		ORGANIC FREE H ₂ O	
Run duration, min.	<u>60</u>	Baro. press., in. Hg	<u>30.05</u>	<u>691.5</u> <u>692.0</u> <u>0.5</u>	
No. of traverse pts.	<u>20</u>	Ambient temp., °F	<u>60</u>	EMPTY	
No. of ports	<u>4</u>	Static (P ₀), in. H ₂ O	<u>-0.61</u>	<u>559.7</u> <u>558.4</u> <u>1.3</u>	
Points per port	<u>5</u>	O ₂ conc., % dry vol.	<u>21.01</u>	SILICA GEL	
Time per point, min.	<u>3</u>	CO ₂ conc., % dry vol.	<u>0.037</u>	<u>968.9</u> <u>976.5</u> <u>7.6</u>	
Probe/filter range, °F	<u>248</u>	Wet bulb temp., °F	<u>-</u>		
Imp. outlet max., °F	<u>668</u>			Tared Line Rinse	
K Factor: ΔH = <u>0.7</u> x ΔP or dwell time = <u> </u> x √ΔP				Total impinger weight gain, g	
				<u>136</u>	
				Filter ID	
				<u>-</u>	

Traverse pt. number	Sample or dwell time (Δt), min.	Clock time (24 hr)	Meter Reading (Vm), cf	ΔP in. H ₂ O	ΔH in. H ₂ O	Stack temp. °F	Probe temp. °F	Filter temp. °F	Imp. outlet °F	Meter temp., °F Inlet	Meter temp., °F outlet	Aux	Vacuum in. Hg
5	0	0:20	519.759	1.6	1.12	66	267	280	45		56	38	1.0
4	3	0:23	521.51	1.6	1.12	67	263	247	47		57	38	1.0
3	6	0:26	523.00	1.7	1.19	67	258	246	47		57	35	1.0
2	9	0:29	524.87	1.6	1.12	68	260	244	47		57	35	1.0
1	12	0:32	526.55	1.4	0.98	69	248	245	46		60	35	1.0
PC	15	0:35	528.82	1.5	1.1								
5	15	0:40	528.82	1.8	1.26	69	261	243	44		62	35	1.0
4	18	0:43	529.86	1.9	1.33	69	259	243	45		58	35	1.0
3	21	0:46	531.67	2.1	1.47	71	256	243	41		58	35	2.0
2	24	0:49	533.52	2.0	1.40	70	256	244	42		57	35	2.0
1	27	0:52	535.43	1.6	1.12	70	256	243	39		57	35	1.0
PC	30	0:55	537.102										
5	30	1:05	537.102	1.9	1.33	70	257	244	48		57	35	2.0
4	33	1:08	538.88	2.1	1.47	70	256	242	41		57	35	2.0
3	36	1:11	540.79	2.1	1.47	68	257	246	40		57	35	2.0
2	39	1:14	542.69	2.1	1.47	68	259	242	39		57	35	2.0
1	42	1:17	544.65	1.9	1.33	69	258	242	40		57	35	2.0
PC	45	1:20	546.437										
5	45	1:53	546.433	1.5	1.05	61	250	242	47		55	35	1.0
4	48	1:56	548.04	1.6	1.12	62	252	241	44		61	35	1.0
3	51	1:59	549.89	1.6	1.12	63	241	241	43		61	35	1.0
2	54	2:02	551.30	1.5	1.05	63	255	242	44		55	35	1.0
1	57	2:05	552.91	1.4	0.98	64	250	241	43		56	35	1.0
END	60	2:08	554.479										

ALT-011 03 89 60 01

Comments:

04 87 60 02

Appendix B.4 CEM Data



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition:
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Initial bias								
	Name:	O2	CO2	THC				
	Make/Model:							
	25A or 7E:	7E	7E	25A				

Cylinder Concentrations								
	Zero:	0.000	0.000	0.000				
	Low:			264.5				
	Mid:	11.57	3.938	503.2				
	High:	21.26	8.419	865.6				

Calibration Readings								
	Zero reading:	-0.005	0.011	0.060				
	Low reading:	0.000	0.000	265.6				
	Mid reading:	11.56	3.947	519.4				
	High reading:	21.26	8.416	867.4				

EPA Method 7E Error Calculations								
Zero %Err:	<2.0	-0.024	0.131	N/A				
Mid %Err:	<2.0	-0.047	0.107	N/A				
High %Err:	<2.0	0.000	-0.036	N/A				

EPA Method 25A Error Calculations								
Zero %Err:	N/A	N/A	N/A	0.060				
Low %Err:	5% of cyl	N/A	N/A	1.100				
Mid %Err:	5% of cyl	N/A	N/A	16.20				
High %Err:	N/A	N/A	N/A	1.800				

Initial Bias Data								
	Zero reading:	0.047	-0.012	N/A				
	Span reading:	11.37	4.000	N/A				
Zero % bias:	<5.0	0.245	-0.273	N/A				
Span % bias:	<5.0	-0.894	0.630	N/A				



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition:
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 1 Average Results - RUN 1

20:00:00 - 21:00:00

	Name:	O2	CO2	THC					
	Make/Model:								
Oct 29 2018	20:01:00	20.75	0.020	87.22					
Oct 29 2018	20:02:00	20.74	0.021	487.9					
Oct 29 2018	20:03:00	20.75	0.020	195.3					
Oct 29 2018	20:04:00	20.75	0.020	106.9					
Oct 29 2018	20:05:00	20.75	0.021	111.3					
Oct 29 2018	20:06:00	20.75	0.019	126.2					
Oct 29 2018	20:07:00	20.75	0.018	86.60					
Oct 29 2018	20:08:00	20.75	0.018	194.4					
Oct 29 2018	20:09:00	20.74	0.018	380.7					
Oct 29 2018	20:10:00	20.74	0.017	412.5					
Oct 29 2018	20:11:00	20.75	0.019	232.9					
Oct 29 2018	20:12:00	20.75	0.015	140.0					
Oct 29 2018	20:13:00	20.74	0.008	693.1					
Oct 29 2018	20:14:00	20.74	0.009	293.3					
Oct 29 2018	20:15:00	20.75	0.016	179.1					
Oct 29 2018	20:16:00	20.75	0.016	147.3					
Oct 29 2018	20:17:00	20.74	0.016	120.8					
Oct 29 2018	20:18:00	20.75	0.022	113.8					
Oct 29 2018	20:19:00	20.75	0.025	110.7					
Oct 29 2018	20:20:00	20.75	0.023	142.0					
Oct 29 2018	20:21:00	20.74	0.028	131.3					
Oct 29 2018	20:22:00	20.75	0.030	117.8					
Oct 29 2018	20:23:00	20.74	0.033	115.4					
Oct 29 2018	20:24:00	20.75	0.030	131.9					
Oct 29 2018	20:25:00	20.75	0.031	101.0					
Oct 29 2018	20:26:00	20.75	0.033	141.7					
Oct 29 2018	20:27:00	20.75	0.037	220.8					
Oct 29 2018	20:28:00	20.75	0.037	107.1					
Oct 29 2018	20:29:00	20.75	0.036	80.18					
Oct 29 2018	20:30:00	20.75	0.033	90.74					
Oct 29 2018	20:31:00	20.75	0.032	54.35					
Oct 29 2018	20:32:00	20.75	0.034	52.57					
Oct 29 2018	20:33:00	20.75	0.036	73.63					
Oct 29 2018	20:34:00	20.75	0.039	118.7					
Oct 29 2018	20:35:00	20.75	0.040	89.74					
Oct 29 2018	20:36:00	20.75	0.038	95.65					
Oct 29 2018	20:37:00	20.75	0.033	103.9					
Oct 29 2018	20:38:00	20.74	0.036	260.5					
Oct 29 2018	20:39:00	20.74	0.038	155.6					
Oct 29 2018	20:40:00	20.74	0.040	121.7					
Oct 29 2018	20:41:00	20.74	0.041	163.7					
Oct 29 2018	20:42:00	20.74	0.039	193.6					
Oct 29 2018	20:43:00	20.74	0.040	136.7					
Oct 29 2018	20:44:00	20.74	0.035	154.9					
Oct 29 2018	20:45:00	20.74	0.034	152.1					
Oct 29 2018	20:46:00	20.74	0.038	129.4					
Oct 29 2018	20:47:00	20.74	0.039	140.4					



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition:
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Oct 29 2018	20:48:00	20.74	0.039	193.6					
Oct 29 2018	20:49:00	20.74	0.042	208.7					
Oct 29 2018	20:50:00	20.74	0.034	354.3					
Oct 29 2018	20:51:00	20.74	0.034	166.9					
Oct 29 2018	20:52:00	20.74	0.036	118.5					
Oct 29 2018	20:53:00	20.73	0.037	354.3					
Oct 29 2018	20:54:00	20.74	0.039	511.8					
Oct 29 2018	20:55:00	20.74	0.039	177.5					
Oct 29 2018	20:56:00	20.74	0.035	135.4					
Oct 29 2018	20:57:00	20.74	0.031	134.1					
Oct 29 2018	20:58:00	20.74	0.034	120.7					
Oct 29 2018	20:59:00	20.74	0.041	132.1					
Oct 29 2018	21:00:00	20.74	0.038	123.9					

	Average:	20.74	0.030	175.5					
	Max:	20.75	0.042	693.1					
	Min:	20.73	0.008	52.57					



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Car Bodies Only
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 1 Post run bias - RUN 1

20:00:00 - 21:00:00

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Run summary data

Raw Avg:	20.74	0.030	175.5					
Max:	20.75	0.042	693.1					
Min:	20.73	0.008	52.57					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	-0.005	0.011	0.060					
Low reading:			265.6					
Mid reading:	11.56	3.947	519.4					
High reading:	21.26	8.416	867.4					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	-0.024	0.131	N/A				
Mid %Err:	<2.0	-0.047	0.107	N/A				
High %Err:	<2.0	0.000	-0.036	N/A				

EPA Method 25A Error Calculations

Zero %Err:	N/A	N/A	N/A	0.060				
Low %Err:	5% of cyl	N/A	N/A	1.100				
Mid %Err:	5% of cyl	N/A	N/A	16.20				
High %Err:	N/A	N/A	N/A	1.800				

Initial Bias Data

Zero reading:	0.156	-0.028	1.040					
Span reading:	11.58	3.916	504.7					
Zero % bias:	<5.0	0.757	-0.463	N/A				
Span % bias:	<5.0	0.094	-0.368	N/A				

Final Bias Data

Zero reading:	-0.005	0.016	2.960					
Span reading:	11.46	3.945	503.7					
Zero % bias:	<5.0	0.000	0.059	N/A				
Span % bias:	<5.0	-0.470	-0.024	N/A				
Zero % drift:	<3.0	0.757	0.522	N/A				
Span % drift:	<3.0	0.564	0.344	N/A				
Zero drift:	<3.0% span	N/A	N/A	-2.900				
Span drift:	<3.0% span	N/A	N/A	15.70				

Bias Corrected Averages

Cor Avg:	20.89	0.036	175.5					
----------	-------	-------	-------	--	--	--	--	--



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Car Bodies Only
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 2 Average Results - run 2

22:35:00 - 00:14:27

	Name:	O2	CO2	THC					
	Make/Model:								
Oct 29 2018	22:36:00	20.73	0.020	186.4					
Oct 29 2018	22:37:00	20.72	0.022	178.8					
Oct 29 2018	22:38:00	20.72	0.019	129.6					
Oct 29 2018	22:39:00	20.72	0.017	191.0					
Oct 29 2018	22:40:00	20.72	0.016	194.4					
Oct 29 2018	22:41:00	20.72	0.013	175.1					
Oct 29 2018	22:42:00	20.72	0.012	238.6					
Oct 29 2018	22:43:00	20.72	0.014	144.2					
Oct 29 2018	22:44:00	20.72	0.013	157.4					
Oct 29 2018	22:45:00	20.72	0.012	160.8					
Oct 29 2018	22:46:00	20.72	0.011	131.7					
Oct 29 2018	22:47:00	20.72	0.013	155.3					
Oct 29 2018	22:48:00	20.72	0.011	221.7					
Oct 29 2018	22:49:00	20.72	0.010	237.4					
Oct 29 2018	22:50:00	20.72	0.009	209.8					
Oct 29 2018	23:30:27	20.72	0.009	147.7					
Oct 29 2018	23:31:27	20.72	0.018	142.7					
Oct 29 2018	23:32:27	20.71	0.019	414.9					
Oct 29 2018	23:33:27	20.72	0.017	278.0					
Oct 29 2018	23:34:27	20.71	0.016	184.7					
Oct 29 2018	23:35:27	20.72	0.012	150.9					
Oct 29 2018	23:36:27	20.71	0.016	132.1					
Oct 29 2018	23:37:27	20.71	0.019	124.9					
Oct 29 2018	23:38:27	20.72	0.020	135.9					
Oct 29 2018	23:39:27	20.71	0.022	153.2					
Oct 29 2018	23:40:27	20.71	0.022	163.5					
Oct 29 2018	23:41:27	20.71	0.021	127.7					
Oct 29 2018	23:42:27	20.72	0.022	100.8					
Oct 29 2018	23:43:27	20.71	0.021	116.2					
Oct 29 2018	23:44:27	20.71	0.023	354.9					
Oct 29 2018	23:45:27	20.71	0.023	677.1					
Oct 29 2018	23:46:27	20.71	0.022	244.9					
Oct 29 2018	23:47:27	20.71	0.023	167.3					
Oct 29 2018	23:48:27	20.71	0.024	148.8					
Oct 29 2018	23:49:27	20.72	0.021	150.3					
Oct 29 2018	23:50:27	20.71	0.021	141.6					
Oct 29 2018	23:51:27	20.71	0.019	119.8					
Oct 29 2018	23:52:27	20.71	0.021	98.83					
Oct 29 2018	23:53:27	20.71	0.016	122.1					
Oct 29 2018	23:54:27	20.71	0.018	142.1					
Oct 29 2018	23:55:27	20.71	0.018	504.7					
Oct 29 2018	23:56:27	20.71	0.017	688.4					
Oct 29 2018	23:57:27	20.71	0.017	224.8					
Oct 29 2018	23:58:27	20.71	0.015	264.8					
Oct 29 2018	23:59:27	20.71	0.015	372.5					
Oct 30 2018	00:00:27	20.71	0.015	145.2					
Oct 30 2018	00:01:27	20.71	0.015	131.3					



MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Car Bodies Only
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Oct 30 2018	00:02:27	20.71	0.014	119.7					
Oct 30 2018	00:03:27	20.71	0.014	126.8					
Oct 30 2018	00:04:27	20.71	0.013	235.7					
Oct 30 2018	00:05:27	20.71	0.012	216.4					
Oct 30 2018	00:06:27	20.71	0.008	138.5					
Oct 30 2018	00:07:27	20.71	0.009	130.2					
Oct 30 2018	00:08:27	20.71	0.013	226.5					
Oct 30 2018	00:09:27	20.71	0.016	237.9					
Oct 30 2018	00:10:27	20.71	0.014	173.1					
Oct 30 2018	00:11:27	20.71	0.014	130.3					
Oct 30 2018	00:12:27	20.71	0.015	112.3					
Oct 30 2018	00:13:27	20.71	0.016	121.1					
Oct 30 2018	00:14:27	20.71	0.015	179.7					

	Average:	20.71	0.016	198.9					
	Max:	20.73	0.024	688.4					
	Min:	20.71	0.008	98.83					



PUBLIC COPY

MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Car Bodies Only
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 2 Post run bias - run 2

22:35:00 - 00:14:27

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Run summary data

Raw Avg:	20.71	0.016	198.9					
Max:	20.73	0.024	688.4					
Min:	20.71	0.008	98.83					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	-0.005	0.011	0.060					
Low reading:			265.6					
Mid reading:	11.56	3.947	519.4					
High reading:	21.26	8.416	867.4					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	-0.024	0.131	N/A				
Mid %Err:	<2.0	-0.047	0.107	N/A				
High %Err:	<2.0	0.000	-0.036	N/A				

EPA Method 25A Error Calculations

Zero %Err:	N/A	N/A	N/A	0.060				
Low %Err:	5% of cyl	N/A	N/A	1.100				
Mid %Err:	5% of cyl	N/A	N/A	16.20				
High %Err:	N/A	N/A	N/A	1.800				

Initial Bias Data

Zero reading:	-0.005	0.016	2.960					
Span reading:	11.46	3.945	503.7					
Zero % bias:	<5.0	0.000	0.059	N/A				
Span % bias:	<5.0	-0.470	-0.024	N/A				

Final Bias Data

Zero reading:	0.125	-0.035	13.61					
Span reading:	11.38	3.924	503.6					
Zero % bias:	<5.0	0.612	-0.546	N/A				
Span % bias:	<5.0	-0.847	-0.273	N/A				
Zero % drift:	<3.0	0.611	0.605	N/A				
Span % drift:	<3.0	0.377	0.249	N/A				
Zero drift:	<3.0% span	N/A	N/A	-10.650				
Span drift:	<3.0% span	N/A	N/A	0.100				

Bias Corrected Averages

Cor Avg:	21.03	0.025	198.9					
----------	-------	-------	-------	--	--	--	--	--



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Car Bodies Only
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 3 Average Results - run 3

00:45:00 - 01:45:00

	Name:	O2	CO2	THC					
	Make/Model:								
Oct 30 2018	00:46:00	20.71	0.016	98.29					
Oct 30 2018	00:47:00	20.71	0.013	102.9					
Oct 30 2018	00:48:00	20.71	0.008	160.9					
Oct 30 2018	00:49:00	20.71	0.008	140.0					
Oct 30 2018	00:50:00	20.71	0.009	134.4					
Oct 30 2018	00:51:00	20.71	0.014	153.3					
Oct 30 2018	00:52:00	20.71	0.019	103.9					
Oct 30 2018	00:53:00	20.71	0.014	124.3					
Oct 30 2018	00:54:00	20.71	0.017	124.8					
Oct 30 2018	00:55:00	20.71	0.022	84.06					
Oct 30 2018	00:56:00	20.70	0.025	85.60					
Oct 30 2018	00:57:00	20.70	0.027	109.9					
Oct 30 2018	00:58:00	20.71	0.024	136.5					
Oct 30 2018	00:59:00	20.71	0.026	117.0					
Oct 30 2018	01:00:00	20.71	0.028	157.6					
Oct 30 2018	01:01:00	20.70	0.031	177.6					
Oct 30 2018	01:02:00	20.70	0.029	146.8					
Oct 30 2018	01:03:00	20.71	0.031	100.9					
Oct 30 2018	01:04:00	20.70	0.031	183.1					
Oct 30 2018	01:05:00	20.70	0.031	132.1					
Oct 30 2018	01:06:00	20.70	0.029	211.1					
Oct 30 2018	01:07:00	20.70	0.030	239.0					
Oct 30 2018	01:08:00	20.70	0.028	157.5					
Oct 30 2018	01:09:00	20.70	0.027	144.4					
Oct 30 2018	01:10:00	20.70	0.027	121.2					
Oct 30 2018	01:11:00	20.70	0.026	162.0					
Oct 30 2018	01:12:00	20.70	0.020	113.9					
Oct 30 2018	01:13:00	20.70	0.017	163.4					
Oct 30 2018	01:14:00	20.70	0.020	114.2					
Oct 30 2018	01:15:00	20.70	0.022	116.4					
Oct 30 2018	01:16:00	20.70	0.026	145.8					
Oct 30 2018	01:17:00	20.70	0.021	102.4					
Oct 30 2018	01:18:00	20.70	0.023	92.03					
Oct 30 2018	01:19:00	20.71	0.030	104.8					
Oct 30 2018	01:20:00	20.71	0.027	119.0					
Oct 30 2018	01:21:00	20.71	0.030	109.2					
Oct 30 2018	01:22:00	20.71	0.033	86.49					
Oct 30 2018	01:23:00	20.70	0.036	107.1					
Oct 30 2018	01:24:00	20.70	0.036	120.8					
Oct 30 2018	01:25:00	20.71	0.033	108.2					
Oct 30 2018	01:26:00	20.70	0.036	96.00					
Oct 30 2018	01:27:00	20.70	0.038	89.97					
Oct 30 2018	01:28:00	20.70	0.037	76.21					
Oct 30 2018	01:29:00	20.70	0.038	71.46					
Oct 30 2018	01:30:00	20.70	0.040	620.8					
Oct 30 2018	01:31:00	20.70	0.038	214.8					
Oct 30 2018	01:32:00	20.70	0.036	139.5					



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Car Bodies Only
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Oct 30 2018	01:33:00	20.70	0.037	208.1					
Oct 30 2018	01:34:00	20.70	0.036	104.0					
Oct 30 2018	01:35:00	20.70	0.034	305.8					
Oct 30 2018	01:36:00	20.70	0.031	455.1					
Oct 30 2018	01:37:00	20.70	0.026	194.3					
Oct 30 2018	01:38:00	20.70	0.029	109.1					
Oct 30 2018	01:39:00	20.70	0.031	143.5					
Oct 30 2018	01:40:00	20.70	0.033	113.3					
Oct 30 2018	01:41:00	20.70	0.031	124.1					
Oct 30 2018	01:42:00	20.70	0.026	90.20					
Oct 30 2018	01:43:00	20.70	0.028	108.5					
Oct 30 2018	01:44:00	20.70	0.032	109.4					
Oct 30 2018	01:45:00	20.70	0.032	110.8					

	Average:	20.70	0.027	145.0					
	Max:	20.71	0.040	620.8					
	Min:	20.70	0.008	71.46					



PUBLIC COPY

MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Car Bodies Only
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 3 Post run bias - run 3

00:45:00 - 01:45:00

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Run summary data

Raw Avg:	20.70	0.027	145.0					
Max:	20.71	0.040	620.8					
Min:	20.70	0.008	71.46					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	-0.005	0.011	0.060					
Low reading:			265.6					
Mid reading:	11.56	3.947	519.4					
High reading:	21.26	8.416	867.4					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	-0.024	0.131	N/A				
Mid %Err:	<2.0	-0.047	0.107	N/A				
High %Err:	<2.0	0.000	-0.036	N/A				

EPA Method 25A Error Calculations

Zero %Err:	N/A	N/A	N/A	0.060				
Low %Err:	5% of cyl	N/A	N/A	1.100				
Mid %Err:	5% of cyl	N/A	N/A	16.20				
High %Err:	N/A	N/A	N/A	1.800				

Initial Bias Data

Zero reading:	0.125	-0.035	13.61					
Span reading:	11.38	3.924	503.6					
Zero % bias:	<5.0	0.612	-0.546	N/A				
Span % bias:	<5.0	-0.847	-0.273	N/A				

Final Bias Data

Zero reading:	0.074	0.038	1.100					
Span reading:	11.44	3.922	503.7					
Zero % bias:	<5.0	0.372	0.321	N/A				
Span % bias:	<5.0	-0.564	-0.297	N/A				
Zero % drift:	<3.0	0.239	0.867	N/A				
Span % drift:	<3.0	0.283	0.024	N/A				
Zero drift:	<3.0% span	N/A	N/A	12.51				
Span drift:	<3.0% span	N/A	N/A	-0.100				

Bias Corrected Averages

Cor Avg:	21.07	0.026	145.0					
----------	-------	-------	-------	--	--	--	--	--



PUBLIC COPY

MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Initial bias

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	0.000	0.003	1.100					
Low reading:	0.000	0.000	270.5					
Mid reading:	11.55	3.924	506.6					
High reading:	21.30	8.412	868.0					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	0.000	0.036	N/A				
Mid %Err:	<2.0	-0.094	-0.166	N/A				
High %Err:	<2.0	0.188	-0.083	N/A				

EPA Method 25A Error Calculations

Zero %Err:	N/A	N/A	N/A	1.100				
Low %Err:	5% of cyl	N/A	N/A	6.000				
Mid %Err:	5% of cyl	N/A	N/A	3.400				
High %Err:	N/A	N/A	N/A	2.400				

Initial Bias Data

Zero reading:	0.226	0.004	N/A					
Span reading:	11.42	3.973	N/A					
Zero % bias:	<5.0	1.063	0.012	N/A				
Span % bias:	<5.0	-0.611	0.582	N/A				



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 1 Average Results - run 4

21:14:00 - 22:14:00

	Name:	O2	CO2	THC					
	Make/Model:								
Oct 30 2018	21:15:00	20.74	0.023	65.11					
Oct 30 2018	21:16:00	20.75	0.025	65.38					
Oct 30 2018	21:17:00	20.75	0.024	71.43					
Oct 30 2018	21:18:00	20.75	0.024	75.67					
Oct 30 2018	21:19:00	20.75	0.025	74.48					
Oct 30 2018	21:20:00	20.75	0.024	67.26					
Oct 30 2018	21:21:00	20.75	0.023	64.44					
Oct 30 2018	21:22:00	20.75	0.022	73.15					
Oct 30 2018	21:23:00	20.75	0.023	60.41					
Oct 30 2018	21:24:00	20.75	0.023	58.78					
Oct 30 2018	21:25:00	20.75	0.021	57.28					
Oct 30 2018	21:26:00	20.75	0.020	78.30					
Oct 30 2018	21:27:00	20.75	0.020	71.20					
Oct 30 2018	21:28:00	20.75	0.019	76.41					
Oct 30 2018	21:29:00	20.75	0.019	75.42					
Oct 30 2018	21:30:00	20.75	0.015	67.20					
Oct 30 2018	21:31:00	20.74	0.012	74.84					
Oct 30 2018	21:32:00	20.74	0.015	65.85					
Oct 30 2018	21:33:00	20.74	0.019	73.89					
Oct 30 2018	21:34:00	20.74	0.018	58.48					
Oct 30 2018	21:35:00	20.74	0.012	92.71					
Oct 30 2018	21:36:00	20.74	0.009	55.23					
Oct 30 2018	21:37:00	20.74	0.013	50.36					
Oct 30 2018	21:38:00	20.74	0.018	48.82					
Oct 30 2018	21:39:00	20.74	0.018	56.39					
Oct 30 2018	21:40:00	20.73	0.025	88.34					
Oct 30 2018	21:41:00	20.73	0.030	86.12					
Oct 30 2018	21:42:00	20.74	0.032	97.10					
Oct 30 2018	21:43:00	20.73	0.032	119.7					
Oct 30 2018	21:44:00	20.74	0.034	109.0					
Oct 30 2018	21:45:00	20.74	0.037	69.24					
Oct 30 2018	21:46:00	20.74	0.035	70.23					
Oct 30 2018	21:47:00	20.74	0.033	112.4					
Oct 30 2018	21:48:00	20.74	0.035	98.76					
Oct 30 2018	21:49:00	20.74	0.033	68.39					
Oct 30 2018	21:50:00	20.74	0.032	79.72					
Oct 30 2018	21:51:00	20.74	0.032	78.17					
Oct 30 2018	21:52:00	20.74	0.032	63.50					
Oct 30 2018	21:53:00	20.74	0.025	55.85					
Oct 30 2018	21:54:00	20.74	0.026	66.25					
Oct 30 2018	21:55:00	20.74	0.030	75.64					
Oct 30 2018	21:56:00	20.74	0.026	73.00					
Oct 30 2018	21:57:00	20.74	0.030	81.99					
Oct 30 2018	21:58:00	20.74	0.031	82.69					
Oct 30 2018	21:59:00	20.74	0.033	91.00					
Oct 30 2018	22:00:00	20.74	0.031	82.06					
Oct 30 2018	22:01:00	20.74	0.030	98.04					



PUBLIC COPY

MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Oct 30 2018	22:02:00	20.74	0.032	95.69					
Oct 30 2018	22:03:00	20.74	0.036	72.74					
Oct 30 2018	22:04:00	20.73	0.036	69.23					
Oct 30 2018	22:05:00	20.74	0.035	88.35					
Oct 30 2018	22:06:00	20.74	0.033	73.55					
Oct 30 2018	22:07:00	20.74	0.035	84.11					
Oct 30 2018	22:08:00	20.74	0.038	138.4					
Oct 30 2018	22:09:00	20.74	0.039	75.18					
Oct 30 2018	22:10:00	20.74	0.040	64.91					
Oct 30 2018	22:11:00	20.74	0.039	66.32					
Oct 30 2018	22:12:00	20.74	0.040	120.6					
Oct 30 2018	22:13:00	20.74	0.039	76.61					
Oct 30 2018	22:14:00	20.74	0.038	81.22					

	Average:	20.74	0.027	77.21					
	Max:	20.75	0.040	138.4					
	Min:	20.73	0.009	48.82					



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 1 Post run bias - run 4

21:14:00 - 22:14:00

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Run summary data

Raw Avg:	20.74	0.027	77.21					
Max:	20.75	0.040	138.4					
Min:	20.73	0.009	48.82					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	0.000	0.003	1.100					
Low reading:			270.5					
Mid reading:	11.55	3.924	506.6					
High reading:	21.30	8.412	868.0					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	0.000	0.036	N/A				
Mid %Err:	<2.0	-0.094	-0.166	N/A				
High %Err:	<2.0	0.188	-0.083	N/A				

EPA Method 25A Error Calculations

Zero %Err:	N/A	N/A	N/A	1.100				
Low %Err:	5% of cyl	N/A	N/A	6.000				
Mid %Err:	5% of cyl	N/A	N/A	3.400				
High %Err:	N/A	N/A	N/A	2.400				

Initial Bias Data

Zero reading:	0.226	0.004	1.100					
Span reading:	11.42	3.973	506.6					
Zero % bias:	<5.0	1.063	0.012	N/A				
Span % bias:	<5.0	-0.611	0.582	N/A				

Final Bias Data

Zero reading:	0.153	0.028	7.840					
Span reading:	11.54	3.921	498.1					
Zero % bias:	<5.0	0.720	0.297	N/A				
Span % bias:	<5.0	-0.047	-0.036	N/A				
Zero % drift:	<3.0	0.343	0.285	N/A				
Span % drift:	<3.0	0.564	0.618	N/A				
Zero drift:	<3.0% span	N/A	N/A	-6.740				
Span drift:	<3.0% span	N/A	N/A	8.500				

Bias Corrected Averages

Cor Avg:	21.06	0.011	77.21					
----------	-------	-------	-------	--	--	--	--	--



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 2 Average Results - run 5

22:43:00 - 23:52:51

	Name:	O2	CO2	THC					
	Make/Model:								
Oct 30 2018	22:53:51	20.73	0.035	75.17					
Oct 30 2018	22:54:51	20.73	0.039	78.09					
Oct 30 2018	22:55:51	20.73	0.040	85.87					
Oct 30 2018	22:56:51	20.73	0.039	95.39					
Oct 30 2018	22:57:51	20.72	0.040	78.16					
Oct 30 2018	22:58:51	20.73	0.039	94.86					
Oct 30 2018	22:59:51	20.73	0.041	89.13					
Oct 30 2018	23:00:51	20.72	0.038	100.5					
Oct 30 2018	23:01:51	20.72	0.035	94.99					
Oct 30 2018	23:02:51	20.72	0.030	79.85					
Oct 30 2018	23:03:51	20.72	0.032	108.0					
Oct 30 2018	23:04:51	20.72	0.038	105.7					
Oct 30 2018	23:05:51	20.72	0.039	83.72					
Oct 30 2018	23:06:51	20.72	0.039	76.73					
Oct 30 2018	23:07:51	20.72	0.042	149.1					
Oct 30 2018	23:08:51	20.72	0.033	153.6					
Oct 30 2018	23:09:51	20.72	0.034	102.3					
Oct 30 2018	23:10:51	20.72	0.038	84.45					
Oct 30 2018	23:11:51	20.72	0.041	84.77					
Oct 30 2018	23:12:51	20.72	0.037	82.61					
Oct 30 2018	23:13:51	20.72	0.039	82.93					
Oct 30 2018	23:14:51	20.72	0.044	83.94					
Oct 30 2018	23:15:51	20.72	0.043	90.29					
Oct 30 2018	23:16:51	20.72	0.044	90.12					
Oct 30 2018	23:17:51	20.72	0.045	79.52					
Oct 30 2018	23:18:51	20.72	0.045	83.37					
Oct 30 2018	23:19:51	20.72	0.044	79.57					
Oct 30 2018	23:20:51	20.72	0.037	75.60					
Oct 30 2018	23:21:51	20.72	0.041	75.63					
Oct 30 2018	23:22:51	20.72	0.045	87.14					
Oct 30 2018	23:23:51	20.72	0.047	117.6					
Oct 30 2018	23:24:51	20.72	0.045	96.94					
Oct 30 2018	23:25:51	20.72	0.046	101.9					
Oct 30 2018	23:26:51	20.72	0.046	85.44					
Oct 30 2018	23:27:51	20.72	0.046	78.01					
Oct 30 2018	23:28:51	20.72	0.046	74.75					
Oct 30 2018	23:29:51	20.72	0.044	77.87					
Oct 30 2018	23:30:51	20.72	0.044	97.17					
Oct 30 2018	23:31:51	20.72	0.043	91.48					
Oct 30 2018	23:32:51	20.72	0.037	79.89					
Oct 30 2018	23:33:51	20.72	0.041	67.80					
Oct 30 2018	23:34:51	20.72	0.045	70.76					
Oct 30 2018	23:35:51	20.72	0.041	90.15					
Oct 30 2018	23:36:51	20.72	0.040	59.62					
Oct 30 2018	23:37:51	20.72	0.045	44.14					
Oct 30 2018	23:38:51	20.72	0.046	46.43					
Oct 30 2018	23:39:51	20.72	0.047	45.85					



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Oct 30 2018	23:40:51	20.72	0.044	47.56					
Oct 30 2018	23:41:51	20.72	0.044	49.29					
Oct 30 2018	23:42:51	20.72	0.047	79.74					
Oct 30 2018	23:43:51	20.72	0.048	83.67					
Oct 30 2018	23:44:51	20.73	0.049	63.77					
Oct 30 2018	23:45:51	20.73	0.047	53.74					
Oct 30 2018	23:46:51	20.72	0.047	64.54					
Oct 30 2018	23:47:51	20.73	0.049	67.31					
Oct 30 2018	23:48:51	20.73	0.046	62.38					
Oct 30 2018	23:49:51	20.73	0.045	77.69					
Oct 30 2018	23:50:51	20.73	0.045	48.06					
Oct 30 2018	23:51:51	20.73	0.043	39.75					
Oct 30 2018	23:52:51	20.73	0.042	47.21					

	Average:	20.72	0.042	80.69					
	Max:	20.73	0.049	153.6					
	Min:	20.72	0.030	39.75					



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 2 Post run bias - run 5

22:43:00 - 23:52:51

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Run summary data

Raw Avg:	20.72	0.042	80.69					
Max:	20.73	0.049	153.6					
Min:	20.72	0.030	39.75					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	0.000	0.003	1.100					
Low reading:			270.5					
Mid reading:	11.55	3.924	506.6					
High reading:	21.30	8.412	868.0					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	0.000	0.036	N/A				
Mid %Err:	<2.0	-0.094	-0.166	N/A				
High %Err:	<2.0	0.188	-0.083	N/A				

EPA Method 25A Error Calculations

Zero %Err:	N/A	N/A	N/A	1.100				
Low %Err:	5% of cyl	N/A	N/A	6.000				
Mid %Err:	5% of cyl	N/A	N/A	3.400				
High %Err:	N/A	N/A	N/A	2.400				

Initial Bias Data

Zero reading:	0.153	0.028	7.840					
Span reading:	11.54	3.921	498.1					
Zero % bias:	<5.0	0.720	0.297	N/A				
Span % bias:	<5.0	-0.047	-0.036	N/A				

Final Bias Data

Zero reading:	0.171	-0.019	2.320					
Span reading:	11.45	3.919	498.1					
Zero % bias:	<5.0	0.804	-0.261	N/A				
Span % bias:	<5.0	-0.470	-0.059	N/A				
Zero % drift:	<3.0	0.084	0.558	N/A				
Span % drift:	<3.0	0.423	0.023	N/A				
Zero drift:	<3.0% span	N/A	N/A	5.520				
Span drift:	<3.0% span	N/A	N/A	0.000				

Bias Corrected Averages

Cor Avg:	20.99	0.038	80.69					
-----------------	-------	-------	-------	--	--	--	--	--



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 3 Average Results - run 6

00:20:00 - 01:20:00

	Name:	O2	CO2	THC					
	Make/Model:								
Oct 31 2018	00:21:00	20.73	0.023	56.77					
Oct 31 2018	00:22:00	20.73	0.022	62.89					
Oct 31 2018	00:23:00	20.73	0.021	87.31					
Oct 31 2018	00:24:00	20.73	0.022	85.78					
Oct 31 2018	00:25:00	20.73	0.020	92.14					
Oct 31 2018	00:26:00	20.73	0.018	97.78					
Oct 31 2018	00:27:00	20.73	0.016	111.0					
Oct 31 2018	00:28:00	20.73	0.017	119.3					
Oct 31 2018	00:29:00	20.73	0.016	92.55					
Oct 31 2018	00:30:00	20.73	0.008	94.76					
Oct 31 2018	00:31:00	20.73	0.010	79.90					
Oct 31 2018	00:32:00	20.73	0.014	75.91					
Oct 31 2018	00:33:00	20.73	0.015	110.1					
Oct 31 2018	00:34:00	20.73	0.014	91.28					
Oct 31 2018	00:35:00	20.73	0.015	96.96					
Oct 31 2018	00:36:00	20.73	0.010	96.14					
Oct 31 2018	00:37:00	20.73	0.009	103.8					
Oct 31 2018	00:38:00	20.73	0.009	96.61					
Oct 31 2018	00:39:00	20.73	0.012	100.7					
Oct 31 2018	00:40:00	20.73	0.018	77.84					
Oct 31 2018	00:41:00	20.74	0.019	107.5					
Oct 31 2018	00:42:00	20.73	0.022	80.42					
Oct 31 2018	00:43:00	20.73	0.023	71.79					
Oct 31 2018	00:44:00	20.73	0.023	66.11					
Oct 31 2018	00:45:00	20.73	0.022	102.8					
Oct 31 2018	00:46:00	20.73	0.023	60.08					
Oct 31 2018	00:47:00	20.73	0.022	73.67					
Oct 31 2018	00:48:00	20.73	0.023	65.00					
Oct 31 2018	00:49:00	20.73	0.020	70.03					
Oct 31 2018	00:50:00	20.73	0.020	81.97					
Oct 31 2018	00:51:00	20.73	0.020	74.98					
Oct 31 2018	00:52:00	20.74	0.021	82.67					
Oct 31 2018	00:53:00	20.73	0.019	132.4					
Oct 31 2018	00:54:00	20.74	0.022	82.79					
Oct 31 2018	00:55:00	20.73	0.017	78.06					
Oct 31 2018	00:56:00	20.73	0.020	97.97					
Oct 31 2018	00:57:00	20.73	0.017	95.86					
Oct 31 2018	00:58:00	20.73	0.012	94.27					
Oct 31 2018	00:59:00	20.73	0.012	97.05					
Oct 31 2018	01:00:00	20.73	0.013	90.16					
Oct 31 2018	01:01:00	20.73	0.013	92.41					
Oct 31 2018	01:02:00	20.74	0.011	77.39					
Oct 31 2018	01:03:00	20.73	0.006	74.64					
Oct 31 2018	01:04:00	20.74	0.003	93.06					
Oct 31 2018	01:05:00	20.74	0.008	106.1					
Oct 31 2018	01:06:00	20.74	0.010	114.3					
Oct 31 2018	01:07:00	20.74	0.010	105.4					



PUBLIC COPY

MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Oct 31 2018	01:08:00	20.74	0.012	97.47					
Oct 31 2018	01:09:00	20.74	0.010	89.25					
Oct 31 2018	01:10:00	20.74	0.012	92.06					
Oct 31 2018	01:11:00	20.74	0.010	71.73					
Oct 31 2018	01:12:00	20.74	0.010	82.17					
Oct 31 2018	01:13:00	20.74	0.010	79.60					
Oct 31 2018	01:14:00	20.74	0.010	78.53					
Oct 31 2018	01:15:00	20.74	0.011	84.43					
Oct 31 2018	01:16:00	20.74	0.010	82.25					
Oct 31 2018	01:17:00	20.74	0.009	90.69					
Oct 31 2018	01:18:00	20.74	0.008	104.5					
Oct 31 2018	01:19:00	20.74	0.007	104.3					
Oct 31 2018	01:20:00	20.74	0.007	87.90					

	Average:	20.73	0.015	89.05					
	Max:	20.74	0.023	132.4					
	Min:	20.73	0.003	56.77					



PUBLIC COPY

MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Run 3 Post run bias - run 6

00:20:00 - 01:20:00

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Run summary data

Raw Avg:	20.73	0.015	89.05					
Max:	20.74	0.023	132.4					
Min:	20.73	0.003	56.77					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	0.000	0.003	1.100					
Low reading:			270.5					
Mid reading:	11.55	3.924	506.6					
High reading:	21.30	8.412	868.0					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	0.000	0.036	N/A				
Mid %Err:	<2.0	-0.094	-0.166	N/A				
High %Err:	<2.0	0.188	-0.083	N/A				

EPA Method 25A Error Calculations

Zero %Err:	N/A	N/A	N/A	1.100				
Low %Err:	5% of cyl	N/A	N/A	6.000				
Mid %Err:	5% of cyl	N/A	N/A	3.400				
High %Err:	N/A	N/A	N/A	2.400				

Initial Bias Data

Zero reading:	0.171	-0.019	2.320					
Span reading:	11.45	3.919	498.1					
Zero % bias:	<5.0	0.804	-0.261	N/A				
Span % bias:	<5.0	-0.470	-0.059	N/A				

Final Bias Data

Zero reading:	0.160	-0.006	3.230					
Span reading:	11.53	3.933	506.2					
Zero % bias:	<5.0	0.753	-0.107	N/A				
Span % bias:	<5.0	-0.094	0.107	N/A				
Zero % drift:	<3.0	0.051	0.154	N/A				
Span % drift:	<3.0	0.376	0.166	N/A				
Zero drift:	<3.0% span	N/A	N/A	-0.910				
Span drift:	<3.0% span	N/A	N/A	-8.100				

Bias Corrected Averages

Cor Avg:	21.01	0.027	89.05					
----------	-------	-------	-------	--	--	--	--	--

APPENDIX C LABORATORY ANALYSIS DATA

Appendix C.1

Hexavalent Chromium Analyses

MONTROSE AIR QUALITY SERVICES

PROJECT: 005AS-452603
SCHNITZER STEEL

CLIENT # M039
REPORT # 18-499

SUBMITTED BY:
CHESTER LabNet
12242 S.W. GARDEN PLACE
TIGARD, OR 97223
(503)624-2183/FAX (503)624-2653
www.ChesterLab.Net

CHESTER LabNet

12242 SW Garden Place ❖ Tigard, OR 97223-8246 ❖ USA
Telephone 503-624-2183 ❖ Fax 503-624-2653 ❖ www.chesterlab.net

Case Narrative

Date: November 13, 2018

General Information

Client: Montrose Air Quality Services
Client Number: M039
Report Number: 18-499
Sample Description: Impinger Trains, Rinses
Sample Numbers: 18-S2774 – 18-S2787


Analysis

Analytes: Total Chromium, Hexavalent Chromium
Analytical Protocols: CARB 425 (7/28/97 version)
Analytical Notes: The pH of all samples was approximately 9 as measured by full range pH paper. The samples contained high concentrations of dissolved solids which caused a low recovery of the matrix spike for total Cr. For total Cr, the samples were diluted by a factor of 5 to alleviate the problem which yielded an acceptable spike recovery. The detection limit for total Cr has been raised by a factor of five to account for the dilution. No problems were encountered during the Cr VI analyses. The results have not been blank corrected.

QA/QC Review: All of the data have been reviewed by the analysts performing the analyses and the project manager. All of the quality control and sample-specific information in this package is complete and meets or exceeds the minimum requirements for acceptability.

Comments: If you have any questions or concerns regarding this analysis, please feel free to contact the project manager.

Disclaimer: This report shall not be reproduced, except in full, without the written approval of the laboratory. The results only represent that of the samples as received into the laboratory.

 11/13/18
Project Manager Date
Paul Duda

Lab ID: 18-S2774
Client ID: 1-Cr FH Rinses
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/29/18
Sample Volume: 90.0 mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.169	0.0200	0.0152	0.0018
Total Cr	< DL	4.00	< DL	0.360

Lab ID: 18-S2775
Client ID: 1-Cr Impingers 1-3
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/29/18
Sample Volume: 390. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.0680	0.0200	0.0265	0.0078
Total Cr	< DL	4.00	< DL	1.56

Lab ID: 18-S2776
Client ID: 2-Cr FH Rinses
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/29/18
Sample Volume: 102. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.137	0.0200	0.0140	0.0020
Total Cr	< DL	4.00	< DL	0.408

Lab ID: 18-S2777
Client ID: 2-Cr Impingers 1-3
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/29/18
Sample Volume: 345. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.0370	0.0200	0.0128	0.0069
Total Cr	< DL	4.00	< DL	1.38

Lab ID: 18-S2778
Client ID: 3-Cr FH Rinses
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/30/18
Sample Volume: 102. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.0930	0.0200	0.0095	0.0020
Total Cr	< DL	4.00	< DL	0.408

Lab ID: 18-S2779
Client ID: 3-Cr Impingers 1-3
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/30/18
Sample Volume: 280. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.0390	0.0200	0.0109	0.0056
Total Cr	< DL	4.00	< DL	1.12

Lab ID: 18-S2780
Client ID: 4-Cr FH Rinses
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/30/18
Sample Volume: 102. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.101	0.0200	0.0103	0.0020
Total Cr	< DL	4.00	< DL	0.408

Lab ID: 18-S2781
Client ID: 4-Cr Impingers 1-3
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/30/18
Sample Volume: 285. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.0430	0.0200	0.0123	0.0057
Total Cr	< DL	4.00	< DL	1.14

Lab ID: 18-S2782
Client ID: 5-Cr FH Rinses
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/30/18
Sample Volume: 102. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.103	0.0200	0.0105	0.0020
Total Cr	< DL	4.00	< DL	0.408

Lab ID: 18-S2783
Client ID: 5-Cr Impingers 1-3
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/30/18
Sample Volume: 270. mL

Analyte	µg/L		µg/sample	
	Conc.	DL	Conc.	DL
Cr VI	0.0520	0.0200	0.0140	0.0054
Total Cr	< DL	4.00	< DL	1.08

Lab ID: 18-S2784
Client ID: 6-Cr FH Rinses
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/31/18
Sample Volume: 139. mL

Analyte	$\mu\text{g/L}$		$\mu\text{g/sample}$	
	Conc.	DL	Conc.	DL
Cr VI	0.0840	0.0200	0.0117	0.0028
Total Cr	< DL	4.00	< DL	0.556

Lab ID: 18-S2785
Client ID: 6-Cr Impingers 1-3
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/31/18
Sample Volume: 270. mL

Analyte	$\mu\text{g/L}$		$\mu\text{g/sample}$	
	Conc.	DL	Conc.	DL
Cr VI	0.0360	0.0200	0.0097	0.0054
Total Cr	< DL	4.00	< DL	1.08

Lab ID: 18-S2786
Client ID: FB-Cr FH Rinses
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/29/18
Sample Volume: 39.0 mL

Analyte	$\mu\text{g/L}$		$\mu\text{g/sample}$	
	Conc.	DL	Conc.	DL
Cr VI	0.583	0.0200	0.0227	0.0008
Total Cr	< DL	4.00	< DL	0.156

Lab ID: 18-S2787
Client ID: FB-Cr Impingers 1-3
Site: Schnitzer Steel
Source: Shredder Exhaust Stack
Sample Date: 10/29/18
Sample Volume: 240. mL

Analyte	$\mu\text{g/L}$		$\mu\text{g/sample}$	
	Conc.	DL	Conc.	DL
Cr VI	0.0290	0.0200	0.0070	0.0048
Total Cr	< DL	4.00	< DL	0.960

QA/QC Report

Client Name: Montrose Air Quality Services
 Project Number: M039
 Analytical Technique: IC-PCR
 Sample Description: CARB 425
 Report Number: 18-499
 =====

Blank Data

Analyte	Sample ID	Measured Conc. µg/L	DL Conc. µg/L
Cr VI	ICB	< DL	0.020
Cr VI	CCB	< DL	0.020
Cr VI	CCB	< DL	0.020

*: Sample Media Blank (SM_BlK) concentration in µg/filter
 ICB: Initial Calibration Blank CCB: Continuing Calibration Blank

Calibration QC

Analyte	Sample ID	Standard Conc. µg/L	Measured Conc. µg/L	Percent Recovery
Cr VI	ICV	1.00	1.01	101.0
Cr VI	LL-LCS	0.040	0.04	97.5
Cr VI	CCV	1.00	0.99	99.0
Cr VI	CCV	1.00	1.02	102.1

ICV: Initial Calibration Verification CCV: Continuing Calibration Verification
 Calibration Verification Limits: 90% - 110% Recovery
 LL-LCS Limits: 50% - 150% Recovery

Duplicate Data

Analyte	Sample ID	Sample Conc. µg/L	Duplicate Conc. µg/L	RPD
Cr VI	18-S2774	0.169	0.168	0.59
Cr VI	18-S2775	0.068	0.067	1.48 #

$RPD = \{ (sample - duplicate) / [(sample + duplicate) / 2] \} \times 100$
 N/C: RPD is not calculated when sample or duplicate is below detection limit
 #: per EPA CLP protocol, control limits do not apply if sample and/or duplicate concentration is less than 5x the detection limit

Laboratory Control Sample/Matrix Spike Analysis

Analyte	Sample ID	Sample Conc. µg/L	Spike Conc. µg/L	Spike Amount µg/L	Percent Recovery
Cr VI	18-S2774	0.169	1.15	1.00	98.3
Cr VI	18-S2775	0.068	1.04	1.00	97.5

*: per EPA CLP protocol, control limits do not apply if spike concentration is less than 25% of the sample concentration

QA/QC Report

Client Name: Montrose Air Quality Services
 Project Number: M039
 Analytical Technique: ICP - Optima 8300
 Sample Description: CARB 425
 Report Number: 18-499
 =====

Blank Data

Analyte	Sample ID	Measured Conc. µg/L	DL Conc. µg/L
Cr	ICB	< DL	4.00
Cr	Meth_Blk	< DL	4.00
Cr	CCB	< DL	4.00
Cr	CCB	< DL	4.00
Cr	CCB	< DL	4.00

*: Sample Media Blank (SM_Blk) concentration in µg/filter
 ICB: Initial Calibration Blank CCB: Continuing Calibration Blank

Calibration QC

Analyte	Sample ID	Standard Conc. µg/L	Measured Conc. µg/L	Percent Recovery
Cr	ICV	2500	2470	98.9
Cr	LL-CCV	4.00	4.19	104.8
Cr	LL-LCS	1.50	1.60	106.3
Cr	CCV	2500	2500	100.0
Cr	CCV	2500	2500	100.1
Cr	CCV	2500	2510	100.6

ICV: Initial Calibration Verification CCV: Continuing Calibration Verification
 Calibration Verification Limits: 90% - 110% Recovery
 LL-CCV (Low Level CCV) Limits: 70% - 130% Recovery
 LL-LCS Limits: 50% - 150% Recovery

Duplicate Data

Analyte	Sample ID	Sample Conc. µg/L	Duplicate Conc. µg/L	RPD
Cr	18-S2774	< 4	< 4	N/C #
Cr	18-S2775	< 4	< 4	N/C #

RPD = $\{(\text{sample} - \text{duplicate}) / [(\text{sample} + \text{duplicate}) / 2]\} \times 100$
 N/C: RPD is not calculated when sample or duplicate is below detection limit
 Duplicate Limit: 20% RPD
 #: per EPA CLP protocol, control limits do not apply if sample and/or duplicate concentration is less than 5x the detection limit

Laboratory Control Sample/Matrix Spike Analysis

Analyte	Sample ID	Sample Conc. µg/L	Spike Conc. µg/L	Spike Amount µg/L	Percent Recovery
Cr	LCS	< 0.8	2408.	2500.	96.3
Cr	18-S2776	< 4	2424.	2500.	97.0
Cr	18-S2777	< 4	2362.	2500.	94.5

LCS Limit: 80% - 120% Recovery Spike Limit: 75% - 125% Recovery
 *: per EPA CLP protocol, control limits do not apply if spike concentration is less than 25% of the sample concentration

CHESTER LABNET

SOURCE SAMPLE RECEIPT CHECKLIST

Client Montrose Air Quality Services Date 11/2/18
 # Runs 6 + Blanks Report # 18-499

Custody Seals Inspected, If Present

NA

Chain-of-Custody Form Inspected

CoC present with samples?

CoC indicate analytical methodology to be used? (eg M29 etc)

CoC indicate if compliance testing? (esp. M26)

M26 samples have Thiosulfate added in field?

M29 indicate FH/BH separate or combined?

Has Form Been Signed?

Have Date and Time Custody Released Been Noted on Form?

✓	
✓	*
✓	!!
Not stated	!!
NA	!!
NA	!!
✓	
✓	

All Sample Containers Inspected

Does Number of Samples Match Number on CoC Form?

Do All Sample ID Numbers Match Those on the CoC Form?

Did client mark sample volumes prior to shipment?

If required by method, did client vent samples prior to shipment?

Are the Sample Containers Intact?

Are signs of leakage present?

✓	
✓	!!
✓	!!
✓	*
NA	
✓	!!
NO	*

Chain-of-Custody Form Signed and Dated by CLN

✓

Corrective Actions

Client Contacted Due to Mismatching Sample ID Numbers

Client Contacted Due to Broken Sample Container(s)

Client Contacted Due to Leaking Sample Container(s)

Client contacted for verification of methodology?

Corrective Actions Documented?

Corrective Actions Accomplished?

11/2/18
John

*Items marked !! shall be addressed prior to any analytical work being started.**Items marked * shall be noted in case narrative upon reporting of results to client.*Signed Lin Ball

Notes _____

CHAIN OF CUSTODY



18-499

MAQS Antioch

2825 Verne Roberts Circle

Antioch, CA 94509

Phone (925) 680-4300 | Fax (925) 680-4416

Client / Project: Schnitzer Steel		Project / Sample Location: Shredder Exhaust Stack		Test / Analytical Method: Carb 425	
Project No.: 005AS-452603		Purchase Order No: PO#1027082		Special Analysis / Reporting Instructions:	
Send Analytical Report To: Antioch QA/QC: AntiochQA-QC@montrose-env.com rodell@montrose-env.com		Sampler or PM Signature: 		Please hold Reagent Blanks; Do not analyze. Will only be analyzed in the event something seems wrong with the samples. Analysis for: Cr, Cr6+ Please record temp & pH upon receiving.	
Run / Sample No.	Date	Containers	Sample Fraction	Reagent	Lab / Sample ID No.
1-CR	10/29/2018	1	(1) Front-Half Rinses	0.1N NaHCO3	18S2774
1-CR	10/29/2018	1	(2) Impingers 1-3	0.1N NaHCO3	S2775
2-CR	10/29/2018	2	(1) & (2)	0.1N NaHCO3	S2776 / S2777
3-CR	10/30/2018	2	(1) & (2)	0.1N NaHCO3	S2778 / S2779
4-CR	10/30/2018	2	(1) & (2)	0.1N NaHCO3	S2780 / S2781
5-CR	10/30/2018	2	(1) & (2)	0.1N NaHCO3	S2782 / S2783
6-CR	10/31/2018	2	(1) & (2)	0.1N NaHCO3	S2784 / S2785
FB-CR	10/29/2018	2	(1) & (2)	0.1N NaHCO3	S2786 / S2787
RB-0.1N NaHCO3	10/31/2018	1	Reagent Blank	0.1N NaHCO3	Hold; Do not analyze
RB-1.0N NaHCO3	10/31/2018	1	Reagent Blank	1.0N NaHCO3	Hold; Do not analyze
Total Containers			16		
Relinquished by 		Date 11/1/18	Time	Received by FEDEx	
Relinquished by FEDEx		Date	Time	Received by 	
Relinquished by		Date	Time	Received by	


15S2786
S2784

Temp
21°C

RAW DATA

Available upon request

Appendix C.2 Benzene Analyses



Atmospheric Analysis & Consulting, Inc.

CLIENT : Montrose AQS
 PROJECT NAME : Schnitzer Steel - Shredder Exhaust Stack
 PROJECT NO. : 005AS-452603
 AAC PROJECT NO. : 181713
 REPORT DATE : 11/16/2018

On November 5, 2018, Atmospheric Analysis & Consulting, Inc. received five (5) Six-Liter Summa Canisters for TNMNEOC analysis by TO-12M/PAMS Protocol. Upon receipt each sample was assigned a unique Laboratory ID number as follows:

Client ID	Lab ID	Initial Pressure (mmHga)
1-POC	181713-114523	Void
2-POC	181713-114524	744.6
3-POC	181713-114525	764.1
4-POC	181713-114526	651.2
5-POC	181713-114527	739.9
6-POC	181713-114528	514.2

Sample 1-POC (181713-114523) was voided due to no sample being collected in the canister. Sample was received at full vacuum.

All of the analyses mentioned above were performed in accordance with AAC's ISO/IEC 17025:2005 and NELAP approved Quality Assurance Plan. For detailed information pertaining to specific EPA, NCASI, ASTM and SCAQMD accreditations (Methods & Analytes), please visit our website at www.aaclab.com.


I certify that this data is technically accurate, complete, and in compliance with the terms and conditions of the contract. No other problems were encountered during receiving, preparation, and/or analysis of these samples. The Laboratory Director or his/her designee, as verified by the following signature, has authorized release of the data contained in this hardcopy report.

If you have any questions or require further explanation of data results, please contact the undersigned.


 Marcus Hueppe
 Laboratory Director

This report consists of 13 pages.





Atmospheric Analysis & Consulting, Inc.

Laboratory Analysis Report


CLIENT : Montrose AQS
 PROJECT NO : 181713
 MATRIX : AIR
 UNITS : PPB (v/v)

DATE RECEIVED : 11/05/2018
 DATE REPORTED : 11/26/2018

HYDROCARBONS (C2-C12) SPECIATED

Client ID	2-POC			Sample Reporting Limit (SRL) (MRLxDF's)	3-POC			Sample Reporting Limit (SRL) (MRLxDF's)	Method Reporting Limit (MRL)
AAC ID	181713-114524				181713-114525				
Date Sampled	10/29/2018				10/30/2018				
Date Analyzed	11/13/2018				11/13/2018				
Can Dilution Factor	1.37				1.33				
	Result	Qualifier	Analysis DF		Result	Qualifier	Analysis DF		
Ethylene	6.43		2.0	1.37	8.14		2.0	1.33	0.50
Acetylene	2.45		2.0	1.37	2.51		2.0	1.33	0.50
Ethane	6.32		2.0	1.37	10.8		2.0	1.33	0.50
Propylene	NR	NA	2.0	0.91	NR	NA	2.0	0.89	0.33
Propane	9.84		2.0	0.91	21.3		2.0	0.89	0.33
Isobutane	5.68		2.0	0.69	18.2		2.0	0.67	0.25
1-Butene	<SRL	U	2.0	0.69	<SRL	U	2.0	0.67	0.25
n-Butane	19.5		2.0	0.69	29.6		2.0	0.67	0.25
trans-2-Butene	<SRL	U	2.0	0.69	1.25		2.0	0.67	0.25
cis-2-Butene	<SRL	U	2.0	0.69	1.01		2.0	0.67	0.25
Isopentane	180	E	2.0	0.55	252	E	2.0	0.53	0.20
1-Pentene	4.13		2.0	0.55	4.69		2.0	0.53	0.20
n-Pentane	69.9		2.0	0.55	96.9		2.0	0.53	0.20
Isoprene	<SRL	U	2.0	0.55	0.88		2.0	0.53	0.20
trans-2-Pentene	9.59		2.0	0.55	12.5		2.0	0.53	0.20
cis-2-Pentene	4.81		2.0	0.55	6.06		2.0	0.53	0.20
2,2-Dimethylbutane	17.5		2.0	0.46	31.2		2.0	0.44	0.17
Cyclopentane	16.8		2.0	0.55	29.3		2.0	0.53	0.20
2,3-Dimethylbutane	29.7		2.0	0.46	43.8		2.0	0.44	0.17
2-Methylpentane	96.5	E	2.0	0.46	140	E	2.0	0.44	0.17
3-Methylpentane	63.5		2.0	0.46	89.1		2.0	0.44	0.17
1-Hexene	0.89		2.0	0.46	1.36		2.0	0.44	0.17
n-Hexane	NR	NA	2.0	0.46	NR	NA	2.0	0.44	0.17
Methylcyclopentane	67.6		2.0	0.46	90.0		2.0	0.44	0.17
2,4-Dimethylpentane	23.2		2.0	0.39	29.4		2.0	0.38	0.14
Benzene	NR	NA	2.0	0.46	NR	NA	2.0	0.44	0.17
Cyclohexane	NR	NA	2.0	0.46	NR	NA	2.0	0.44	0.17
2-Methylhexane	41.7		2.0	0.39	57.1		2.0	0.38	0.14
2,3-Dimethylpentane	38.4		2.0	0.39	40.4		2.0	0.38	0.14
3-Methylhexane	43.6		2.0	0.39	60.6		2.0	0.38	0.14
2,2,4-Trimethylpentane	NR	NA	2.0	0.34	NR	NA	2.0	0.33	0.13
n-Heptane	NR	NA	2.0	0.39	NR	NA	2.0	0.38	0.14
Methylcyclohexane	29.8		2.0	0.39	40.5		2.0	0.38	0.14
2,3,4-Trimethylpentane	20.6		2.0	0.34	31.3		2.0	0.33	0.13





Atmospheric Analysis & Consulting, Inc.

Laboratory Analysis Report

CLIENT : Montrose AQS
 PROJECT NO : 181713
 MATRIX : AIR
 UNITS : PPB (v/v)

DATE RECEIVED : 11/05/2018
 DATE REPORTED : 11/26/2018


HYDROCARBONS (C2-C12) SPECIATED

Client ID	2-POC			Sample Reporting Limit (SRL) (MRLxDF's)	3-POC			Sample Reporting Limit (SRL) (MRLxDF's)	Method Reporting Limit (MRL)
AAC ID	181713-114524				181713-114525				
Date Sampled	10/29/2018				10/30/2018				
Date Analyzed	11/13/2018				11/13/2018				
Can Dilution Factor	1.37				1.33				
	Result	Qualifier	Analysis DF		Result	Qualifier	Analysis DF		
Toluene	NR	NA	2.0	0.39	NR	NA	2.0	0.38	0.14
2-Methylheptane	11.1		2.0	0.34	19.8		2.0	0.33	0.13
3-Methylheptane	13.0		2.0	0.34	20.6		2.0	0.33	0.13
n-Octane	9.33		2.0	0.34	14.7		2.0	0.33	0.13
Ethylbenzene	NR	NA	2.0	0.34	NR	NA	2.0	0.33	0.13
m/p-Xylenes	NR	NA	2.0	0.34	NR	NA	2.0	0.33	0.13
Styrene	NR	NA	2.0	0.34	NR	NA	2.0	0.33	0.13
o-Xylene	NR	NA	2.0	0.34	NR	NA	2.0	0.33	0.13
Nonane	3.01		2.0	0.30	4.02		2.0	0.30	0.11
Isopropylbenzene	0.50		2.0	0.30	0.73		2.0	0.30	0.11
n-Propylbenzene	1.72		2.0	0.30	2.49		2.0	0.30	0.11
m-Ethyltoluene	6.03		2.0	0.30	8.87		2.0	0.30	0.11
p-Ethyltoluene	NR	NA	2.0	0.30	NR	NA	2.0	0.30	0.11
1,3,5-Trimethylbenzene	NR	NA	2.0	0.30	NR	NA	2.0	0.30	0.11
o-Ethyltoluene	1.82		2.0	0.30	3.30		2.0	0.30	0.11
1,2,4-Trimethylbenzene	NR	NA	2.0	0.30	NR	NA	2.0	0.30	0.11
n-Decane	1.49		2.0	0.27	1.25		2.0	0.27	0.10
1,2,3-Trimethylbenzene	0.88		2.0	0.30	2.06		2.0	0.30	0.11
m-Diethylbenzene	0.42		2.0	0.27	<SRL	U	2.0	0.27	0.10
p-Diethylbenzene	1.20		2.0	0.27	<SRL	U	2.0	0.27	0.10
n-Undecane	1.92		2.0	0.25	1.33		2.0	0.24	0.09
n-Dodecane	0.60		2.0	0.23	0.48		2.0	0.22	0.08


U - Compound was analyzed for, but was not detected at or above the SRL.

NR - Compound is not reported. See TO-15 results

E - Estimated concentration is above the calibration curve


 Marcus Hueppe
 Laboratory Director





Atmospheric Analysis & Consulting, Inc.

Laboratory Analysis Report


CLIENT : Montrose AQS
 PROJECT NO : 181713
 MATRIX : AIR
 UNITS : PPB (v/v)

DATE RECEIVED : 11/05/2018
 DATE REPORTED : 11/26/2018

HYDROCARBONS (C2-C12) SPECIATED

Client ID	4-POC			Sample Reporting Limit (SRL) (MRLxDF's)	5-POC			Sample Reporting Limit (SRL) (MRLxDF's)	Method Reporting Limit (MRL)
AAC ID	181713-114526				181713-114527				
Date Sampled	10/30/2018				10/30/2018				
Date Analyzed	11/13/2018				11/13/2018				
Can Dilution Factor	1.56				1.37				
	Result	Qualifier	Analysis DF		Result	Qualifier	Analysis DF		
Ethylene	13.2		2.0	1.56	9.55		2.0	1.37	0.50
Acetylene	2.20		2.0	1.56	3.03		2.0	1.37	0.50
Ethane	67.0		2.0	1.56	39.1		2.0	1.37	0.50
Propylene	NR	NA	2.0	1.04	NR	NA	2.0	0.91	0.33
Propane	1220	E	2.0	1.04	294	E	2.0	0.91	0.33
Isobutane	78.0		2.0	0.78	18.8		2.0	0.69	0.25
1-Butene	1.79		2.0	0.78	<SRL	U	2.0	0.69	0.25
n-Butane	68.3		2.0	0.78	20.9		2.0	0.69	0.25
trans-2-Butene	1.68		2.0	0.78	<SRL	U	2.0	0.69	0.25
cis-2-Butene	1.50		2.0	0.78	<SRL	U	2.0	0.69	0.25
Isopentane	50.7		2.0	0.62	16.0		2.0	0.55	0.20
1-Pentene	<SRL	U	2.0	0.62	<SRL	U	2.0	0.55	0.20
n-Pentane	19.7		2.0	0.62	5.82		2.0	0.55	0.20
Isoprene	<SRL	U	2.0	0.62	<SRL	U	2.0	0.55	0.20
trans-2-Pentene	<SRL	U	2.0	0.62	<SRL	U	2.0	0.55	0.20
cis-2-Pentene	<SRL	U	2.0	0.62	<SRL	U	2.0	0.55	0.20
2,2-Dimethylbutane	13.1		2.0	0.52	2.69		2.0	0.46	0.17
Cyclopentane	576	E	2.0	0.62	151	E	2.0	0.55	0.20
2,3-Dimethylbutane	6.57		2.0	0.52	1.71		2.0	0.46	0.17
2-Methylpentane	19.7		2.0	0.52	5.10		2.0	0.46	0.17
3-Methylpentane	13.9		2.0	0.52	2.93		2.0	0.46	0.17
1-Hexene	0.59		2.0	0.52	<SRL	U	2.0	0.46	0.17
n-Hexane	NR	NA	2.0	0.52	NR	NA	2.0	0.46	0.17
Methylcyclopentane	16.7		2.0	0.52	3.60		2.0	0.46	0.17
2,4-Dimethylpentane	5.36		2.0	0.45	1.12		2.0	0.39	0.14
Benzene	NR	NA	2.0	0.52	NR	NA	2.0	0.46	0.17
Cyclohexane	NR	NA	2.0	0.52	NR	NA	2.0	0.46	0.17
2-Methylhexane	16.1		2.0	0.45	3.28		2.0	0.39	0.14
2,3-Dimethylpentane	10.0		2.0	0.45	1.96		2.0	0.39	0.14
3-Methylhexane	18.7		2.0	0.45	3.80		2.0	0.39	0.14
2,2,4-Trimethylpentane	NR	NA	2.0	0.39	NR	NA	2.0	0.34	0.13
n-Heptane	NR	NA	2.0	0.45	NR	NA	2.0	0.39	0.14
Methylcyclohexane	19.3		2.0	0.45	2.69		2.0	0.39	0.14
2,3,4-Trimethylpentane	5.46		2.0	0.39	1.49		2.0	0.34	0.13





Atmospheric Analysis & Consulting, Inc.

Laboratory Analysis Report

CLIENT : Montrose AQS
 PROJECT NO : 181713
 MATRIX : AIR
 UNITS : PPB (v/v)

DATE RECEIVED : 11/05/2018
 DATE REPORTED : 11/26/2018


HYDROCARBONS (C2-C12) SPECIATED

Client ID	4-POC			Sample Reporting Limit (SRL) (MRLxDF's)	5-POC			Sample Reporting Limit (SRL) (MRLxDF's)	Method Reporting Limit (MRL)
AAC ID	181713-114526				181713-114527				
Date Sampled	10/30/2018				10/30/2018				
Date Analyzed	11/13/2018				11/13/2018				
Can Dilution Factor	1.56				1.37				
	Result	Qualifier	Analysis DF		Result	Qualifier	Analysis DF		
Toluene	NR	NA	2.0	0.45	NR	NA	2.0	0.39	0.14
2-Methylheptane	5.37		2.0	0.39	1.06		2.0	0.34	0.13
3-Methylheptane	4.93		2.0	0.39	1.29		2.0	0.34	0.13
n-Octane	8.49		2.0	0.39	1.61		2.0	0.34	0.13
Ethylbenzene	NR	NA	2.0	0.39	NR	NA	2.0	0.34	0.13
m/p-Xylenes	NR	NA	2.0	0.39	NR	NA	2.0	0.34	0.13
Styrene	NR	NA	2.0	0.39	NR	NA	2.0	0.34	0.13
o-Xylene	NR	NA	2.0	0.39	NR	NA	2.0	0.34	0.13
Nonane	4.63		2.0	0.35	2.06		2.0	0.30	0.11
Isopropylbenzene	0.40		2.0	0.35	<SRL	U	2.0	0.30	0.11
n-Propylbenzene	1.34		2.0	0.35	0.70		2.0	0.30	0.11
m-Ethyltoluene	3.95		2.0	0.35	2.49		2.0	0.30	0.11
p-Ethyltoluene	NR	NA	2.0	0.35	NR	NA	2.0	0.30	0.11
1,3,5-Trimethylbenzene	NR	NA	2.0	0.35	NR	NA	2.0	0.30	0.11
o-Ethyltoluene	1.39		2.0	0.35	0.89		2.0	0.30	0.11
1,2,4-Trimethylbenzene	NR	NA	2.0	0.35	NR	NA	2.0	0.30	0.11
n-Decane	1.72		2.0	0.31	1.11	E	2.0	0.27	0.10
1,2,3-Trimethylbenzene	1.17		2.0	0.35	0.77		2.0	0.30	0.11
m-Diethylbenzene	0.45		2.0	0.31	0.37		2.0	0.27	0.10
p-Diethylbenzene	0.87		2.0	0.31	0.63		2.0	0.27	0.10
n-Undecane	0.72		2.0	0.28	0.64		2.0	0.25	0.09
n-Dodecane	0.31		2.0	0.26	0.27		2.0	0.23	0.08


U - Compound was analyzed for, but was not detected at or above the SRL.

NR - Compound is not reported. See TO-15 results

E - Estimated concentration is above the calibration curve


 Marcus Hueppe
 Laboratory Director





Atmospheric Analysis & Consulting, Inc.

Laboratory Analysis Report


CLIENT : Montrose AQS
 PROJECT NO : 181713
 MATRIX : AIR
 UNITS : PPB (v/v)

DATE RECEIVED : 11/05/2018
 DATE REPORTED : 11/26/2018

HYDROCARBONS (C2-C12) SPECIATED

Client ID	6-POC			Sample Reporting Limit (SRL) (MRLxDF's)	Method Reporting Limit (MRL)
AAC ID	181713-114528				
Date Sampled	10/31/2018				
Date Analyzed	11/13/2018				
Can Dilution Factor	2.14				
	Result	Qualifier	Analysis DF		
Ethylene	6.85		2.0	2.14	0.50
Acetylene	4.68		2.0	2.14	0.50
Ethane	27.8		2.0	2.14	0.50
Propylene	NR	NA	2.0	1.43	0.33
Propane	19.9		2.0	1.43	0.33
Isobutane	3.45		2.0	1.07	0.25
1-Butene	<SRL	U	2.0	1.07	0.25
n-Butane	7.84		2.0	1.07	0.25
trans-2-Butene	<SRL	U	2.0	1.07	0.25
cis-2-Butene	<SRL	U	2.0	1.07	0.25
Isopentane	7.44		2.0	0.86	0.20
1-Pentene	34.1		2.0	0.86	0.20
n-Pentane	3.06		2.0	0.86	0.20
Isoprene	<SRL	U	2.0	0.86	0.20
trans-2-Pentene	<SRL	U	2.0	0.86	0.20
cis-2-Pentene	<SRL	U	2.0	0.86	0.20
2,2-Dimethylbutane	1.22		2.0	0.71	0.17
Cyclopentane	37.0		2.0	0.86	0.20
2,3-Dimethylbutane	1.08		2.0	0.71	0.17
2-Methylpentane	3.89		2.0	0.71	0.17
3-Methylpentane	2.11		2.0	0.71	0.17
1-Hexene	<SRL	U	2.0	0.71	0.17
n-Hexane	NR	NA	2.0	0.71	0.17
Methylcyclopentane	2.58		2.0	0.71	0.17
2,4-Dimethylpentane	0.80		2.0	0.61	0.14
Benzene	NR	NA	2.0	0.71	0.17
Cyclohexane	NR	NA	2.0	0.71	0.17
2-Methylhexane	1.34		2.0	0.61	0.14
2,3-Dimethylpentane	1.27		2.0	0.61	0.14
3-Methylhexane	2.14		2.0	0.61	0.14
2,2,4-Trimethylpentane	NR	NA	2.0	0.54	0.13
n-Heptane	NR	NA	2.0	0.61	0.14
Methylcyclohexane	1.22		2.0	0.61	0.14
2,3,4-Trimethylpentane	1.34		2.0	0.54	0.13





Atmospheric Analysis & Consulting, Inc.

Laboratory Analysis Report

CLIENT : Montrose AOS
 PROJECT NO : 181713
 MATRIX : AIR
 UNITS : PPB (v/v)

DATE RECEIVED : 11/05/2018
 DATE REPORTED : 11/26/2018

HYDROCARBONS (C2-C12) SPECIATED


<i>Client ID</i>	6-POC			Sample Reporting Limit (SRL) (MRLxDF's)	Method Reporting Limit (MRL)
<i>AAC ID</i>	181713-114528				
<i>Date Sampled</i>	10/31/2018				
<i>Date Analyzed</i>	11/13/2018				
<i>Can Dilution Factor</i>	2.14				
	Result	Qualifier	Analysis DF		
Toluene	NR	NA	2.0	0.61	0.14
2-Methylheptane	0.88		2.0	0.54	0.13
3-Methylheptane	0.95		2.0	0.54	0.13
n-Octane	1.19		2.0	0.54	0.13
Ethylbenzene	NR	NA	2.0	0.54	0.13
m/p-Xylenes	NR	NA	2.0	0.54	0.13
Styrene	NR	NA	2.0	0.54	0.13
o-Xylene	NR	NA	2.0	0.54	0.13
Nonane	1.32		2.0	0.48	0.11
Isopropylbenzene	<SRL	U	2.0	0.48	0.11
n-Propylbenzene	<SRL	U	2.0	0.48	0.11
m-Ethyltoluene	1.64		2.0	0.48	0.11
p-Ethyltoluene	NR	NA	2.0	0.48	0.11
1,3,5-Trimethylbenzene	NR	NA	2.0	0.48	0.11
o-Ethyltoluene	0.74		2.0	0.48	0.11
1,2,4-Trimethylbenzene	NR	NA	2.0	0.48	0.11
n-Decane	0.75		2.0	0.43	0.10
1,2,3-Trimethylbenzene	0.53		2.0	0.48	0.11
m-Diethylbenzene	<SRL	U	2.0	0.43	0.10
p-Diethylbenzene	0.46		2.0	0.43	0.10
n-Undecane	0.41		2.0	0.39	0.09
n-Dodecane	<SRL	U	2.0	0.36	0.08

U - Compound was analyzed for, but was not detected at or above the SRL.

NR - Compound is not reported. See TO-15 results


 Marcus Hueppe
 Laboratory Director





Atmospheric Analysis & Consulting, Inc.

Quality Control/Quality Assurance Report PAMS Calibration Verification Analysis

Analysis Date : 11/13/2018
Analyst : JJG

Instrument ID : MS-01
Standard ID : PS101818-01
Calibration Date : 10/23/2018

Continuing Calibration Verification

Analyte	xRF	daily RF	%RPD*
Propane	765	784	2.4


* %RPD must be < 10%

Laboratory Control Spike Recovery


Analyte	Sample Conc.	Spike Added	Spike Res	Spike Dup Res	Spike % Rec **	Spike Dup % Rec **	RPD*** %
Propane	0.0	3.88	3.98	4.02	102.6	103.6	1.0

** Must be 80-120%

*** Must be < 25%


Marcus Hueppe
Laboratory Director





Atmospheric Analysis & Consulting, Inc.

Quality Control/Quality Assurance Report


PAMS Method Blank Analysis

Matrix : Air
Units : ppbC

Analysis Date : 11/13/2018
Report Date : 11/13/2018

<i>Client ID</i>	Method Blank	PQL
<i>AAC ID</i>	PAMS BLANK	
Ethylene	<PQL	1.0
Acetylene	<PQL	1.0
Ethane	<PQL	1.0
Propylene	<PQL	1.0
Propane	<PQL	1.0
Isobutane	<PQL	1.0
1-Butene	<PQL	1.0
n-Butane	<PQL	1.0
trans-2-Butene	<PQL	1.0
cis-2-Butene	<PQL	1.0
Isopentane	<PQL	1.0
1-Pentene	<PQL	1.0
n-Pentane	<PQL	1.0
Isoprene	<PQL	1.0
trans-2-Pentene	<PQL	1.0
cis-2-Pentene	<PQL	1.0
2,2-Dimethylbutane	<PQL	1.0
Cyclopentane	<PQL	1.0
2,3-Dimethylbutane	<PQL	1.0
2-Methylpentane	<PQL	1.0
3-Methylpentane	<PQL	1.0
1-Hexene	<PQL	1.0
n-Hexane	<PQL	1.0
Methylcyclopentane	<PQL	1.0
2,4-Dimethylpentane	<PQL	1.0
Benzene	<PQL	1.0
Cyclohexane	<PQL	1.0
2-Methylhexane	<PQL	1.0





Atmospheric Analysis & Consulting, Inc.


Quality Control/Quality Assurance Report

PAMS Method Blank Analysis

Matrix : Air
Units : ppbC

Analysis Date : 11/13/2018
Report Date : 11/13/2018


<i>Client ID</i>	Method Blank	PQL
<i>AAC ID</i>	PAMS BLANK	
2,3-Dimethylpentane	<PQL	1.0
3-Methylhexane	<PQL	1.0
2,2,4-Trimethylpentane	<PQL	1.0
n-Heptane	<PQL	1.0
Methylcyclohexane	<PQL	1.0
2,3,4-Trimethylpentane	<PQL	1.0
Toluene	<PQL	1.0
2-Methylheptane	<PQL	1.0
3-Methylheptane	<PQL	1.0
n-Octane	<PQL	1.0
Ethylbenzene	<PQL	1.0
m/p-Xylenes	<PQL	1.0
Styrene	<PQL	1.0
o-Xylene	<PQL	1.0
Nonane	<PQL	1.0
Isopropylbenzene	<PQL	1.0
n-Propylbenzene	<PQL	1.0
m-Ethyltoluene	<PQL	1.0
p-Ethyltoluene	<PQL	1.0
1,3,5-Trimethylbenzene	<PQL	1.0
o-Ethyltoluene	<PQL	1.0
1,2,4-Trimethylbenzene	<PQL	1.0
n-Decane	<PQL	1.0
1,2,3-Trimethylbenzene	<PQL	1.0
m-Diethylbenzene	<PQL	1.0
p-Diethylbenzene	<PQL	1.0
n-Undecane	<PQL	1.0
n-Dodecane	<PQL	1.0
TNMHC (ppbC)	<PQL	20



 Marcus Hueppe
 Laboratory Director

Page 10





Atmospheric Analysis & Consulting, Inc.


Quality Control/Quality Assurance Report PAMS Duplicate Analysis

AAC ID : 181721-114582
Matrix : Air

Analysis Date : 11/13/2018
Report Date : 11/14/2018
Units : ppbC

Analyte	Sample Analysis	Sample Duplicate Analysis	%RPD
Ethylene	4.52	4.45	1.6
Acetylene	<PQL	<PQL	0.0
Ethane	13.6	13.3	2.2
Propylene	<PQL	<PQL	0.0
Propane	<PQL	<PQL	0.0
Isobutane	<PQL	<PQL	0.0
1-Butene	<PQL	<PQL	0.0
n-Butane	<PQL	<PQL	0.0
trans-2-Butene	<PQL	<PQL	0.0
cis-2-Butene	<PQL	<PQL	0.0
Isopentane	<PQL	<PQL	0.0
1-Pentene	<PQL	<PQL	0.0
n-Pentane	<PQL	<PQL	0.0
Isoprene	<PQL	<PQL	0.0
trans-2-Pentene	<PQL	<PQL	0.0
cis-2-Pentene	<PQL	<PQL	0.0
2,2-Dimethylbutane	<PQL	<PQL	0.0
Cyclopentane	<PQL	<PQL	0.0
2,3-Dimethylbutane	<PQL	<PQL	0.0
2-Methylpentane	<PQL	<PQL	0.0
3-Methylpentane	14.2	13.9	2.1
1-Hexene	<PQL	<PQL	0.0
n-Hexane	57.1	56.9	0.4
Methylcyclopentane	12.0	11.9	0.8
2,4-Dimethylpentane	<PQL	<PQL	0.0
Benzene	<PQL	<PQL	0.0
Cyclohexane	<PQL	<PQL	0.0
2-Methylhexane	<PQL	<PQL	0.0





Atmospheric Analysis & Consulting, Inc.

Quality Control/Quality Assurance Report PAMS Duplicate Analysis

AAC ID : 181721-114582
Matrix : Air

Analysis Date : 11/13/2018
Report Date : 11/14/2018
Units : ppbC

Analyte	Sample Analysis	Sample Duplicate Analysis	%RPD
2,3-Dimethylpentane	<PQL	<PQL	0.0
3-Methylhexane	<PQL	<PQL	0.0
2,2,4-Trimethylpentane	<PQL	<PQL	0.0
n-Heptane	<PQL	<PQL	0.0
Methylcyclohexane	<PQL	<PQL	0.0
2,3,4-Trimethylpentane	<PQL	<PQL	0.0
Toluene	<PQL	<PQL	0.0
2-Methylheptane	<PQL	<PQL	0.0
3-Methylheptane	<PQL	<PQL	0.0
n-Octane	<PQL	<PQL	0.0
Ethylbenzene	<PQL	<PQL	0.0
m/p-Xylenes	<PQL	<PQL	0.0
Styrene	<PQL	<PQL	0.0
o-Xylene	<PQL	<PQL	0.0
Nonane	<PQL	<PQL	0.0
Isopropylbenzene	<PQL	<PQL	0.0
n-Propylbenzene	<PQL	<PQL	0.0
m-Ethyltoluene	<PQL	<PQL	0.0
p-Ethyltoluene	<PQL	<PQL	0.0
1,3,5-Trimethylbenzene	<PQL	<PQL	0.0
o-Ethyltoluene	<PQL	<PQL	0.0
1,2,4-Trimethylbenzene	<PQL	<PQL	0.0
n-Decane	<PQL	<PQL	0.0
1,2,3-Trimethylbenzene	<PQL	<PQL	0.0
m-Diethylbenzene	<PQL	<PQL	0.0
p-Diethylbenzene	<PQL	<PQL	0.0
n-Undecane	<PQL	<PQL	0.0
n-Dodecane	<PQL	<PQL	0.0
Total PAMS (ppbC)	101	100	1.0
TNMHC (ppbc)	199	194	2.5


Marcus Hueppe
Laboratory Director

Page 12





2825 Verne Roberts Circle

Antioch, CA 94509

Phone (925) 680-4300 | Fax (925) 680-4416


CHAIN OF CUSTODY

#181713

Client / Project: Schnitzer Steel			Project / Sample Location: Shredder Exhaust Stack			Test / Analytical Method: EPA 25c & TO-15-TICs & TO-12 PAMS					
Project No.: 005AS-452603			Purchase Order No: PO#1027083			Special Analysis / Reporting Instructions: Please try to also identify: 2-methyl-2-butene, 1,3,3,3-Tetrafluoropropene [HFO-1234ze(E)], 1,1,1,2-Tetrafluoroethane [HFC-134a], and Pentafluoropropane [HFC-245fa]					
Send Analytical Report To: Antioch QA/QC: AntiochQA-QC@montrose-env.com rodell@montrose-env.com			Sampler or PM Signature: 								
Run / Sample No.	Date	Containers	Sample Fraction			Reagent	Lab / Sample ID No.				
1-POC	10/29/2018	1	(1) Summa Canister			--	114523				
2-POC	10/29/2018	1	(1) Summa Canister			--	114524				
3-POC	10/30/2018	1	(1) Summa Canister			--	114525				
4-POC	10/30/2018	1	(1) Summa Canister			--	114526				
5-POC	10/30/2018	1	(1) Summa Canister			--	114527				
6-POC	10/31/2018	1	(1) Summa Canister			--	114528				
Total Containers		6									
Relinquished by 			Date 11/1/16	Time	Received by FEDER			Date	Time		
Relinquished by FEDER			Date	Time	Received by			Date	Time		
Relinquished by			Date	Time	Received by Wick			Date 11/5/18	Time 0900		

Appendix C.3

Total Organic Carbon – EPA 25C Analyses



Atmospheric Analysis & Consulting, Inc.

CLIENT : Montrose AQS
PROJECT NAME : Schnitzer Steel
PROJECT NO. : 005AS-452603
AAC PROJECT NO. : 181713
REPORT DATE : 11/15/2018

On November 5, 2018, Atmospheric Analysis & Consulting, Inc. received six (6) Six-Liter Summa Canisters for TNMOC analysis by EPA 25C. Upon receipt, the samples were assigned unique Laboratory ID numbers as follows:

Client ID	Lab No.	Return Pressure (mmHgA)
1-POC	181713-114523	VOID
2-POC	181713-114524	744.6
3-POC	181713-114525	764.1
4-POC	181713-114526	651.2
5-POC	181713-114527	739.9
6-POC	181713-114528	514.2

All of the analyses mentioned above were performed in accordance with AAC's ISO/IEC 17025:2005 and NELAP approved Quality Assurance Plan. For detailed information pertaining to specific EPA, NCASI, ASTM and SCAQMD accreditations (Methods & Analytes), please visit our website at www.aacclab.com.


I certify that this data is technically accurate, complete, and in compliance with the terms and conditions of the contract. Sample 1-POC (114523) was voided due to the sample canister being at full vacuum upon receipt. No other problems were encountered during receiving, preparation, and/or analysis of these samples. The Laboratory Director or his/her designee, as verified by the following signature, has authorized release of the data contained in this hardcopy report.

If you have any questions or require further explanation of data results, please contact the undersigned.

Marcus Hueppe
Laboratory Director

This report consists of 4 pages.





Atmospheric Analysis & Consulting, Inc.

Laboratory Analysis Report

Client : Montrose AQS
 Project No. : 181713
 Matrix : AIR
 Units : ppmC


Sampling Date : 10/29-31/2018
 Receiving Date : 11/05/2018
 Analysis Date : 11/07/2018
 Report Date : 11/15/2018

EPA 25C


Reporting Limit: 3.0 ppmC		Canister Dilution Factor	Analysis Dilution Factor	TNMOC*	SRL (RL x DF's)
Client Sample ID	AAC ID				
2-POC	181713-114524	1.4	1.0	15.5	4.1
3-POC	181713-114525	1.3	1.0	22.1	4.0
4-POC	181713-114526	1.6	1.0	42.5	4.7
5-POC	181713-114527	1.4	1.0	23.7	4.1
6-POC	181713-114528	2.1	1.0	<SRL	6.4

Sample Reporting Limit (SRL) is equal to Reporting Limit x Analysis Dil. Fac x Canister Dil. Fac.

*Total Non-Methane Organic Carbon


 Marcus Hueppe
 Laboratory Director





Atmospheric Analysis & Consulting, Inc.

Quality Control/Quality Assurance Report

Analysis Date : 11/07/2018
 Analyst : DL
 Units : ppmv

Instrument ID: GCTCA#2-FID
 Calibration Date: 8/17/2018

I - Opening Calibration Verification Standard - Method 25C

Analyte	xRF	DRF	%RPD*
Propane	1531741	1573900	2.7

II - TNMOC Response Factor - Method 25C

Analyte	xRF	CV RF	CV dp RF	CV tp RF	Average RF	% RPD***
Propane	1531741	1573900	1589407	1525639	1562982	2.0

III - Method Blank - Method 25C

AAC ID	Analyte	Sample Result
MB	TNMOC	ND

IV - Laboratory Control Spike & Duplicate - Method 25C

AAC ID	Analyte	Spike Added	LCS Result	LCSD Result	LCS % Rec **	LCSD % Rec **	% RPD***
LCS/LCSD	Propane	203.4	211.1	202.6	103.8	99.6	4.1

V - Closing Calibration Verification Standard - Method 25C

Analyte	xCF	dCF	%RPD*
Propane	1531741	1525253	0.4

xCF - Average Calibration Factor from Initial Calibration Curve

dCF - Daily Calibration Factor

* Must be <15%

** Must be 90-110 %

*** Must be <20%


 Marcus Hueppe
 Laboratory Director

Page 3





Phone (925) 680-4300 | Fax (925) 680-4416

#181713

[illegible]

005AS-452603-RT-310

141 of 231


ONE CAP MISSING (#552)

8x GWS (2x UNWIZD) + 2x Flow
VOID 005

005AS437604 POC COC

Appendix C.4

Total Organic Carbon – TO-12 Analyses



Atmospheric Analysis & Consulting, Inc.

CLIENT : Montrose AQS
 PROJECT NAME : Schnitzer Steel - Shredder Exhaust Stack
 PROJECT NO. : 005AS-452603
 AAC PROJECT NO. : 181713
 REPORT DATE : 11/16/2018

On November 5, 2018, Atmospheric Analysis & Consulting, Inc. received five (5) Six-Liter Summa Canisters for TNMNEOC analysis by TO-12M/PAMS Protocol. Upon receipt each sample was assigned a unique Laboratory ID number as follows:

Client ID	Lab ID	Initial Pressure (mmHga)
1-POC	181713-114523	Void
2-POC	181713-114524	744.6
3-POC	181713-114525	764.1
4-POC	181713-114526	651.2
5-POC	181713-114527	739.9
6-POC	181713-114528	514.2

Sample 1-POC (181713-114523) was voided due to no sample being collected in the canister. Sample was received at full vacuum.

All of the analyses mentioned above were performed in accordance with AAC's ISO/IEC 17025:2005 and NELAP approved Quality Assurance Plan. For detailed information pertaining to specific EPA, NCASI, ASTM and SCAQMD accreditations (Methods & Analytes), please visit our website at www.aacalab.com.

I certify that this data is technically accurate, complete, and in compliance with the terms and conditions of the contract. No other problems were encountered during receiving, preparation, and/or analysis of these samples. The Laboratory Director or his/her designee, as verified by the following signature, has authorized release of the data contained in this hardcopy report.


If you have any questions or require further explanation of data results, please contact the undersigned.


 Marcus Hueppe
 Laboratory Director

This report consists of 8 pages.

Page 1





Atmospheric Analysis & Consulting, Inc.


Laboratory Analysis Report

TOTAL NON-METHANE NON-ETHANE ORGANIC COMPOUNDS BY PAMS PROTOCOL


CLIENT : Montrose AQS
PROJECT NUMBER : 181713
MATRIX : AIR

RECEIVING DATE : 11/05/2018
ANALYSIS DATE : 11/13/2018
REPORT DATE : 11/16/2018

Client Sample ID	AAC Sample ID	Sampling Date	Analysis Date	TNMNEOC as Carbon ppbC	Can Dilution Factor	Sample Dilution Factor	Sample RL (RL x DF's) ppbC	Method RL as Carbon ppbC
2-POC	181713-114524	10/29/2018	11/13/2018	12100	1.37	2.0	54.9	20
3-POC	181713-114525	10/30/2018	11/13/2018	19500	1.33	2.0	53.4	20
4-POC	181713-114526	10/30/2018	11/13/2018	20900	1.56	2.0	62.4	20
5-POC	181713-114527	10/30/2018	11/13/2018	7880	1.37	2.0	54.8	20
6-POC	181713-114528	10/31/2018	11/13/2018	3670	2.14	2.0	85.7	20



Marcus Hueppe
Laboratory Director



Atmospheric Analysis & Consulting, Inc.

Quality Control/Quality Assurance Report

PAMS Calibration Verification Analysis

Analysis Date : 11/13/2018
Analyst : JJG

Instrument ID : MS-01
Standard ID : PS101818-01
Calibration Date : 10/23/2018

Continuing Calibration Verification

Analyte	xRF	daily RF	%RPD*
Propane	765	784	2.4

* %RPD must be < 10%

Laboratory Control Spike Recovery

Analyte	Sample Conc.	Spike Added	Spike Res	Spike Dup Res	Spike % Rec **	Spike Dup % Rec **	RPD*** %
Propane	0.0	3.88	3.98	4.02	102.6	103.6	1.0


** Must be 80-120%

*** Must be < 25%



Marcus Hueppe
Laboratory Director





Atmospheric Analysis & Consulting, Inc.

Quality Control/Quality Assurance Report


PAMS Method Blank Analysis

Matrix : Air
Units : ppbC

Analysis Date : 11/13/2018
Report Date : 11/13/2018

<i>Client ID</i>	Method Blank	PQL
<i>AAC ID</i>	PAMS BLANK	
Ethylene	<PQL	1.0
Acetylene	<PQL	1.0
Ethane	<PQL	1.0
Propylene	<PQL	1.0
Propane	<PQL	1.0
Isobutane	<PQL	1.0
1-Butene	<PQL	1.0
n-Butane	<PQL	1.0
trans-2-Butene	<PQL	1.0
cis-2-Butene	<PQL	1.0
Isopentane	<PQL	1.0
1-Pentene	<PQL	1.0
n-Pentane	<PQL	1.0
Isoprene	<PQL	1.0
trans-2-Pentene	<PQL	1.0
cis-2-Pentene	<PQL	1.0
2,2-Dimethylbutane	<PQL	1.0
Cyclopentane	<PQL	1.0
2,3-Dimethylbutane	<PQL	1.0
2-Methylpentane	<PQL	1.0
3-Methylpentane	<PQL	1.0
1-Hexene	<PQL	1.0
n-Hexane	<PQL	1.0
Methylcyclopentane	<PQL	1.0
2,4-Dimethylpentane	<PQL	1.0
Benzene	<PQL	1.0
Cyclohexane	<PQL	1.0
2-Methylhexane	<PQL	1.0





Atmospheric Analysis & Consulting, Inc.


Quality Control/Quality Assurance Report

PAMS Method Blank Analysis

Matrix : Air
Units : ppbC

Analysis Date : 11/13/2018
Report Date : 11/13/2018


<i>Client ID</i> AAC ID	Method Blank PAMS BLANK	PQL
2,3-Dimethylpentane	<PQL	1.0
3-Methylhexane	<PQL	1.0
2,2,4-Trimethylpentane	<PQL	1.0
n-Heptane	<PQL	1.0
Methylcyclohexane	<PQL	1.0
2,3,4-Trimethylpentane	<PQL	1.0
Toluene	<PQL	1.0
2-Methylheptane	<PQL	1.0
3-Methylheptane	<PQL	1.0
n-Octane	<PQL	1.0
Ethylbenzene	<PQL	1.0
m/p-Xylenes	<PQL	1.0
Styrene	<PQL	1.0
o-Xylene	<PQL	1.0
Nonane	<PQL	1.0
Isopropylbenzene	<PQL	1.0
n-Propylbenzene	<PQL	1.0
m-Ethyltoluene	<PQL	1.0
p-Ethyltoluene	<PQL	1.0
1,3,5-Trimethylbenzene	<PQL	1.0
o-Ethyltoluene	<PQL	1.0
1,2,4-Trimethylbenzene	<PQL	1.0
n-Decane	<PQL	1.0
1,2,3-Trimethylbenzene	<PQL	1.0
m-Diethylbenzene	<PQL	1.0
p-Diethylbenzene	<PQL	1.0
n-Undecane	<PQL	1.0
n-Dodecane	<PQL	1.0
TNMHC (ppbC)	<PQL	20



 Marcus Hueppe
 Laboratory Director

Page 5





Atmospheric Analysis & Consulting, Inc.


Quality Control/Quality Assurance Report PAMS Duplicate Analysis

AAC ID : 181721-114582
Matrix : Air

Analysis Date : 11/13/2018
Report Date : 11/14/2018
Units : ppbC

Analyte	Sample Analysis	Sample Duplicate Analysis	%RPD
Ethylene	4.52	4.45	1.6
Acetylene	<PQL	<PQL	0.0
Ethane	13.6	13.3	2.2
Propylene	<PQL	<PQL	0.0
Propane	<PQL	<PQL	0.0
Isobutane	<PQL	<PQL	0.0
1-Butene	<PQL	<PQL	0.0
n-Butane	<PQL	<PQL	0.0
trans-2-Butene	<PQL	<PQL	0.0
cis-2-Butene	<PQL	<PQL	0.0
Isopentane	<PQL	<PQL	0.0
1-Pentene	<PQL	<PQL	0.0
n-Pentane	<PQL	<PQL	0.0
Isoprene	<PQL	<PQL	0.0
trans-2-Pentene	<PQL	<PQL	0.0
cis-2-Pentene	<PQL	<PQL	0.0
2,2-Dimethylbutane	<PQL	<PQL	0.0
Cyclopentane	<PQL	<PQL	0.0
2,3-Dimethylbutane	<PQL	<PQL	0.0
2-Methylpentane	<PQL	<PQL	0.0
3-Methylpentane	14.2	13.9	2.1
1-Hexene	<PQL	<PQL	0.0
n-Hexane	57.1	56.9	0.4
Methylcyclopentane	12.0	11.9	0.8
2,4-Dimethylpentane	<PQL	<PQL	0.0
Benzene	<PQL	<PQL	0.0
Cyclohexane	<PQL	<PQL	0.0
2-Methylhexane	<PQL	<PQL	0.0






Atmospheric Analysis & Consulting, Inc.

Quality Control/Quality Assurance Report PAMS Duplicate Analysis

AAC ID : 181721-114582
Matrix : Air


Analysis Date : 11/13/2018
Report Date : 11/14/2018
Units : ppbC

Analyte	Sample Analysis	Sample Duplicate Analysis	%RPD
2,3-Dimethylpentane	<PQL	<PQL	0.0
3-Methylhexane	<PQL	<PQL	0.0
2,2,4-Trimethylpentane	<PQL	<PQL	0.0
n-Heptane	<PQL	<PQL	0.0
Methylcyclohexane	<PQL	<PQL	0.0
2,3,4-Trimethylpentane	<PQL	<PQL	0.0
Toluene	<PQL	<PQL	0.0
2-Methylheptane	<PQL	<PQL	0.0
3-Methylheptane	<PQL	<PQL	0.0
n-Octane	<PQL	<PQL	0.0
Ethylbenzene	<PQL	<PQL	0.0
m/p-Xylenes	<PQL	<PQL	0.0
Styrene	<PQL	<PQL	0.0
o-Xylene	<PQL	<PQL	0.0
Nonane	<PQL	<PQL	0.0
Isopropylbenzene	<PQL	<PQL	0.0
n-Propylbenzene	<PQL	<PQL	0.0
m-Ethyltoluene	<PQL	<PQL	0.0
p-Ethyltoluene	<PQL	<PQL	0.0
1,3,5-Trimethylbenzene	<PQL	<PQL	0.0
o-Ethyltoluene	<PQL	<PQL	0.0
1,2,4-Trimethylbenzene	<PQL	<PQL	0.0
n-Decane	<PQL	<PQL	0.0
1,2,3-Trimethylbenzene	<PQL	<PQL	0.0
m-Diethylbenzene	<PQL	<PQL	0.0
p-Diethylbenzene	<PQL	<PQL	0.0
n-Undecane	<PQL	<PQL	0.0
n-Dodecane	<PQL	<PQL	0.0
Total PAMS (ppbC)	101	100	1.0
TNMHC (ppbc)	199	194	2.5




Marcus Hueppe
Laboratory Director

Page 7





| 81713

Client / Project: Schnitzer Steel			Project / Sample Location: Shredder Exhaust Stack			Test / Analytical Method: EPA 25c & TO-15-TICs & TO-12 PAMS		
Project No.: 005AS-452603			Purchase Order No: PO#1027083			Special Analysis / Reporting Instructions: Please try to also identify: 2-methyl-2-butene, 1,3,3,3-Tetrafluoropropene [HFO-1234ze(E)], 1,1,1,2-Tetrafluoroethane [HFC-134a], and Pentafluoropropane [HFC-245fa]		
Send Analytical Report To: Antioch QA/QC: AntiochQA-QC@montrose-env.com rodell@montrose-env.com			Sampler or PM Signature: 					
Run / Sample No.	Date	Containers	Sample Fraction			Reagent	Lab / Sample ID No.	
1-POC	10/29/2018	1	(1) Summa Canister			--	114523	
2-POC	10/29/2018	1	(1) Summa Canister			--	114524	
3-POC	10/30/2018	1	(1) Summa Canister			--	114525	
4-POC	10/30/2018	1	(1) Summa Canister			--	114526	
5-POC	10/30/2018	1	(1) Summa Canister			--	114527	
6-POC	10/31/2018	1	(1) Summa Canister			--	114528	
Total Containers		6						
Relinquished by 			Date 11/1/16	Time	Received by FEDER		Date	Time
Relinquished by FEDER			Date	Time	Received by		Date	Time
Relinquished by			Date	Time	Received by Wick		Date 11/5/18	Time 0900

Appendix C.5

PolyChlorinated Biphenyls Analyses



November 27, 2018

Vista Work Order No. 1803396

Mr. Robert Odell
Montrose Environmental Company
2825 Verne Roberts Circle
Antioch, CA 94509

Dear Mr. Odell,

Enclosed are the results for the sample set received at Vista Analytical Laboratory on November 01, 2018 under your Project Name 'Schnitzer Steel 005AS-452603'.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at mmaier@vista-analytical.com.

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

Martha Maier
Laboratory Director



Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.

Vista Work Order No. 1803396

Case Narrative

Sample Condition on Receipt:

Eight MM5 samples were received in good condition and within the method temperature requirements. The samples were received and stored securely in accordance with Vista standard operating procedures and EPA methodology. As requested, the reagent blanks were placed on hold.

Analytical Notes:

CARB Method 428

These samples were extracted and analyzed for total homologue PCBs by CARB Method 428 using a ZB-1 GC column.

Holding Times

The method holding time criteria were met for the samples.

Quality Control

The Initial Calibration and Continuing Calibration Verifications met the method acceptance criteria.

A Method Blank and Ongoing Precision and Recovery sample (OPR) were extracted and analyzed with the preparation batch. No analytes were detected above the reporting limits in the Method Blank. The OPR recoveries were within the method acceptance criteria.

The labeled standard recoveries outside the acceptance criteria are listed in the table below.

QC Anomalies

LabNumber	SampleName	Analysis	Analyte	Flag	%Rec
1803396-01	1-PCB	CARB Method 428	13C-PCB-1	H	31.0
1803396-01	1-PCB	CARB Method 428	13C-PCB-3	H	30.9
1803396-01	1-PCB	CARB Method 428	13C-PCB-4	H	130
1803396-01	1-PCB	CARB Method 428	13C-PCB-209	H	133
1803396-02	2-PCB	CARB Method 428	13C-PCB-1	H	31.4
1803396-02	2-PCB	CARB Method 428	13C-PCB-3	H	29.4
1803396-02	2-PCB	CARB Method 428	13C-PCB-209	H	132
1803396-03	3-PCB	CARB Method 428	13C-PCB-3	H	39.0
1803396-04	4-PCB	CARB Method 428	13C-PCB-1	H	33.3
1803396-04	4-PCB	CARB Method 428	13C-PCB-3	H	31.3
1803396-05	5-PCB	CARB Method 428	13C-PCB-1	H	28.6
1803396-05	5-PCB	CARB Method 428	13C-PCB-3	H	30.0
1803396-06	6-PCB	CARB Method 428	13C-PCB-1	H	30.3
1803396-06	6-PCB	CARB Method 428	13C-PCB-3	H	29.4

H = Recovery was outside laboratory acceptance criteria.

TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	4
Sample Inventory.....	5
Analytical Results.....	7
Qualifiers.....	26
Certifications.....	27
Sample Receipt.....	30

Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1803396-01	1-PCB	29-Oct-18 00:00	01-Nov-18 15:16	Filter XAD FH Rinse BH Rinse IMP Rinse IMP Contents
1803396-02	2-PCB	29-Oct-18 00:00	01-Nov-18 15:16	Filter XAD FH Rinse BH Rinse IMP Rinse IMP Contents
1803396-03	3-PCB	30-Oct-18 00:00	01-Nov-18 15:16	Filter XAD FH Rinse BH Rinse IMP Rinse IMP Contents
1803396-04	4-PCB	30-Oct-18 00:00	01-Nov-18 15:16	Filter XAD FH Rinse BH Rinse IMP Rinse IMP Contents
1803396-05	5-PCB	30-Oct-18 00:00	01-Nov-18 15:16	Filter XAD FH Rinse BH Rinse IMP Rinse IMP Contents
1803396-06	6-PCB	31-Oct-18 00:00	01-Nov-18 15:16	Filter XAD FH Rinse BH Rinse IMP Rinse IMP Contents
1803396-07	FB-PCB	31-Oct-18 00:00	01-Nov-18 15:16	Filter XAD FH Rinse

Vista Project: 1803396

Client Project: Schnitzer Steel 005AS-452603

Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1803396-07	FB-PCB	31-Oct-18 00:00	01-Nov-18 15:16	BH Rinse IMP Rinse IMP Contents
1803396-08	Reagent Blanks	31-Oct-18 00:00	01-Nov-18 15:16	Rinse Methanol Rinse Toluene Rinse MeCl2 Rinse Other

ANALYTICAL RESULTS

Sample ID: Method Blank					CARB Method 428			
Matrix: Air		QC Batch: B8K0070 Date Extracted: 12-Nov-2018 7:33			Lab Sample: B8K0070-BLK1 Date Analyzed: 14-Nov-18 18:29 Column: ZB-1			
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	ND	0.0125			IS 13C-PCB-1	43.8	40-120	
Total diCB	ND	0.0387			IS 13C-PCB-3	46.7	40-120	
Total triCB	ND	0.00973			IS 13C-PCB-4	65.9	40-120	
Total tetraCB	ND	0.0130			IS 13C-PCB-11	75.1	40-120	
Total pentaCB	ND	0.0211			IS 13C-PCB-9	67.6	40-120	
Total hexaCB	ND	0.0154			IS 13C-PCB-19	54.3	40-120	
Total heptaCB	ND	0.00698			IS 13C-PCB-28	67.6	40-120	
Total octaCB	ND	0.0103			IS 13C-PCB-32	59.5	40-120	
Total nonaCB	ND	0.00824			IS 13C-PCB-37	73.7	40-120	
DecaCB	ND	0.00551			IS 13C-PCB-47	81.0	40-120	
Total PCB	ND	0.0387			IS 13C-PCB-52	87.4	40-120	
					IS 13C-PCB-54	91.5	40-120	
					IS 13C-PCB-70	89.0	40-120	
					IS 13C-PCB-77	82.2	40-120	
					IS 13C-PCB-80	87.5	40-120	
					IS 13C-PCB-81	84.5	40-120	
					IS 13C-PCB-95	80.6	40-120	
					IS 13C-PCB-97	86.2	40-120	
					IS 13C-PCB-101	86.0	40-120	
					IS 13C-PCB-104	83.1	40-120	
					IS 13C-PCB-105	96.7	40-120	
					IS 13C-PCB-114	93.3	40-120	
					IS 13C-PCB-118	87.0	40-120	
					IS 13C-PCB-123	88.8	40-120	
					IS 13C-PCB-126	93.4	40-120	
					IS 13C-PCB-127	97.4	40-120	
					IS 13C-PCB-138	89.1	40-120	
					IS 13C-PCB-141	90.9	40-120	
					IS 13C-PCB-153	88.3	40-120	
					IS 13C-PCB-155	90.8	40-120	
					IS 13C-PCB-156	91.6	40-120	
					IS 13C-PCB-157	91.1	40-120	
					IS 13C-PCB-159	91.5	40-120	
					IS 13C-PCB-167	90.5	40-120	
					IS 13C-PCB-169	87.3	40-120	
					IS 13C-PCB-170	88.8	40-120	
					IS 13C-PCB-180	89.6	40-120	

Sample ID: Method Blank		CARB Method 428			
Matrix: Air	QC Batch: B8K0070 Date Extracted: 12-Nov-2018 7:33	Lab Sample: B8K0070-BLK1 Date Analyzed: 14-Nov-18 18:29 Column: ZB-1			
		Labeled Standard	%R	LCL-UCL	Qualifiers
		IS 13C-PCB-188	84.3	40-120	
		IS 13C-PCB-189	87.7	40-120	
		IS 13C-PCB-194	82.1	40-120	
		IS 13C-PCB-202	89.7	40-120	
		IS 13C-PCB-206	84.5	40-120	
		IS 13C-PCB-208	83.7	40-120	
		IS 13C-PCB-209	90.0	40-120	

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Results reported to RL.

Sample ID: OPR					CARB Method 428			
Matrix: Air		QC Batch: B8K0070 Date Extracted: 12-Nov-2018 7:33			Lab Sample: B8K0070-BS1 Date Analyzed: 14-Nov-18 16:19 Column: ZB-1			
Analyte	Amt Found (ng/Sample)	Spike Amt	%R	Limits	Labeled Standard		%R	LCL-UCL
PCB-3	6.00	5.00	120	60 - 140	IS	13C-PCB-1	50.3	40 - 120
PCB-15	5.56	5.00	111	60 - 140	IS	13C-PCB-3	52.3	40 - 120
PCB-28	5.81	5.00	116	60 - 140	IS	13C-PCB-4	74.5	40 - 120
PCB-77	5.28	5.00	106	60 - 140	IS	13C-PCB-11	82.3	40 - 120
PCB-106/118	9.54	10.0	95.4	60 - 140	IS	13C-PCB-9	77.2	40 - 120
PCB-156	5.10	5.00	102	60 - 140	IS	13C-PCB-19	61.0	40 - 120
PCB-180	5.10	5.00	102	60 - 140	IS	13C-PCB-28	73.9	40 - 120
PCB-202	5.30	5.00	106	60 - 140	IS	13C-PCB-32	60.8	40 - 120
PCB-207	5.04	5.00	101	60 - 140	IS	13C-PCB-37	80.9	40 - 120
PCB-209	5.01	5.00	100	60 - 140	IS	13C-PCB-47	89.9	40 - 120
					IS	13C-PCB-52	94.1	40 - 120
					IS	13C-PCB-54	97.6	40 - 120
					IS	13C-PCB-70	96.4	40 - 120
					IS	13C-PCB-77	93.7	40 - 120
					IS	13C-PCB-80	96.0	40 - 120
					IS	13C-PCB-81	99.2	40 - 120
					IS	13C-PCB-95	89.6	40 - 120
					IS	13C-PCB-97	90.5	40 - 120
					IS	13C-PCB-101	90.6	40 - 120
					IS	13C-PCB-104	91.6	40 - 120
					IS	13C-PCB-105	108	40 - 120
					IS	13C-PCB-114	108	40 - 120
					IS	13C-PCB-118	95.6	40 - 120
					IS	13C-PCB-123	96.4	40 - 120
					IS	13C-PCB-126	106	40 - 120
					IS	13C-PCB-127	105	40 - 120
					IS	13C-PCB-138	94.8	40 - 120
					IS	13C-PCB-141	96.3	40 - 120
					IS	13C-PCB-153	95.9	40 - 120
					IS	13C-PCB-155	98.4	40 - 120
					IS	13C-PCB-156	98.1	40 - 120
					IS	13C-PCB-157	97.3	40 - 120
					IS	13C-PCB-159	98.3	40 - 120
					IS	13C-PCB-167	95.9	40 - 120
					IS	13C-PCB-169	95.0	40 - 120
					IS	13C-PCB-170	98.0	40 - 120
					IS	13C-PCB-180	95.5	40 - 120
					IS	13C-PCB-188	94.9	40 - 120

Sample ID: OPR					CARB Method 428			
Matrix: Air		QC Batch: B8K0070 Date Extracted: 12-Nov-2018 7:33			Lab Sample: B8K0070-BS1 Date Analyzed: 14-Nov-18 16:19 Column: ZB-1			
Analyte	Amt Found (ng/Sample)	Spike Amt	%R	Limits	Labeled Standard		%R	LCL-UCL
					IS	13C-PCB-189	101	40 - 120
					IS	13C-PCB-194	89.2	40 - 120
					IS	13C-PCB-202	92.7	40 - 120
					IS	13C-PCB-206	89.6	40 - 120
					IS	13C-PCB-208	85.7	40 - 120
					IS	13C-PCB-209	90.4	40 - 120

LCL-UCL - Lower control limit - upper control limit

Sample ID: 1-PCB					CARB Method 428			
Client Data			Sample Data		Laboratory Data			
Name:	Montrose Environmental Company		Matrix:	Air Train	Lab Sample:	1803396-01	Date Received:	11/1/2018 3:16:00PM
Project:	Schnitzer Steel 005AS-452603				QC Batch:	B8K0070	Date Extracted:	12-Nov-18 07:33
Date Collected:	10/29/2018 12:00:00AM				Date Analyzed:	14-Nov-18 20:39	Column:	ZB-1
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	57.8				IS 13C-PCB-1	31.0	40 - 120	H
Total diCB	627				IS 13C-PCB-3	30.9	40 - 120	H
Total triCB	1200				IS 13C-PCB-4	130	40 - 120	H
Total tetraCB	288				IS 13C-PCB-11	87.2	40 - 120	
Total pentaCB	28.9				IS 13C-PCB-9	81.8	40 - 120	
Total hexaCB	8.99				IS 13C-PCB-19	48.1	40 - 120	
Total heptaCB	5.87				IS 13C-PCB-28	76.3	40 - 120	
Total octaCB	1.42				IS 13C-PCB-32	59.6	40 - 120	
Total nonaCB	ND	0.0341			IS 13C-PCB-37	89.7	40 - 120	
DecaCB	ND	0.0328			IS 13C-PCB-47	97.6	40 - 120	
Total PCB	2220				IS 13C-PCB-52	93.0	40 - 120	
					IS 13C-PCB-54	86.2	40 - 120	
					IS 13C-PCB-70	102	40 - 120	
					IS 13C-PCB-77	90.8	40 - 120	
					IS 13C-PCB-80	105	40 - 120	
					IS 13C-PCB-81	90.1	40 - 120	
					IS 13C-PCB-95	100	40 - 120	
					IS 13C-PCB-97	99.3	40 - 120	
					IS 13C-PCB-101	95.7	40 - 120	
					IS 13C-PCB-104	98.2	40 - 120	
					IS 13C-PCB-105	89.4	40 - 120	
					IS 13C-PCB-114	98.6	40 - 120	
					IS 13C-PCB-118	85.1	40 - 120	
					IS 13C-PCB-123	88.2	40 - 120	
					IS 13C-PCB-126	84.3	40 - 120	
					IS 13C-PCB-127	91.8	40 - 120	
					IS 13C-PCB-138	84.5	40 - 120	
					IS 13C-PCB-141	90.1	40 - 120	
					IS 13C-PCB-153	94.9	40 - 120	
					IS 13C-PCB-155	97.8	40 - 120	
					IS 13C-PCB-156	85.3	40 - 120	
					IS 13C-PCB-157	91.8	40 - 120	
					IS 13C-PCB-159	91.6	40 - 120	
					IS 13C-PCB-167	87.9	40 - 120	
					IS 13C-PCB-169	69.3	40 - 120	
					IS 13C-PCB-170	83.1	40 - 120	
					IS 13C-PCB-180	94.2	40 - 120	
					IS 13C-PCB-188	98.0	40 - 120	
					IS 13C-PCB-189	72.3	40 - 120	

Sample ID: 1-PCB				CARB Method 428			
Client Data		Sample Data		Laboratory Data			
Name:	Montrose Environmental Company	Matrix:	Air Train	Lab Sample:	1803396-01	Date Received:	11/1/2018 3:16:00PM
Project:	Schnitzer Steel 005AS-452603			QC Batch:	B8K0070	Date Extracted:	12-Nov-18 07:33
Date Collected:	10/29/2018 12:00:00AM			Date Analyzed:	14-Nov-18 20:39	Column:	ZB-1
				Labeled Standard	%R	LCL-UCL	Qualifiers
				IS	13C-PCB-194	88.1	40 - 120
				IS	13C-PCB-202	74.2	40 - 120
				IS	13C-PCB-206	105	40 - 120
				IS	13C-PCB-208	95.0	40 - 120
				IS	13C-PCB-209	133	40 - 120 H
				PS	13C-PCB-79	86.1	60 - 140
				PS	13C-PCB-178	84.4	60 - 140

DL - Sample specific estimated detection limit
EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit
Results reported to RL.

Sample ID: 2-PCB					CARB Method 428			
Client Data			Sample Data		Laboratory Data			
Name:	Montrose Environmental Company		Matrix:	Air Train	Lab Sample:	1803396-02	Date Received:	11/1/2018 3:16:00PM
Project:	Schnitzer Steel 005AS-452603				QC Batch:	B8K0070	Date Extracted:	12-Nov-18 07:33
Date Collected:	10/29/2018 12:00:00AM				Date Analyzed:	14-Nov-18 21:44	Column:	ZB-1
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	27.6				IS 13C-PCB-1	31.4	40 - 120	H
Total diCB	334				IS 13C-PCB-3	29.4	40 - 120	H
Total triCB	542				IS 13C-PCB-4	67.0	40 - 120	
Total tetraCB	131				IS 13C-PCB-11	99.2	40 - 120	
Total pentaCB	15.3				IS 13C-PCB-9	85.1	40 - 120	
Total hexaCB	3.23				IS 13C-PCB-19	48.9	40 - 120	
Total heptaCB	1.10				IS 13C-PCB-28	83.1	40 - 120	
Total octaCB	0.124		0.384		IS 13C-PCB-32	52.0	40 - 120	
Total nonaCB	ND	0.0370			IS 13C-PCB-37	74.4	40 - 120	
DecaCB	ND	0.00900			IS 13C-PCB-47	95.0	40 - 120	
Total PCB	1050				IS 13C-PCB-52	88.8	40 - 120	
					IS 13C-PCB-54	93.4	40 - 120	
					IS 13C-PCB-70	104	40 - 120	
					IS 13C-PCB-77	90.7	40 - 120	
					IS 13C-PCB-80	97.0	40 - 120	
					IS 13C-PCB-81	99.5	40 - 120	
					IS 13C-PCB-95	105	40 - 120	
					IS 13C-PCB-97	100	40 - 120	
					IS 13C-PCB-101	102	40 - 120	
					IS 13C-PCB-104	101	40 - 120	
					IS 13C-PCB-105	87.5	40 - 120	
					IS 13C-PCB-114	99.8	40 - 120	
					IS 13C-PCB-118	93.9	40 - 120	
					IS 13C-PCB-123	93.0	40 - 120	
					IS 13C-PCB-126	84.3	40 - 120	
					IS 13C-PCB-127	82.7	40 - 120	
					IS 13C-PCB-138	93.0	40 - 120	
					IS 13C-PCB-141	95.3	40 - 120	
					IS 13C-PCB-153	99.5	40 - 120	
					IS 13C-PCB-155	93.2	40 - 120	
					IS 13C-PCB-156	91.6	40 - 120	
					IS 13C-PCB-157	101	40 - 120	
					IS 13C-PCB-159	97.0	40 - 120	
					IS 13C-PCB-167	92.0	40 - 120	
					IS 13C-PCB-169	72.8	40 - 120	
					IS 13C-PCB-170	90.7	40 - 120	
					IS 13C-PCB-180	102	40 - 120	
					IS 13C-PCB-188	102	40 - 120	
					IS 13C-PCB-189	80.9	40 - 120	

Sample ID: 2-PCB		CARB Method 428	
Client Data Name: Montrose Environmental Company Project: Schnitzer Steel 005AS-452603 Date Collected: 10/29/2018 12:00:00AM		Sample Data Matrix: Air Train	
		Laboratory Data Lab Sample: 1803396-02 Date Received: 11/1/2018 3:16:00PM QC Batch: B8K0070 Date Extracted: 12-Nov-18 07:33 Date Analyzed: 14-Nov-18 21:44 Column: ZB-1	
		Labeled Standard	%R
		IS 13C-PCB-194	99.2
		IS 13C-PCB-202	77.3
		IS 13C-PCB-206	108
		IS 13C-PCB-208	99.8
		IS 13C-PCB-209	132
		PS 13C-PCB-79	98.4
		PS 13C-PCB-178	101

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Results reported to RL.

Sample ID: 3-PCB					CARB Method 428			
Client Data			Sample Data		Laboratory Data			
Name:	Montrose Environmental Company		Matrix:	Air Train	Lab Sample:	1803396-03	Date Received:	11/1/2018 3:16:00PM
Project:	Schnitzer Steel 005AS-452603				QC Batch:	B8K0070	Date Extracted:	12-Nov-18 07:33
Date Collected:	10/30/2018 12:00:00AM				Date Analyzed:	15-Nov-18 05:32	Column:	ZB-1
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	19.8				IS 13C-PCB-1	41.9	40 - 120	
Total diCB	311				IS 13C-PCB-3	39.0	40 - 120	H
Total triCB	418		446		IS 13C-PCB-4	68.9	40 - 120	
Total tetraCB	139				IS 13C-PCB-11	89.9	40 - 120	
Total pentaCB	13.3				IS 13C-PCB-9	84.1	40 - 120	
Total hexaCB	2.10				IS 13C-PCB-19	68.9	40 - 120	
Total heptaCB	0.314				IS 13C-PCB-28	87.2	40 - 120	
Total octaCB	0.0746				IS 13C-PCB-32	81.3	40 - 120	
Total nonaCB	ND	0.0227			IS 13C-PCB-37	99.1	40 - 120	
DecaCB	ND	0.0115			IS 13C-PCB-47	91.6	40 - 120	
Total PCB	904				IS 13C-PCB-52	89.8	40 - 120	
					IS 13C-PCB-54	75.4	40 - 120	
					IS 13C-PCB-70	94.0	40 - 120	
					IS 13C-PCB-77	89.2	40 - 120	
					IS 13C-PCB-80	100	40 - 120	
					IS 13C-PCB-81	94.7	40 - 120	
					IS 13C-PCB-95	97.9	40 - 120	
					IS 13C-PCB-97	97.4	40 - 120	
					IS 13C-PCB-101	94.8	40 - 120	
					IS 13C-PCB-104	92.9	40 - 120	
					IS 13C-PCB-105	113	40 - 120	
					IS 13C-PCB-114	118	40 - 120	
					IS 13C-PCB-118	91.4	40 - 120	
					IS 13C-PCB-123	92.5	40 - 120	
					IS 13C-PCB-126	109	40 - 120	
					IS 13C-PCB-127	113	40 - 120	
					IS 13C-PCB-138	87.2	40 - 120	
					IS 13C-PCB-141	92.9	40 - 120	
					IS 13C-PCB-153	97.0	40 - 120	
					IS 13C-PCB-155	107	40 - 120	
					IS 13C-PCB-156	88.8	40 - 120	
					IS 13C-PCB-157	96.7	40 - 120	
					IS 13C-PCB-159	94.7	40 - 120	
					IS 13C-PCB-167	89.4	40 - 120	
					IS 13C-PCB-169	74.7	40 - 120	
					IS 13C-PCB-170	91.7	40 - 120	
					IS 13C-PCB-180	99.3	40 - 120	
					IS 13C-PCB-188	98.9	40 - 120	
					IS 13C-PCB-189	83.9	40 - 120	

Sample ID: 3-PCB		CARB Method 428	
Client Data Name: Montrose Environmental Company Project: Schnitzer Steel 005AS-452603 Date Collected: 10/30/2018 12:00:00AM		Sample Data Matrix: Air Train	
		Laboratory Data Lab Sample: 1803396-03 Date Received: 11/1/2018 3:16:00PM QC Batch: B8K0070 Date Extracted: 12-Nov-18 07:33 Date Analyzed: 15-Nov-18 05:32 Column: ZB-1	
		Labeled Standard	%R
		IS 13C-PCB-194	93.5
		IS 13C-PCB-202	106
		IS 13C-PCB-206	95.1
		IS 13C-PCB-208	84.2
		IS 13C-PCB-209	108
		PS 13C-PCB-79	98.5
		PS 13C-PCB-178	60.7

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Results reported to RL.

Sample ID: 4-PCB					CARB Method 428			
Client Data Name: Montrose Environmental Company Project: Schnitzer Steel 005AS-452603 Date Collected: 10/30/2018 12:00:00AM			Sample Data Matrix: Air Train		Laboratory Data Lab Sample: 1803396-04 Date Received: 11/1/2018 3:16:00PM QC Batch: B8K0070 Date Extracted: 12-Nov-18 07:33 Date Analyzed: 15-Nov-18 06:37 Column: ZB-1 16-Nov-18 10:52 Column: ZB-1			
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	2560				IS 13C-PCB-1	33.3	40 - 120	H
Total diCB	12000				IS 13C-PCB-3	31.3	40 - 120	H
Total triCB	9400				IS 13C-PCB-4	80.3	40 - 120	D
Total tetraCB	2240				IS 13C-PCB-11	90.2	40 - 120	
Total pentaCB	677				IS 13C-PCB-9	83.1	40 - 120	D
Total hexaCB	252				IS 13C-PCB-19	58.9	40 - 120	
Total heptaCB	29.8				IS 13C-PCB-28	74.0	40 - 120	
Total octaCB	3.15				IS 13C-PCB-32	74.2	40 - 120	D
Total nonaCB	0.602				IS 13C-PCB-37	98.7	40 - 120	
DecaCB	0.0752				IS 13C-PCB-47	83.7	40 - 120	
Total PCB	27200				IS 13C-PCB-52	79.2	40 - 120	
					IS 13C-PCB-54	65.8	40 - 120	
					IS 13C-PCB-70	86.6	40 - 120	
					IS 13C-PCB-77	93.5	40 - 120	
					IS 13C-PCB-80	92.2	40 - 120	
					IS 13C-PCB-81	95.7	40 - 120	
					IS 13C-PCB-95	86.2	40 - 120	
					IS 13C-PCB-97	90.9	40 - 120	
					IS 13C-PCB-101	90.5	40 - 120	
					IS 13C-PCB-104	80.7	40 - 120	
					IS 13C-PCB-105	114	40 - 120	
					IS 13C-PCB-114	109	40 - 120	
					IS 13C-PCB-118	96.5	40 - 120	
					IS 13C-PCB-123	92.6	40 - 120	
					IS 13C-PCB-126	111	40 - 120	
					IS 13C-PCB-127	111	40 - 120	
					IS 13C-PCB-138	89.9	40 - 120	
					IS 13C-PCB-141	91.0	40 - 120	
					IS 13C-PCB-153	88.4	40 - 120	
					IS 13C-PCB-155	89.8	40 - 120	
					IS 13C-PCB-156	99.2	40 - 120	
					IS 13C-PCB-157	106	40 - 120	
					IS 13C-PCB-159	99.2	40 - 120	
					IS 13C-PCB-167	95.8	40 - 120	
					IS 13C-PCB-169	93.2	40 - 120	
					IS 13C-PCB-170	98.4	40 - 120	
					IS 13C-PCB-180	96.3	40 - 120	
					IS 13C-PCB-188	89.1	40 - 120	
					IS 13C-PCB-189	96.4	40 - 120	

Sample ID: 4-PCB		CARB Method 428	
Client Data Name: Montrose Environmental Company Project: Schnitzer Steel 005AS-452603 Date Collected: 10/30/2018 12:00:00AM		Sample Data Matrix: Air Train	
		Laboratory Data Lab Sample: 1803396-04 Date Received: 11/1/2018 3:16:00PM QC Batch: B8K0070 Date Extracted: 12-Nov-18 07:33 Date Analyzed: 15-Nov-18 06:37 Column: ZB-1 16-Nov-18 10:52 Column: ZB-1	
		Labeled Standard	%R
		IS 13C-PCB-194	90.5
		IS 13C-PCB-202	96.2
		IS 13C-PCB-206	86.9
		IS 13C-PCB-208	83.2
		IS 13C-PCB-209	91.2
		PS 13C-PCB-79	91.9
		PS 13C-PCB-178	60.6

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Results reported to RL.

Sample ID: 5-PCB					CARB Method 428			
Client Data Name: Montrose Environmental Company Project: Schnitzer Steel 005AS-452603 Date Collected: 10/30/2018 12:00:00AM			Sample Data Matrix: Air Train		Laboratory Data Lab Sample: 1803396-05 Date Received: 11/1/2018 3:16:00PM QC Batch: B8K0070 Date Extracted: 12-Nov-18 07:33 Date Analyzed: 15-Nov-18 07:42 Column: ZB-1 15-Nov-18 18:31 Column: ZB-1			
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	2980				IS 13C-PCB-1	28.6	40 - 120	H
Total diCB	16100				IS 13C-PCB-3	30.0	40 - 120	H
Total triCB	15700				IS 13C-PCB-4	72.1	40 - 120	D
Total tetraCB	3980				IS 13C-PCB-11	85.3	40 - 120	
Total pentaCB	564				IS 13C-PCB-9	78.6	40 - 120	D
Total hexaCB	176				IS 13C-PCB-19	51.9	40 - 120	
Total heptaCB	30.5				IS 13C-PCB-28	68.4	40 - 120	
Total octaCB	7.68				IS 13C-PCB-32	69.3	40 - 120	D
Total nonaCB	2.23				IS 13C-PCB-37	89.1	40 - 120	
DecaCB	0.250				IS 13C-PCB-47	68.1	40 - 120	
Total PCB	39500				IS 13C-PCB-52	65.6	40 - 120	
					IS 13C-PCB-54	53.9	40 - 120	
					IS 13C-PCB-70	76.9	40 - 120	
					IS 13C-PCB-77	86.7	40 - 120	
					IS 13C-PCB-80	81.2	40 - 120	
					IS 13C-PCB-81	82.9	40 - 120	
					IS 13C-PCB-95	74.6	40 - 120	
					IS 13C-PCB-97	81.1	40 - 120	
					IS 13C-PCB-101	76.5	40 - 120	
					IS 13C-PCB-104	69.1	40 - 120	
					IS 13C-PCB-105	99.5	40 - 120	
					IS 13C-PCB-114	97.8	40 - 120	
					IS 13C-PCB-118	82.4	40 - 120	
					IS 13C-PCB-123	82.6	40 - 120	
					IS 13C-PCB-126	100	40 - 120	
					IS 13C-PCB-127	97.2	40 - 120	
					IS 13C-PCB-138	79.5	40 - 120	
					IS 13C-PCB-141	79.8	40 - 120	
					IS 13C-PCB-153	81.2	40 - 120	
					IS 13C-PCB-155	77.3	40 - 120	
					IS 13C-PCB-156	96.6	40 - 120	
					IS 13C-PCB-157	97.4	40 - 120	
					IS 13C-PCB-159	89.7	40 - 120	
					IS 13C-PCB-167	85.4	40 - 120	
					IS 13C-PCB-169	83.5	40 - 120	
					IS 13C-PCB-170	87.1	40 - 120	
					IS 13C-PCB-180	89.3	40 - 120	
					IS 13C-PCB-188	78.6	40 - 120	
					IS 13C-PCB-189	82.4	40 - 120	

Sample ID: 5-PCB		CARB Method 428	
Client Data Name: Montrose Environmental Company Project: Schnitzer Steel 005AS-452603 Date Collected: 10/30/2018 12:00:00AM		Sample Data Matrix: Air Train	
		Laboratory Data Lab Sample: 1803396-05 Date Received: 11/1/2018 3:16:00PM QC Batch: B8K0070 Date Extracted: 12-Nov-18 07:33 Date Analyzed: 15-Nov-18 07:42 Column: ZB-1 15-Nov-18 18:31 Column: ZB-1	
		Labeled Standard	%R
		IS 13C-PCB-194	81.5
		IS 13C-PCB-202	83.2
		IS 13C-PCB-206	78.5
		IS 13C-PCB-208	73.0
		IS 13C-PCB-209	82.1
		PS 13C-PCB-79	79.3
		PS 13C-PCB-178	82.7

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Results reported to RL.

Sample ID: 6-PCB					CARB Method 428			
Client Data			Sample Data		Laboratory Data			
Name:	Montrose Environmental Company		Matrix:	Air Train	Lab Sample:	1803396-06	Date Received:	11/1/2018 3:16:00PM
Project:	Schnitzer Steel 005AS-452603				QC Batch:	B8K0070	Date Extracted:	12-Nov-18 07:33
Date Collected:	10/31/2018 12:00:00AM				Date Analyzed:	15-Nov-18 08:47	Column:	ZB-1
						15-Nov-18 19:36	Column:	ZB-1
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	4430				IS 13C-PCB-1	30.3	40 - 120	H
Total diCB	24300				IS 13C-PCB-3	29.4	40 - 120	H
Total triCB	22400				IS 13C-PCB-4	77.9	40 - 120	D
Total tetraCB	4510				IS 13C-PCB-11	92.8	40 - 120	
Total pentaCB	331				IS 13C-PCB-9	79.4	40 - 120	D
Total hexaCB	61.5				IS 13C-PCB-19	51.0	40 - 120	
Total heptaCB	11.6				IS 13C-PCB-28	70.5	40 - 120	
Total octaCB	3.93				IS 13C-PCB-32	77.1	40 - 120	D
Total nonaCB	0.963				IS 13C-PCB-37	86.1	40 - 120	
DecaCB	0.0997				IS 13C-PCB-47	76.6	40 - 120	
Total PCB	56000				IS 13C-PCB-52	73.6	40 - 120	
					IS 13C-PCB-54	58.9	40 - 120	
					IS 13C-PCB-70	87.0	40 - 120	
					IS 13C-PCB-77	94.8	40 - 120	
					IS 13C-PCB-80	90.9	40 - 120	
					IS 13C-PCB-81	95.5	40 - 120	
					IS 13C-PCB-95	84.3	40 - 120	
					IS 13C-PCB-97	91.7	40 - 120	
					IS 13C-PCB-101	88.0	40 - 120	
					IS 13C-PCB-104	73.6	40 - 120	
					IS 13C-PCB-105	107	40 - 120	
					IS 13C-PCB-114	106	40 - 120	
					IS 13C-PCB-118	90.3	40 - 120	
					IS 13C-PCB-123	94.3	40 - 120	
					IS 13C-PCB-126	105	40 - 120	
					IS 13C-PCB-127	102	40 - 120	
					IS 13C-PCB-138	88.7	40 - 120	
					IS 13C-PCB-141	87.5	40 - 120	
					IS 13C-PCB-153	85.4	40 - 120	
					IS 13C-PCB-155	87.4	40 - 120	
					IS 13C-PCB-156	94.9	40 - 120	
					IS 13C-PCB-157	113	40 - 120	
					IS 13C-PCB-159	95.3	40 - 120	
					IS 13C-PCB-167	94.1	40 - 120	
					IS 13C-PCB-169	89.1	40 - 120	
					IS 13C-PCB-170	94.0	40 - 120	
					IS 13C-PCB-180	97.1	40 - 120	
					IS 13C-PCB-188	84.9	40 - 120	
					IS 13C-PCB-189	91.6	40 - 120	

Sample ID: 6-PCB				CARB Method 428			
Client Data		Sample Data		Laboratory Data			
Name:	Montrose Environmental Company	Matrix:	Air Train	Lab Sample:	1803396-06	Date Received:	11/1/2018 3:16:00PM
Project:	Schnitzer Steel 005AS-452603			QC Batch:	B8K0070	Date Extracted:	12-Nov-18 07:33
Date Collected:	10/31/2018 12:00:00AM			Date Analyzed:	15-Nov-18 08:47	Column:	ZB-1
					15-Nov-18 19:36	Column:	ZB-1
				Labeled Standard	%R	LCL-UCL	Qualifiers
				IS	13C-PCB-194	95.7	40 - 120
				IS	13C-PCB-202	92.5	40 - 120
				IS	13C-PCB-206	87.0	40 - 120
				IS	13C-PCB-208	82.3	40 - 120
				IS	13C-PCB-209	92.8	40 - 120
				PS	13C-PCB-79	98.1	60 - 140
				PS	13C-PCB-178	96.3	60 - 140

DL - Sample specific estimated detection limit
EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit
Results reported to RL.

Sample ID: FB-PCB					CARB Method 428			
Client Data			Sample Data		Laboratory Data			
Name:	Montrose Environmental Company		Matrix:	Air Train	Lab Sample:	1803396-07	Date Received:	11/1/2018 3:16:00PM
Project:	Schnitzer Steel 005AS-452603				QC Batch:	B8K0070	Date Extracted:	12-Nov-18 07:33
Date Collected:	10/31/2018 12:00:00AM				Date Analyzed:	15-Nov-18 16:21	Column:	ZB-1
Analyte	Conc. (ng/Sample)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Total monoCB	0.110				IS 13C-PCB-1	58.6	40 - 120	
Total diCB	0.624				IS 13C-PCB-3	56.8	40 - 120	
Total triCB	0.555				IS 13C-PCB-4	70.5	40 - 120	
Total tetraCB	0.188		0.229		IS 13C-PCB-11	73.1	40 - 120	
Total pentaCB	ND	0.0269			IS 13C-PCB-9	71.7	40 - 120	
Total hexaCB	ND	0.00784			IS 13C-PCB-19	64.9	40 - 120	
Total heptaCB	ND	0.00706			IS 13C-PCB-28	77.1	40 - 120	
Total octaCB	ND	0.00965			IS 13C-PCB-32	72.0	40 - 120	
Total nonaCB	ND	0.00607			IS 13C-PCB-37	80.2	40 - 120	
DecaCB	ND	0.00558			IS 13C-PCB-47	81.5	40 - 120	
Total PCB	1.48				IS 13C-PCB-52	81.7	40 - 120	
					IS 13C-PCB-54	76.6	40 - 120	
					IS 13C-PCB-70	88.2	40 - 120	
					IS 13C-PCB-77	92.7	40 - 120	
					IS 13C-PCB-80	88.3	40 - 120	
					IS 13C-PCB-81	91.9	40 - 120	
					IS 13C-PCB-95	86.1	40 - 120	
					IS 13C-PCB-97	91.3	40 - 120	
					IS 13C-PCB-101	89.7	40 - 120	
					IS 13C-PCB-104	85.9	40 - 120	
					IS 13C-PCB-105	102	40 - 120	
					IS 13C-PCB-114	101	40 - 120	
					IS 13C-PCB-118	98.9	40 - 120	
					IS 13C-PCB-123	98.1	40 - 120	
					IS 13C-PCB-126	99.2	40 - 120	
					IS 13C-PCB-127	102	40 - 120	
					IS 13C-PCB-138	95.5	40 - 120	
					IS 13C-PCB-141	97.5	40 - 120	
					IS 13C-PCB-153	94.4	40 - 120	
					IS 13C-PCB-155	82.6	40 - 120	
					IS 13C-PCB-156	100	40 - 120	
					IS 13C-PCB-157	102	40 - 120	
					IS 13C-PCB-159	98.5	40 - 120	
					IS 13C-PCB-167	99.2	40 - 120	
					IS 13C-PCB-169	93.9	40 - 120	
					IS 13C-PCB-170	95.4	40 - 120	
					IS 13C-PCB-180	99.2	40 - 120	
					IS 13C-PCB-188	95.3	40 - 120	
					IS 13C-PCB-189	98.4	40 - 120	

Sample ID: FB-PCB		CARB Method 428	
Client Data Name: Montrose Environmental Company Project: Schnitzer Steel 005AS-452603 Date Collected: 10/31/2018 12:00:00AM		Sample Data Matrix: Air Train	
		Laboratory Data Lab Sample: 1803396-07 Date Received: 11/1/2018 3:16:00PM QC Batch: B8K0070 Date Extracted: 12-Nov-18 07:33 Date Analyzed: 15-Nov-18 16:21 Column: ZB-1	
		Labeled Standard	%R
		IS 13C-PCB-194	94.7
		IS 13C-PCB-202	103
		IS 13C-PCB-206	106
		IS 13C-PCB-208	107
		IS 13C-PCB-209	116
		PS 13C-PCB-79	84.7
		PS 13C-PCB-178	89.3
		LCL-UCL	Qualifiers
		40 - 120	
		40 - 120	
		40 - 120	
		40 - 120	
		40 - 120	
		60 - 140	
		60 - 140	

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Results reported to RL.

DATA QUALIFIERS & ABBREVIATIONS

B	This compound was also detected in the method blank
Conc.	Concentration
D	Dilution
DL	Detection limit
E	The associated compound concentration exceeded the calibration range of the instrument
H	Recovery and/or RPD was outside laboratory acceptance limits
I	Chemical Interference
J	The amount detected is below the Reporting Limit/LOQ
LOD	Limits of Detection
LOQ	Limits of Quantitation
M	Estimated Maximum Possible Concentration (CA Region 2 projects only)
NA	Not applicable
ND	Not Detected
Q	Ion ratio outside of 70-130% of Standard Ratio. (DOD PFAS projects only)
TEQ	Toxic Equivalency
U	Not Detected (specific projects only)
*	See Cover Letter

Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.

CERTIFICATIONS

Accrediting Authority	Certificate Number
Alaska Department of Environmental Conservation	17-013
Arkansas Department of Environmental Quality	18-008-0
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777-18
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2018017
Minnesota Department of Health	1322288
New Hampshire Environmental Accreditation Program	207717
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-009
Pennsylvania Department of Environmental Protection	014
Texas Commission on Environmental Quality	T104704189-18-8
Virginia Department of General Services	9077
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request.

NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

CHAIN OF CUSTODY





MAQS Antioch

2825 Verne Roberts Circle

Antioch, CA 94509

Phone (925) 680-4300 | Fax (925) 680-4416

1803396

Client / Project: Schnitzer Steel		Project / Sample Location: Shredder Exhaust Stack		Test / Analytical Method: CARB 428 PCBs	
Project No.: 005AS-452603		Purchase Order No: PO#1027084		Special Analysis / Reporting Instructions: 14.9, 8.5, 5.7	
Send Analytical Report To: Antioch QA/QC: AntiochQA-QC@montrose-env.com rodell@montrose-env.com		Sampler or PM Signature: 			
Run / Sample No.	Date	Containers	Sample Fraction	Reagent	Lab / Sample ID No.
1-PCB	10/29/2018	1	1a - Filter	Filter	
1-PCB	10/29/2018	1	1b - XAD Trap	XAD Trap	
1-PCB	10/29/2018	1	2 - Front-Half Rinses	Methanol, Toluene, MeCl2	
1-PCB	10/29/2018	1	3 - Back-Half Rinses	Methanol, Toluene, MeCl2	
1-PCB	10/29/2018	1	4 - Impinger 1 Contents & Rinses	Methanol, Toluene, MeCl2	
1-PCB	10/29/2018	1	5 - Impingers 2 & 3 Contents	Org. Free H2O	
2-PCB	10/29/2018	6	1a, 1b, 2, 3, 4, & 5	See Above	
3-PCB	10/30/2018	6	1a, 1b, 2, 3, 4, & 5	See Above	
4-PCB	10/30/2018	6	1a, 1b, 2, 3, 4, & 5	See Above	
5-PCB	10/30/2018	6	1a, 1b, 2, 3, 4, & 5	See Above	
6-PCB	10/31/2018	6	1a, 1b, 2, 3, 4, & 5	See Above	
FB-PCB	10/29/2018	6	1a, 1b, 2, 3, 4, & 5	See Above	
RB-Methanol	10/31/2018	1	Reagent Blank	Methanol	
RB-Toluene	10/31/2018	1	Reagent Blank	Toluene	
RB-MeCl2	10/31/2018	1	Reagent Blank	MeCl2	
RB-ORG H2O	10/31/2018	1	Reagent Blank	Org. Free H2O	
Total Containers		46			
Relinquished by 		Date 11/1/16	Time 12:00	Received by 	Date 11/1/18 Time 13:30
Relinquished by 		Date 11/1/18	Time 15:17	Received by 	Date 11/1/18 Time 15:16
Relinquished by		Date	Time	Received by	Date Time

Sample Log-In Checklist

Page # 1 of 6Vista Work Order #: 1803396TAT std

Samples Arrival:	Date/Time <u>11/1/18 1516</u>	Initials: <u>KE</u>	Location: <u>MR-2</u> Shelf/Rack: <u>N/A</u>
Logged In:	Date/Time <u>11/2/18 0730</u>	Initials: <u>KE</u>	Location: <u>R-9</u> Shelf/Rack: <u>NA</u>
Delivered By:	FedEx	UPS	On Trac
	GSO	DHL	Hand Delivered
Other			
Preservation:	Ice	Blue Ice	Dry Ice
	None		
Temp °C: <u>5.8</u> (uncorrected)	Probe used: Y / <u>N</u>		Thermometer ID: <u>TR4</u>
Temp °C: <u>5.7</u> (corrected)			

	YES	NO	NA
Adequate Sample Volume Received?	☒		
Holding Time Acceptable?	☒		
Shipping Container(s) Intact?	☒		
Shipping Custody Seals Intact?			☒
Shipping Documentation Present?			☒
Airbill			☒
Trk #			
Sample Container Intact?	☒		
Sample Custody Seals Intact?			☒
Chain of Custody / Sample Documentation Present?	☒		
COC Anomaly/Sample Acceptance Form completed?			☒
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			☒
Preservation Documented:	Na ₂ S ₂ O ₃	Trizma	None
Other	Yes	No	<u>NA</u>
Shipping Container	Vista	Client	Retain
	Return	Dispose	

Comments:

XAD/Filter (large Vista cooler)
#1
* ALL XAD WERE LABELED BY "1,2,3,4,5,6"
INSTEAD OF COC SAMPLE NUMBER 1-PCB, 2-PCB, 3-PCB
etc "



Sample Log-In Checklist – Additional Information

Page # 22 of 6
 WO#: 1803396
 Cooler # 3 of 3

Sample Label ID	Notes
1	* LARGE COOLER
2	• SAMPLE ID WRITTEN DIRECTLY ON XAD BUBBLE WRAP IN RED
3	• 1 UNUSED FILTER
4	
5	
6	
FB	
FB-PCB-CONT 3	
FB-PCB-CONT 2	
FB-PCB-CONT 1A	
4-PCB-CONT 1A	
1-PCB-CONT 1A	
5-PCB-CONT 1A	
2-PCB-CONT 1A	
6-PCB-CONT 1A	
3-PCB-CONT 1A	
3-PCB-CONT 3	
3-PCB-CONT 4	
3-PCB-CONT 5	
2-PCB-CONT 3	
2-PCB-CONT 4	
2-PCB-CONT 5	
1-PCB-CONT 3	
1-PCB-CONT 4	
1-PCB-CONT 5	
RB-ORG-H2O	
FB-PCB-CONT 4	
FB-PCB-CONT 5	
	Recorded By/Date: <u>FS 11/2/18</u>



Sample Log-In Checklist

Page # 3 of 6Vista Work Order #: 1803396 TAT std

Samples Arrival:	Date/Time <u>11/1/18 1516</u>	Initials: <u>KE</u>	Location: <u>WR-2</u> Shelf/Rack: <u>NA</u>
Logged In:	Date/Time <u>11/2/18 0730</u>	Initials: <u>KA</u>	Location: <u>R-9</u> Shelf/Rack: <u>NA</u>
Delivered By:	FedEx	UPS	On Trac
	GSO	DHL	Hand Delivered
Other			
Preservation:	Ice	Blue Ice	Dry Ice
	None		
Temp °C: <u>8.6</u> (uncorrected)	Probe used: Y / <u>N</u>		Thermometer ID: <u>TR4</u>
Temp °C: <u>8.5</u> (corrected)			

	YES	NO	NA
Adequate Sample Volume Received?	☒		
Holding Time Acceptable?	☒		
Shipping Container(s) Intact?	☒		
Shipping Custody Seals Intact?			☒
Shipping Documentation Present?			☒
Airbill			☒
Trk #			
Sample Container Intact?	☒		
Sample Custody Seals Intact?			☒
Chain of Custody / Sample Documentation Present?	☒		
COC Anomaly/Sample Acceptance Form completed?			☒
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			☒
Preservation Documented:	Na ₂ S ₂ O ₃	Trizma	None
	Other		
Shipping Container	Vista	Client	Retain
		Return	Dispose

Comments:

CARD BOARD BOX

Page # 4 of 6
WO#: 1803396
Cooler # 1 of 3

Page: 1 of 1



Sample Log-In Checklist

Page # 5 of 6Vista Work Order #: 1803396 TAT std

Samples Arrival:	Date/Time <u>11/1/18 1516</u>	Initials: <u>KE</u>	Location: <u>WR-Z</u> Shelf/Rack: <u>NA</u>
Logged In:	Date/Time <u>11/2/18 0730</u>	Initials: <u>KE</u>	Location: <u>WR-Z R-9</u> Shelf/Rack: <u>R-9</u>
Delivered By:	FedEx	UPS	On Trac
	GSO	DHL	Hand Delivered
Other			
Preservation:	Ice	Blue Ice	Dry Ice
	None		
Temp °C: <u>15.0</u> (uncorrected)	Probe used: Y / <u>N</u>		Thermometer ID: <u>IR4</u>
Temp °C: <u>14.9</u> (corrected)			

	YES	NO	NA
Adequate Sample Volume Received?	✓		
Holding Time Acceptable?	✓		
Shipping Container(s) Intact?	✓		
Shipping Custody Seals Intact?			✓
Shipping Documentation Present?			✓
Airbill			✓
Trk #			
Sample Container Intact?	✓		
Sample Custody Seals Intact?			✓
Chain of Custody / Sample Documentation Present?	✓		
COC Anomaly/Sample Acceptance Form completed?			✓
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			✓
Preservation Documented:	Na ₂ S ₂ O ₃	Trizma	None
	Other		
Shipping Container	Vista	Client	Retain
	Return	Dispose	

Comments: SOLVENT



Sample Log-In Checklist – Additional Information

Page # 6 of 6
WO#: 1803396
Cooler # 2 of 3

Sample Label ID	Notes
RB - METHANOL	* BLUE COOLER
RB - TOLUENE	
RB - MeCl2	
4-PCB-CONT 5	
4-PCB-CONT 4	
4-PCB-CONT 3	
5-PCB-CONT 5	
5-PCB-CONT 4	
5-PCB-CONT 3	
6-PCB-CONT 5	
6-PCB-CONT 4	
6-PCB-CONT 3	
Recorded By/Date: <u>FS</u> <u>11/2/18</u>	

APPENDIX D CLIENT PROCESS DATA

Appendix D.1 Process Data

Oct 2018 Source Test		Run Time (minutes)	Material Feed Rate (Tons/hr)	Material output (Tons/hr)	Fan Amps		Mill Water Spray Rate (GPM)	Venturi DP (Inches WG)	
Run#, Date	Time				Fan 1 (SFA3)	Fan 2 (SFA4)		Scrubber 1 (PDIT 10)	Scrubber 2 (PDIT20)
Car Bodies Only									
Run 1 10/29/18	2000-2109	69	■	■	516	541	28	29	24
Run 2 10/29/18	2235-2250	15	■	■	518	544	27	29	21
	2331-0024	53	■	■	522	546	28	29	24
	Run 2 TWA:		■	■	521	546	28	29	23
Run 3 10/30/18	0045-0157	72	■	■	520	545	30	29	24
Average			■	■	519	544	29	29	24
Light Iron Only									
Run 4 10/30/18	2114-2224	70	■	■	515	540	28	29	24
Run 5 10/30/18	2253-0002	69	■	■	516	540	27	29	24
Run 6 10/31/18	0020-0120	60	■	■	514	538	28	29	24
	0153-0208	15	■	■	519	546	28	29	24
	Run 6 TWA:		■	■	515	540	28	29	24
Averages			■	■	515	540	28	29	24

APPENDIX E

QUALITY ASSURANCE/QUALITY CONTROL

Appendix E.1

Quality Assurance Program Summary and Equipment Calibration Schedule

QUALITY ASSURANCE PROGRAM SUMMARY AND CERTIFICATIONS

Montrose Air Quality Services, LLC (Montrose) ensures the quality and validity of its emission measurement and reporting procedures through a rigorous quality assurance (QA) program. The program is developed and administered by internal QA personnel and encompasses eight major areas:

1. Development and use of an internal QA manual
2. QA reviews of reports, laboratory work, and field testing
3. Equipment calibration and maintenance
4. Chain of custody
5. Continuous training
6. Knowledge of current test methods
7. Agency certification
8. Uncertainty of results

Each of these areas is discussed individually below.

Quality Assurance Manual. Montrose has prepared a QA Manual according to EPA guidelines and ASTM D-7036. The manual serves to document and formalize all of Montrose's QA efforts. The manual is constantly updated, and each employee involved in technical services for emission measurements is required to read, understand its contents, and sign a statement that all work they perform will conform to its practices. The manual includes details on the other seven QA areas discussed below.

QA Reviews. Montrose's review procedure includes review of each source test report by the QA Manager or equivalent position including data input, calculations and averages, and report text. The laboratory manager or equivalent reviews all laboratory work, and the qualified individual on-site reviews all field work and data sheets.

The most important review is the one that takes place before a test program begins. The QA Manager works with testing personnel to prepare and review test protocols. Test protocol review includes selection of appropriate test procedures, evaluation of any interferences or other restrictions that might preclude use of standard test procedures, and evaluation and/or development of alternate procedures.

Equipment Calibration and Maintenance. The equipment used to conduct the emission measurements is maintained according to the manufacturer's instructions to ensure proper operation. In addition to the maintenance program, calibrations are carried out on each measurement device according to the schedule outlined below. The schedules for maintenance and calibrations are given in Tables A-1 and A-2.

Quality control checks are also conducted in the field for each test program. A partial list of checks made as part of each continuous analyzer system test series is included below as an example of the field QA procedures.

- Sample acquisition and conditioning system leak check
- 3-point analyzer calibrations (all analyzers)

- Complete system calibration check ("dynamic calibration" through entire sample system)
- Periodic analyzer calibration checks are conducted at the start and end of each test run. Any change between pre- and post-test readings are recorded.
- All calibrations are conducted using EPA Protocol gases certified by the manufacturer
- Calibration and continuous analyzer performance data are fully documented, and are included in each source test report

Chain of Custody. Montrose maintains full chain of custody documentation on all samples and data sheets. In addition to normal documentation of changes between field sample custodians, laboratory personnel, and field test personnel, Montrose documents every individual who handles any test component in the field (e.g., probe wash, impinger loading and recovery, filter loading and recovery, etc.).

Samples are stored in a locked area to which only laboratory personnel have access. Neither other Montrose employees nor cleaning crews have keys to this area.

Training. Personnel training is essential to ensure quality testing. Montrose has formal and informal training programs which may include some or all of the following:

1. Attendance at EPA-sponsored training courses
2. A requirement for all technicians to read, understand, and sign Montrose 's QA Manual
3. In-house training and Montrose meetings on a regular basis
4. Maintenance of training records
5. Administration of internal qualified individual (QI) tests for all methods performed
6. Participation in the Qualified Source Testing Individual (QSTI) program administered by the Source Evaluation Society (SES)

Knowledge of Current Test Methods. With the constant updating of standard test methods and the wide variety of emerging test methods, it is essential that any qualified source tester keep abreast of new developments. Montrose subscribes to services which provide updates on EPA reference methods, and on EPA and local agency rules and regulations. Additionally, source test personnel regularly attend and present papers at testing and emission-related seminars and conferences.

Audit Program. Montrose participates in the TNI Stationary Source Audit Sample (SSAS) audit program for all methods for which audit samples are available.

Uncertainty of Results. Both qualitative and quantitative factors contribute to field measurement uncertainty and should be taken into consideration when interpreting the results contained within this report. Whenever possible, Montrose personnel reduce the impact of these uncertainty factors through the use of approved and validated test methods. In addition, Montrose personnel perform routine instrument and equipment calibrations and ensure that the calibration standards, instruments, and equipment used during test events meet, at a minimum, test method specifications as well as the specifications of our Quality Manual and ASTM D 7036-04.

The limitations of the various methods, instruments, equipment, and materials utilized during this test have been reasonably considered, but the ultimate impact of the cumulative uncertainty of this project is not fully identified within the results of this report.

TABLE A-1
SAMPLING INSTRUMENTS AND
EQUIPMENT CALIBRATION SCHEDULE

Instrument Type	Frequency of Calibration ¹	Standard of Comparison or Method of Calibration	Acceptance Limits
Orifice Meter(large)	12 months	Calibrated dry test meter	± 2% of volume measured
Dry Gas Meter	6 months or when repaired	Calibrated dry test meter	± 2% of volume measured
Critical Orifice	6 months	Calibrated dry test meter	± 0.5% of average K'
S-Type Pitot (for use with EPA-type sampling train)	6 months	EPA Method 2	Geometric measurements within method-specified ranges
Vacuum Gauges	12 months	NIST-traceable gauge	≤ 1.0 in Hg difference
Temperature Measurement (thermocouples)	12 months	NBS mercury thermometer or NBS calibrated platinum RTD	±4 °F for <400 °F ± 1.5% for >400 °F
Temperature Readout Devices	6 months	Thermocouple simulator	± 2% full scale reading
Analytical Balance	12 months (check prior to each use)	NIST-traceable weights	± 0.5 mg of stated weight
Probe Nozzles	12 months	Nozzle diameter check	Range <± 0.10 mm for micrometer three measurements
Continuous Analyzers	Every field day, Depends upon use, frequency and performance	As specified by manufacturers' operating manuals, EPA NBS gases and/or reference methods	Satisfy all limits specified in operating specifications

¹ The tabulated calibration frequencies are minimum standards. In certain instances, calibrations are performed more frequently.

TABLE A-2
EQUIPMENT MAINTENANCE SCHEDULE
Based on Manufacturer's Specifications and Montrose's Experience

Equipment	Performance Requirement	Maintenance Interval ²	Corrective Action
Pumps	1. Absence of leaks 2. Ability to draw manufacturer required vacuum and flow	6 months	1. Visual inspection 2. Clean 3. Replace worn parts 4. Leak check
Flow Measuring Device	1. Free mechanical movement 2. Absence of malfunction	6 months	1. Visual inspection 2. Clean 3. Calibrate
Sampling Instruments	1. Absence of malfunction 2. Proper response to zero, span gas	As required by the manufacturer	As recommended by manufacturer
Mobile Van Sampling Systems	Absence of leaks	Depends on nature of use	1. Change filters 2. Leak check 3. Check for system contamination
Sampling Lines	Sample degradation less than 2%	After each test or test series	Blow filtered air through line until dry

² The tabulated maintenance intervals are minimum standards. In certain instances, maintenance is performed more frequently.

Appendix E.2

ASTM D-7036 Accreditation, ARB Certification, and QI Certificates

Accredited Air Emission Testing Body

A2LA has accredited

MONTROSE AIR QUALITY SERVICES

In recognition of the successful completion of the joint A2LA and Stack Testing Accreditation Council (STAC) evaluation process, this laboratory is accredited to perform testing activities in compliance with ASTM D7036:2004 - Standard Practice for Competence of Air Emission Testing Bodies.

Presented this 5th day of March 2018.

A handwritten signature in black ink, appearing to be "L. L. L.", written over a horizontal line.

President and CEO
For the Accreditation Council
Certificate Number 3925.01
Valid to February 29, 2020

This accreditation program is not included under the A2LA ILAC Mutual Recognition Arrangement.

January 5, 2018

Mr. Matt McCune
Montrose Air Quality Services, LLC
1631 East Saint Andrew Place
Santa Ana, California 92705

Dear Mr. McCune:

I am pleased to inform you that the California Air Resources Board (CARB) has renewed, by means of enclosed Executive Order (EO) I-18-002, Montrose Air Quality Services, LLC's approval to perform CARB Test Methods 1, 2, 3, 4, 5, 6, 8, 17, 20, and 100 (CO, CO₂, NO_x, O₂, SO₂, THC), Visible Emission Evaluation, and U.S. Environmental Protection Agency Test Methods 201A, 202, and 205. This approval is valid through June 30, 2020, during which time additional audits of Montrose Air Quality Services, LLC's testing ability may be performed. I have also enclosed two certificates of approval that expire June 30, 2020.

If you have questions or need further assistance, please contact Kathryn Gugeler at (916) 322-0221 or via email at kathryn.gugeler@arb.ca.gov, or Angus MacPherson at (916) 445-4686 or via email at angus.macpherson@arb.ca.gov.

Sincerely,



Dr. Michael T. Benjamin, Chief
Monitoring and Laboratory Division

Enclosures (3)

cc: Angus MacPherson, Manager
Testing and Certification Section

Kathryn Gugeler
Monitoring and Laboratory Division

**State of California
AIR RESOURCES BOARD**

EXECUTIVE ORDER I-18-002

**Approval of Independent Contractor Pursuant to
California Code of Regulations, title 17, section 91207**

Montrose Air Quality Services, LLC

WHEREAS, the California Air Resources Board (CARB), pursuant to California Health and Safety Code, section 41512, has established the procedures contained in California Code of Regulations, title 17, section 91200 and following, to allow the use of independent testers for compliance tests required by CARB;


WHEREAS, it has been determined that Montrose Air Quality Services, LLC meets the requirements of CARB for performing 1, 2, 3, 4, 5, 6, 8, 17, 20, and 100 (CO, CO₂, NO_x, O₂, SO₂, THC), Visible Emission Evaluation (VEE), and U.S. Environmental Protection Agency (U.S. EPA) Test Methods 201A, 202, and 205 pursuant to Cal. Code Regs., tit. 17, § 91200 and following, when the following conditions are met:

1. Montrose Air Quality Services, LLC permanently marks or engraves an identification number on the body of each of its pitot tubes in accordance with section 2.1 of CARB Test Method 2;
2. Montrose Air Quality Services, LLC calibrates its differential pressure gauges after each test series in accordance with section 2.2 of CARB Test Method 2, and establishes and maintains a log of the calibrations;
3. Montrose Air Quality Services, LLC calibrates its temperature gauges in accordance with section 4.3 of CARB Test Method 2, and establishes and maintains a log of the calibrations;
4. Montrose Air Quality Services, LLC calibrates its metering system in accordance with section 5.3 of CARB Test Method 5, and establishes and maintains a log of the calibrations;
5. Montrose Air Quality Services, LLC acquires and uses a 5-mL burette in accordance with section 2.3.3 of CARB Test Method 6 and section 4.2 of CARB Test Method 20;
6. Montrose Air Quality Services, LLC acquires and uses 300 to 500 mL glass beakers in accordance with Section 6.2.2(c) of U.S. EPA Test Method 202;
7. Montrose Air Quality Services, LLC uses desiccant in accordance with section 3.3.2 of CARB Test Methods 5 and 17, section 7.2.2 of U.S. EPA Test Method 201A, and section 7.2.4 of U.S. EPA Test Method 202;

State of California
Air Resources Board
Approved Independent Contractor
Montrose Air Quality Services, LLC

This is to certify that the company listed above has been approved by the California Air Resources Board to conduct compliance testing pursuant to California Code of Regulations, title 17, section 91207, through June 30, 2020, for those test methods listed below:

CARB Source Test Methods:
1, 2, 3, 4, 5, 6, 8, 17, 20
100 (CO, CO₂, NO_x, O₂, SO₂, THC)




Dr. Michael T. Benjamin, Chief
Monitoring and Laboratory Division

State of California
Air Resources Board
Approved Independent Contractor
Montrose Air Quality Services, LLC

This is to certify that the company listed above has been approved by the California Air Resources Board to conduct compliance testing pursuant to California Code of Regulations, title 17, section 91207, through June 30, 2020, for those test methods listed below:

U.S. EPA Source Test Methods 201A, 202 and 205
Visible Emissions Evaluation



Dr. Michael T. Benjamin, Chief
Monitoring and Laboratory Division

SOURCE EVALUATION SOCIETY



Qualified Source Testing Individual

LET IT BE KNOWN THAT

ROBERT M. ODELL

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED
EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES
ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

HAZARDOUS METALS MEASUREMENT SAMPLING METHODS

ISSUED THIS 18TH DAY OF MARCH, 2016 AND EFFECTIVE UNTIL MARCH 17TH, 2021

Peter R. Westlin, QSTI/QSTO Review Board

Peter S. Pakalnis, QSTI/QSTO Review Board


Theresa Lowe, QSTI/QSTO Review Board

C. David Bagwell, QSTI/QSTO Review Board

Karen D. Kajiy-Mills, QSTI/QSTO Review Board

Bruce Randall, QSTI/QSTO Review Board

CERTIFICATE
NO.
2012-642



SOURCE EVALUATION SOCIETY



Qualified Source Testing Individual

LET IT BE KNOWN THAT

ROBERT M. ODELL

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED
EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES
ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

**MANUAL GAS VOLUME MEASUREMENTS AND ISOKINETIC PARTICULATE
SAMPLING METHODS**

ISSUED THIS 11TH DAY OF FEBRUARY 2017 AND EFFECTIVE UNTIL FEBRUARY 10TH, 2022

Peter R. Westlin, QSTI/QSTO Review Board

Peter S. Pakalnis, QSTI/QSTO Review Board


Theresa Lowe, QSTI/QSTO Review Board

J. Wade Bice, QSTI/QSTO Review Board

Karen D. Kajiya-Mills, QSTI/QSTO Review Board

Bruce Randall QSTI/QSTO Review Board

CERTIFICATE
NO.
2012-642



SOURCE EVALUATION SOCIETY



Qualified Source Testing Individual

LET IT BE KNOWN THAT

ROBERT M. ODELL

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED
EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES
ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

MANUAL GASEOUS POLLUTANTS SOURCE SAMPLING METHODS

ISSUED THIS 18TH DAY OF MARCH 2016 AND EFFECTIVE UNTIL MARCH 17TH, 2021

Peter R. Westlin, QSTI/QSTO Review Board

Peter S. Pakalnis, QSTI/QSTO Review Board


Theresa Lowe, QSTI/QSTO Review Board

C. David Bagwell, QSTI/QSTO Review Board

Karen D. Kajlya-Mills, QSTI/QSTO Review Board

Bruce Randall QSTI/QSTO Review Board

CERTIFICATE
NO.
2012-642



SOURCE EVALUATION SOCIETY



Qualified Source Testing Individual

LET IT BE KNOWN THAT

ROBERT M. ODELL

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED
EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES
ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

GASEOUS POLLUTANTS INSTRUMENTAL SAMPLING METHODS

ISSUED THIS 11TH DAY OF FEBRUARY 2017 AND EFFECTIVE UNTIL FEBRUARY 10TH, 2022

Peter R. Westlin, QSTI/QSTO Review Board

Peter S. Pakalnis, QSTI/QSTO Review Board


Theresa Lowe, QSTI/QSTO Review Board

J. Wade Bice, QSTI/QSTO Review Board

Karen D. Kajlya-Mills, QSTI/QSTO Review Board

Bruce Randall QSTI/QSTO Review Board

CERTIFICATE
NO.
2012-642



Appendix E.3

CEM Analyzer Calibration Data



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition:
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Analyzer Configuration							
Name:	O2	CO2	THC				
Make/Model:							
25A or 7E:	7E	7E	25A				
Voltage max:	10	10	10				
Voltage offset:	0	0	0				
Range:	10	10	10				
Upscale:							
Downscale:							

Cylinder Information							
Zero Number:	CC73814	CC73814	EB0083042				
Zero Conc:	0	0	0				
Low Number:			CC222293				
Low Conc:			264.5				
Mid Number:	CC154441	CC154441	CC203412				
Mid Conc:	11.57	3.938	503.2				
High Number:	EB0094194	EB0094194	CC25564				
High Conc:	21.26	8.419	865.6				
Bias Number:	CC154441	CC154441	CC203412				
Bias Conc:	11.57	3.938	503.2				



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition:
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Calibration								
	Name:	O2	CO2	THC				
	Make/Model:							
	25A or 7E:	7E	7E	25A				

Cylinder Concentrations								
	Zero:	0.000	0.000	0.000				
	Low:			264.5				
	Mid:	11.57	3.938	503.2				
	High:	21.26	8.419	865.6				

Calibration Readings								
	Zero reading:	-0.005	0.011	0.060				
	Low reading:	0.000	0.000	265.6				
	Mid reading:	11.56	3.947	519.4				
	High reading:	21.26	8.416	867.4				

EPA Method 7E Error Calculations								
Zero %Err:	<2.0	-0.024	0.131	N/A				
Mid %Err:	<2.0	-0.047	0.107	N/A				
High %Err:	<2.0	0.000	-0.036	N/A				

EPA Method 25A Error Calculations								
Zero Err:	N/A	N/A	N/A	0.060				
Low Err:	5% of cyl	N/A	N/A	1.100				
Mid Err:	5% of cyl	N/A	N/A	16.20				
High Err:	N/A	N/A	N/A	1.800				



MAQDAQ 1.0			
Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Analyzer Configuration							
Name:	O2	CO2	THC				
Make/Model:							
25A or 7E:	7E	7E	25A				
Voltage max:	10	10	10				
Voltage offset:	0	0	0				
Range:	10	10	10				
Upscale:							
Downscale:							

Cylinder Information							
Zero Number:	CC73814	CC73814	EB0083042				
Zero Conc:	0	0	0				
Low Number:			CC222293				
Low Conc:			264.5				
Mid Number:	CC154441	CC154441	CC203412				
Mid Conc:	11.57	3.938	503.2				
High Number:	EB0094194	EB0094194	CC25564				
High Conc:	21.26	8.419	865.6				
Bias Number:	CC154441	CC154441	CC203412				
Bias Conc:	11.57	3.938	503.2				



PUBLIC COPY

MAQDAQ 1.0

Project Name: Schnitzer Steel	Project Number: 005AS-452603	CEMS Operator: RO	Unit/Condition: Light Iron
Run Length: 60	Record Interval: 6	Average Interval: 60	Triplicate Sampling: False
Traverse: False	Ports: N/A	Points per port: N/A	DAQ Device: DT9803(06)

Calibration

Name:	O2	CO2	THC					
Make/Model:								
25A or 7E:	7E	7E	25A					

Cylinder Concentrations

Zero:	0.000	0.000	0.000					
Low:			264.5					
Mid:	11.57	3.938	503.2					
High:	21.26	8.419	865.6					

Calibration Readings

Zero reading:	0.000	0.003	1.100					
Low reading:	0.000	0.000	270.5					
Mid reading:	11.55	3.924	506.6					
High reading:	21.30	8.412	868.0					

EPA Method 7E Error Calculations

Zero %Err:	<2.0	0.000	0.036	N/A				
Mid %Err:	<2.0	-0.094	-0.166	N/A				
High %Err:	<2.0	0.188	-0.083	N/A				

EPA Method 25A Error Calculations

Zero Err:	N/A	N/A	N/A	1.100				
Low Err:	5% of cyl	N/A	N/A	6.000				
Mid Err:	5% of cyl	N/A	N/A	3.400				
High Err:	N/A	N/A	N/A	2.400				

Appendix E.4

Span Gas Certificates

CERTIFICATE OF BATCH ANALYSIS

Grade of Product: CEM-CAL ZERO

Part Number:	NI CZ15A	Reference Number:	153-401216018-1
Cylinder Analyzed:	SG9149074BAL	Cylinder Volume:	142.0 CF
Laboratory:	124 - Tooele (SAP) - UT	Cylinder Pressure:	2000 PSIG
Analysis Date:	May 29, 2018	Valve Outlet:	580
Lot Number:	153-401216018-1		

Expiration Date: May 29, 2026

ANALYTICAL RESULTS

Component	Requested Purity	Certified Concentration
NITROGEN	99.9995 %	99.9995 %
CARBON DIOXIDE	< 1.0 PPM	0.32 PPM
NOx	< 0.1 PPM	0.02 PPM
SO2	< 0.1 PPM	<LDL 0.1 PPM
THC	< 0.1 PPM	0.08 PPM
CARBON MONOXIDE	< 0.5 PPM	0.02 PPM

Permanent Notes: Airgas certifies that the contents of this cylinder meet the requirements of 40 CFR 72.2

Cylinders in Batch:

AL-0093, ALM-032685, CC222230, CC435034, CC484549, CC494749, CC505121, CC505425, CC701890, CC73814, EB0081877, EB0081881, EB0086969, EB0088933, EB0097111, EB0097253, EB0098483, SG9102233ALB, SG9149074BAL, SG9164954BAL

Impurities verified against analytical standards traceable to NIST by weight and/or analysis.

Signature on file

Approved for Release

005AS-452603-RT-310

213 of 231

Page 1 of 153-401216018-1

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number: E03NI84E15A7419 Reference Number: 153-401259902-1
Cylinder Number: CC154441 Cylinder Volume: 147.5 CF
Laboratory: 124 - Tooele (SAP) - UT Cylinder Pressure: 2015 PSIG
PGVP Number: B72018 Valve Outlet: 590
Gas Code: CO2,O2,BALN Certification Date: Jul 31, 2018

Expiration Date: Jul 31, 2026

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
CARBON DIOXIDE	4.000 %	3.938 %	G1	+/- 0.7% NIST Traceable	07/31/2018
OXYGEN	11.50 %	11.57 %	G1	+/- 0.7% NIST Traceable	07/30/2018
NITROGEN	Balance			-	

CALIBRATION STANDARDS					
Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	05010527	K011448	3.000 % CARBON DIOXIDE/NITROGEN	0.3%	Jun 05, 2019
NTRM	98051014	SG9162888BAL	12.05 % OXYGEN/NITROGEN	0.7%	Dec 14, 2023

ANALYTICAL EQUIPMENT		
Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Horiba VIA-510 SV4MEUTJ CO2	CO2 NDIR (Dixon)	Jul 12, 2018
Horiba MPA-510 X9A4UGL8 O2	O2 Paramagnetic (Dixon)	Jul 13, 2018

Triad Data Available Upon Request



Signature on file

Approved for Release

005AS-452603-RT-310

214 of 231

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number:	E02AI99E15A0333	Reference Number:	48-401248365-1
Cylinder Number:	CC25564	Cylinder Volume:	146.3 CF
Laboratory:	124 - Los Angeles (SAP) - CA	Cylinder Pressure:	2015 PSIG
PGVP Number:	B32018	Valve Outlet:	590
Gas Code:	PPN,BALA	Certification Date:	Jul 19, 2018

Expiration Date: Jul 19, 2026

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
PROPANE	850.0 PPM	865.6 PPM	G1	+/- 0.8% NIST Traceable	07/19/2018
AIR	Balance			-	

CALIBRATION STANDARDS					
Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	15060803	CC462447	992.3 PPM PROPANE/NITROGEN	+/- 0.6%	Jul 22, 2021

ANALYTICAL EQUIPMENT		
Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Nicolet 6700 AHR0801551 C3H8	FTIR	Jul 18, 2018

Triad Data Available Upon Request



Signature on file

Approved for Release

005AS-452603-RT-310

215 of 231

Page 1 of 48-401248365-1

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number:	E02AI99E15A0332	Reference Number:	48-124600300-1
Cylinder Number:	CC203412	Cylinder Volume:	146.3 CF
Laboratory:	124 - Los Angeles (SAP) - CA	Cylinder Pressure:	2015 PSIG
PGVP Number:	B32017	Valve Outlet:	590
Gas Code:	PPN,BALA	Certification Date:	Feb 01, 2017

Expiration Date: Feb 01, 2025

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
PROPANE	500.0 PPM	503.2 PPM	G1	+/- 0.5% NIST Traceable	02/01/2017
AIR	Balance				

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	10060524	CC281414	495.3 PPM PROPANE/AIR	+/- 0.5%	Jan 06, 2022

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Nicolet 6700 AHR0801551 C3H8	FTIR	Jan 25, 2017

Triad Data Available Upon Request



Signature on file

Approved for Release

005AS-452603-RT-310

216 of 231

Page 1 of 48-124600300-1

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number: E03NI70E15A7420 Reference Number: 153-401102413-1
Cylinder Number: EB0094194 Cylinder Volume: 151.2 CF
Laboratory: 124 - Tooele (SAP) - UT Cylinder Pressure: 2015 PSIG
PGVP Number: B72018 Valve Outlet: 590
Gas Code: CO2,O2,BALN Certification Date: Jan 18, 2018

Expiration Date: Jan 18, 2026

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
CARBON DIOXIDE	8.500 %	8.419 %	G1	+/- 0.7% NIST Traceable	01/18/2018
OXYGEN	21.00 %	21.26 %	G1	+/- 0.5% NIST Traceable	01/18/2018
NITROGEN	Balance			-	

CALIBRATION STANDARDS					
Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	13060410	CC413504	7.489 % CARBON DIOXIDE/NITROGEN	0.6%	Jan 14, 2019
NTRM	09061433	CC282486	22.53 % OXYGEN/NITROGEN	0.4%	Mar 08, 2019

ANALYTICAL EQUIPMENT		
Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Horiba VIA-510 SV4MEUTJ CO2	CO2 NDIR (Dixon)	Jan 09, 2018
Horiba MPA-510 X9A4UGL8 O2	O2 Paramagnetic (Dixon)	Jan 08, 2018

Triad Data Available Upon Request



Signature on file

Approved for Release

005AS-452603-RT-310

217 of 231

Page 1 of 153-401102413-1

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number: E02AI99E15A7414 Reference Number: 48-401166384-1
Cylinder Number: CC222293 Cylinder Volume: 146.2 CF
Laboratory: 124 - Los Angeles (SAP) - CA Cylinder Pressure: 2015 PSIG
PGVP Number: B32018 Valve Outlet: 590
Gas Code: PPN,BALA Certification Date: Apr 02, 2018

Expiration Date: Apr 02, 2026

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
PROPANE	265.0 PPM	264.5 PPM	G1	+/- 0.9% NIST Traceable	04/02/2018
AIR	Balance			-	

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	14060208	CC348942	249.2 PPM PROPANE/AIR	+/- 0.5%	Dec 12, 2019

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Nicolet 6700 AHR0801551 C3H8	FTIR	Mar 06, 2018

Triad Data Available Upon Request



Signature on file

Approved for Release

005AS-452603-RT-310

218 of 231

Page 1 of 48-401166384-1

Appendix E.5 Equipment Calibration Data



EPA Method 5 **Meter Box Calibration by Calibrated Critical Orifice,** **Leak Check, and Thermocouple Calibration Check** **English Meter Box Units, English K' Factor**

Meter box ID:	CB-22
Meter ID (if applicable):	CB-22
Orifice set ID:	Antioch
Calibrated by:	SC
Expires:	12/9/18

Date:	6/9/18
Location:	Antioch
No. of orifices used (min. 3)	5
Barometric pressure (in. Hg):	29.89 in. Hg
Theoretical critical vacuum	14.10 in. Hg

Yd:	0.9895
$\Delta H@$:	1.850

Meter Box Orifice Calibration

IMPORTANT For valid test results, the Actual Vacuum should be 1 to 2 in. Hg greater than the Theoretical Critical Vacuum shown above
 IMPORTANT The Critical Orifice Coefficient, K', must be entered in English units, (ft³*3/(deg R)*0.5/(in.Hg)*(min)).

ΔH (in H ₂ O)	Time (min)	Volume			Initial Temps.		Final Temps.		Orifice Serial# (number)	K' Orifice Coefficient (see above)	Vacuum (in Hg)	— Ambient Temperature —		
		Initial (cu ft)	Final (cu ft)	Net (cu ft)	Inlet (deg F)	Outlet (deg F)	Inlet (deg F)	Outlet (deg F)				Initial (deg F)	Final (deg F)	Average (deg F)
0.33	17.00	369.100	374.498	5.398	68.0	68.0	69.0	69.0	RG-40	0.2373	17.0	68.0	69.0	68.5
0.70	12.00	337.084	342.613	5.529	64.0	64.0	65.0	65.0	RG-48	0.3490	17.0	64.0	65.0	64.5
1.06	9.00	361.558	366.687	5.129	68.0	68.0	69.0	69.0	RG-55	0.4345	17.0	68.0	69.0	68.5
1.95	9.00	375.152	382.191	7.039	69.0	69.0	70.0	70.0	RG-63	0.6010	17.0	69.0	69.0	69.0
3.30	6.00	355.101	361.231	6.130	67.0	67.0	68.0	68.0	RG-73	0.7938	17.0	67.0	68.0	67.5

— SAMPLE RATE —
 INDICATED VS. ACTUAL

ΔH (in. H ₂ O)	Sample Rate (scfm)
0.33	0.309
0.70	0.455
1.06	0.565
1.95	0.781
3.30	1.033

— DRY GAS METER —
 VOLUME
 CORRECTED

Vm(std) (cu ft)
5.390
5.568
5.130
7.043
6.177

— ORIFICE —
 VOLUME
 CORRECTED

Vcr(std) (cu ft)	Vcr (cu ft)
5.245	5.257
5.466	5.437
5.084	5.096
7.029	7.053
6.198	6.201

— DRY GAS METER —
 CALIBRATION FACTOR

Yd	Variation (number)
0.9732	-0.016
0.9817	-0.008
0.9910	0.002
0.998	0.009
1.003	0.014

— ORIFICE —
 CALIBRATION FACTOR
 $\Delta H@$

Value (in H ₂ O)	Variation (in H ₂ O)
1.946	0.096
1.909	0.059
1.865	0.015
1.791	-0.059
1.739	-0.111

For Calibration Factor Yd, the ratio of the reading of the calibration meter to the dry gas meter, acceptable tolerance of individual values from the average is +/-0.02.

For Orifice Calibration Factor $\Delta H@$, the orifice differential pressure in inches of H₂O that equates to 0.75 cfm of air at 68 F and 29.92 inches of Hg, acceptable tolerance of individual values from the average is +/-0.2.

QA Criteria:	
Average Yd	0.9895
Average $\Delta H@$	1.8499
Variation of Yd's	PASS
Variation of $\Delta H@$	PASS
Vacuum Criteria	PASS

Meter Box Pressure Leak Check

Test Pressure, (in H ₂ O):	7	Should be 5-7 in. H ₂ O
Leak Rate, (in H ₂ O/min):	0	Must be zero (manometer level stable for 1 minute)

Meter Box Vacuum Leak Check

Test Vacuum, (in. Hg):	25	Coarse adjust valve fully open, fine adjust fully closed, sample inlet plugged
Leak Rate, (cfm):	0	Must be zero (meter dial stable for 1 minute)

Meter Box Thermocouple Readout Calibration Check

Input Temperature	Allowable Temp. Dev.*	Low	High
30	7	23	37
70	8	62	78
120	9	111	129
250	11	239	261
350	12	338	362
500	14	486	514
700	17	683	717
900	20	880	920

Stack	Probe	Filter	Exit	Aux.	Meter In / Out
24	24	24	24	25	31
63	63	63	63	63	64
114	114	113	114	114	115
246	246	245			
345	345	345			
493					
696					
896					

Thermocouple simulator	
Make:	Omega
Model:	HH911T
Serial Number:	1788
Cal Date:	4/6/2018

* Reading values must be within 1.5% of reference thermometer values (based on absolute temperature scale) for calibration to be acceptable.

Performed by:

Name:

STEVE CROGHAN

Signature

[Signature]

Date:

6/11/18

Approved by:

Name:

Todd Smith

Signature

[Signature]

Date:

6/11/18



EPA Method 5

Meter Box Calibration by Calibrated Critical Orifice, Leak Check, and Thermocouple Calibration Check

English Meter Box Units, English K' Factor

Meter box ID:	CB-14
Meter ID (if applicable):	CB-14
Orifice set ID:	Antioch
Calibrated by:	SC
Expires:	12/8/18

Date:	6/8/18
Location:	Antioch
No. of orifices used (min. 3)	5
Barometric pressure (in. Hg):	29.95 in. Hg
Theoretical critical vacuum	14.13 in. Hg

Yd:	1.0140
$\Delta H@$:	1.756

Meter Box Orifice Calibration

IMPORTANT For valid test results, the Actual Vacuum should be 1 to 2 in. Hg greater than the Theoretical Critical Vacuum shown above
 IMPORTANT The Critical Orifice Coefficient, K', must be entered in English units, (ft)³/(deg R)^{0.5}/((in.Hg)^{0.5}(min)).

ΔH (in H ₂ O)	Time (min)	Volume			Initial Temps.		Final Temps.		Orifice Serial# (number)	K' Orifice Coefficient (see above)	Vacuum (in Hg)	-- Ambient Temperature --		
		Initial (cu ft)	Final (cu ft)	Net (cu ft)	Inlet (deg F)	Outlet (deg F)	Inlet (deg F)	Outlet (deg F)				Initial (deg F)	Final (deg F)	Average (deg F)
0.30	17.00	415.272	420.570	5.298	76.0	76.0	76.0	76.0	RG-40	0.2373	17.0	76.0	76.0	76.0
0.66	12.00	409.707	415.184	5.477	75.0	75.0	75.0	75.0	RG-48	0.3490	17.0	75.0	75.0	75.0
1.05	12.00	401.150	407.857	6.707	72.0	72.0	74.0	74.0	RG-55	0.4345	17.0	72.0	74.0	73.0
1.90	7.00	421.043	426.402	5.359	76.0	76.0	77.0	77.0	RG-63	0.6010	17.0	76.0	77.0	76.5
3.10	6.00	426.837	432.869	6.032	77.0	77.0	77.0	77.0	RG-73	0.7938	17.0	77.0	77.0	77.0

— SAMPLE RATE —
INDICATED VS. ACTUAL

ΔH (in H ₂ O)	Sample Rate (scfm)
0.30	0.307
0.66	0.452
1.05	0.564
1.90	0.777
3.10	1.026

— DRY GAS METER —
VOLUME
CORRECTED

Vm(std) (cu ft)
5.226
5.417
6.665
5.302
5.980

— ORIFICE —
VOLUME
CORRECTED NOMINAL

Vcr(std) (cu ft)	Vcr (cu ft)
5.219	5.295
5.423	5.491
6.764	6.824
5.440	5.524
6.156	6.257

— DRY GAS METER —
CALIBRATION FACTOR

Yd	Variation
Value (number)	(number)
0.9986	-0.015
1.0010	-0.013
1.0148	0.001
1.026	0.012
1.029	0.015

— ORIFICE —
CALIBRATION FACTOR
 $\Delta H@$

Value (in H ₂ O)	Variation (in H ₂ O)
1.766	0.010
1.796	0.040
1.843	0.088
1.743	-0.012
1.631	-0.125

For Calibration Factor Y, the ratio of the reading of the calibration meter to the dry gas meter, acceptable tolerance of individual values from the average is +/-0.02.

For Orifice Calibration Factor $\Delta H@$, the orifice differential pressure in inches of H₂O that equates to 0.75 cfm of air at 68 F and 29.92 inches of Hg, acceptable tolerance of individual values from the average is +/-0.2.

QA Criteria:	
Average Yd	1.0140
Average $\Delta H@$	1.7558
Variation of Yd's	PASS
Variation of $\Delta H@$	PASS
Vacuum Criteria	PASS

Meter Box Pressure Leak Check

Test Pressure, (in H ₂ O):	7	Should be 5-7 in. H ₂ O
Leak Rate, (in H ₂ O/min):	0	Must be zero (manometer level stable for 1 minute)

Meter Box Vacuum Leak Check

Test Vacuum, (in. Hg):	25	Coarse adjust valve fully open, fine adjust fully closed, sample inlet plugged
Leak Rate, (cfm):	0	Must be zero (meter dial stable for 1 minute)

Meter Box Thermocouple Readout Calibration Check

Input Temperature	Allowable Temp. Dev.*	Low	High
30	7	23	37
70	8	62	78
120	9	111	129
250	11	239	261
350	12	338	362
500	14	486	514
700	17	683	717
900	20	880	920

Stack	Probe	Filter	Exit	Aux.	Meter In / Out
24	23	25	23	23	31
63	63	64	63	65	71
112	112	112	112	112	120
244	244	244			
343	343	343			
491					
694					
894					

Thermocouple simulator	
Make:	Omega
Model:	HH911T
Serial Number:	1788
Cal Date:	4/6/2018

* Reading values must be within 1.5% of reference thermometer values (based on absolute temperature scale) for calibration to be acceptable.

Performed by:

Name:

STEVE CROGHAN

Signature

[Signature]

Date:

6/11/18

Approved by:

Name:

Todd Smith

Signature

[Signature]

Date:

6/11/18



Pitot Tube Calibration Data Sheet

Calibration Date:	12/7/2018	Performed by:	RV	Expiration Date:	June 7, 2019
		ID No.:	161	No obstructions:	YES
Calibrated Pitot Tube:	S-type	Probe/Pitot ID No:	161-NP-3	No damage:	YES
Probe Description:	NP	Effective Length (ft):	3	Level and Perpendicular:	YES
Thermocouple calibration performed?	Yes	Thermocouple passed calibration?	YES		




Protractor or Digital Angle Finder ID: 1-DPR-OAK

Measuring Tape ID: 1-TM-OAK



Caliper ID: CC#A114

Calibration performed using the procedures of EPA Method 2, Section 10.1

Alignment and Tubing Dimensions

Degree indicating level position for determining α_1 and α_2 .Degree indicating level position for determining θ .Degree indicating level position for determining γ then calculating Z.

Assembly Inter-Component Spacing Requirements



α_1 ($-10^\circ < \alpha_1 < +10^\circ$)	5
α_2 ($-10^\circ < \alpha_2 < +10^\circ$)	5
β_1 ($-5^\circ < \beta_1 < +5^\circ$)	-1
β_2 ($-5^\circ < \beta_2 < +5^\circ$)	2
γ	0
θ	0
A	0.8680
$z = A \tan \gamma$ ($\pm 0.125^\circ$)	-0.0015
$w = A \tan \theta$ ($\pm 0.03125^\circ$)	-0.0045
D_t ($0.1875" < D_t < 0.375"$)	0.3490
P_A ($1.05D_t < P_A < 1.5D_t$)	0.4620
P_B ($1.05D_t < P_B < 1.5D_t$)	0.4430
$ P_A - P_B \leq 0.0625$	0.0190

Pass


Pass

Pass

Pass

Pass

Pass



$W (\geq 3.0")$	7.000
-or- $AA (\geq 2.0")$	
X	0.878
D_n	0.500
$X / D_n (\geq 1.5)$	1.756
$Y (\geq 3.0")$	4.500
$Z \geq 0.75"$	1.198

Pass

Offset TC only


Setback TC only

Pass

Pass

Pass

Offset TC only



Performed By: Ryan Vogler

Approved By: STEVE CROCKMAN

Signature: Ryan Vogler

Signature: STEVE CROCKMAN

Date: 12/12/18

Date: 12/12/18

Pitot Tube Measurement Calibration Sheet

Revision: 2

Created: 3/16/15 by IE

Last revised: 5/11/18 by AV



Pitot Tube Calibration Data Sheet

Calibration Date:	12/7/2018	Performed by:	RV	Expiration Date:	June 7, 2019
		ID No.:	162	No obstructions:	YES
Calibrated Pitot Tube:	S-type	Probe/Pitot ID No:	162-NP-3	No damage:	YES
Probe Description:	NP	Effective Length (ft):	3	Level and Perpendicular:	YES
Thermocouple calibration performed?	Yes	Thermocouple passed calibration?	YES		





Protractor or Digital Angle Finder ID: 1-DPR-OAK

Measuring Tape ID: 1-TM-OAK



Caliper ID: CC#A114

Calibration performed using the procedures of EPA Method 2, Section 10.1


Alignment and Tubing Dimensions

Degree indicating level position for determining α_1 and α_2 .Degree indicating level position for determining θ .Degree indicating level position for determining γ then calculating Z.

Assembly Inter-Component Spacing Requirements



$W (\geq 3.0")$	7.000	Pass	Offset TC only
-or- $AA (\geq 2.0")$			Setback TC only
X	0.903		
D_n	0.500		
$X / D_n (\geq 1.5)$	1.806	Pass	
$Y (\geq 3.0")$	4.500	Pass	
$Z \geq 0.75"$	1.522	Pass	Offset TC only



Performed By:

Ryan Vogler

Approved By:

STEVE CROBLEN

Signature:

Ryan Vogler

Signature:

STEVE CROBLEN

Date:

12/12/18

Date:

12/12/18

Pitot Tube Measurement Calibration Sheet

Revision: 2

Created: 3/4/15 by IE

Last revised: 5/11/18 by AV

APPENDIX F MISCELLANEOUS INFORMATION

Appendix F.1 Permit Excerpts

**Condition # 23114**


S-6 & S-7 Shredder and Infeed Conveyor; abated by A-6 Water Sprays, A-2 Cyclone #2, A-3 Wet Scrubber; A-4 Dry Filter, A-9 Cyclone #3, and A-5 Mist Eliminator (until installation of enclosure and upgraded abatement system);
(A #14194; Revision 1: A #16721)

1. The owner/operator shall not exceed the scrap-in throughput limit of 720,000 tons in any calendar year at this facility.
(basis: baseline 2005 production level of 431,471 tons/yr; cumulative increase for the incremental throughput; health risk screening analysis)
2. The owner/operator shall enclose and vent the shredder to the abatement system at all times it is operating to minimize fugitive emissions.
(basis: TBACT)
3. The owner/operator shall abate particulate emissions from the shredder by water injection at a sufficient rate to ensure that non-metallic material exiting the unit be moist to the touch at all times, and abatement system consisting of cyclones, scrubber, filter, and demister at all times when the shredder is in operation. The PM grain loading at the exhaust outlet of the abatement system shall not exceed 0.01 gr/dscf.
(basis: TBACT)
4. The owner/operator shall operate the Recycling Center in such a manner that particulate emissions into the atmosphere from any operation/equipment for a period or periods aggregating more than three minutes in any hour shall not cause a visible emission which is as dark or darker than No. 0.5 on the Ringelmann Chart, or of such opacity as to obscure an observer's view to an equivalent or greater degree or result in fallout on adjacent property in such quantities as to cause public nuisance per District Regulation 1-301.
(basis: Regulations 6-1-301; 1-301)
5. The owner/operator shall use water spray to minimize fugitive dust emissions from material/scrap handling and storage to comply with condition 4. The owner/operator shall pave the site truck transport roads and sweep/spray with water/other actions deemed appropriate by the District, if necessary, to minimize fugitive dust emissions from trucking activities to comply with condition 4.
(basis: Regulations 6-1-301; 1-301)



6. The owner/operator shall not exceed a total of 26 ship calls and 63,875 truck calls per calendar year to haul in/out scrap/materials at the facility.
(basis: health risk screening analysis; CEQA review)
7. In order to demonstrate compliance with condition numbers 1 and 6, the owner/operator shall keep records of monthly and yearly throughput of materials, ship and truck calls in a District approved log. The log shall be maintained for a period of at least 24 months from the date of data entry and shall be made available to the District staff upon request for inspection.
(basis: recordkeeping)


End of Conditions

**Condition # 26401**

Upon installation of enclosure and upgraded abatement system for S-6:

S-6 Shredder and S-7 Infeed Conveyor; abated by A-6 Water Sprays, A-11 Venturi Scrubber, and A-12 Venturi Scrubber
(A #14194; Revision 1: A #16721; A #27762)

1. The owner/operator shall not exceed the scrap-in throughput limit of 720,000 tons in any calendar year at this facility. (Basis: Regulations 2-1-301 - baseline 2005 production level of 431,471 tons/yr - and 2-5-302 and Cumulative Increase for the incremental throughput)
2. The owner/operator shall enclose the shredder, S-6, and shall vent the shredder, at all times it is operating, to the Venturi Scrubbers, A-11 and A-12. The owner/operator shall minimize fugitive emissions from the shredder enclosure during shredder operation by (a) designing the enclosure such that the total surface area of all openings in the enclosure does not exceed 5% of the total surface area of the enclosure walls, floor, and ceiling; (b) using curtain walls or strip curtains on the inlet feed conveyor opening; and (c) ensuring that the ventilation fan is operating within its design range. The owner/operator shall demonstrate that the ventilation fan is operating within its design range by maintaining the amperage greater than [xxx, tbd by source test] amperes during shredder operation. The owner/operator shall operate each Venturi Scrubber in accordance with manufacture specifications. The owner/operator shall demonstrate this by maintaining a minimum water flow rate of [xx gallons per minute (gpm), tbd after source test] and an effective pressure differential operating range [xx to xx inches of H₂O, tbd after source test]. (Basis: TBACT)
3. Based on the results of the source testing required by Part 4, the owner/operator shall propose new emission rate limits for the shredder at stack P-15. The owner/operator shall propose limits for each of the following pollutants: Precursor Organic Compounds (POC), PM₁₀, PM_{2.5}, benzene, hexavalent chromium, PCBs, cadmium, lead, tetrachloroethylene, and trichloroethylene. The proposed emission rate limits shall be submitted to the District within 90 days of receiving the Part 4 source test results. The District will analyze the proposed limits, notify the owner/operator of any necessary changes to these limits, and revise this condition to include the new stack limits and associated monitoring requirements for P-15. In addition, the owner/operator shall estimate the fugitive emission rates that are not captured by the new shredder enclosure. (Basis: Cumulative Increase and Regulation 2-5-302)
4. Source Testing Requirements for Parts 3 and 5:
 - a. Prior to removal of the existing particulate abatement system, the owner/operator shall conduct source testing on the existing shredder abatement system that is intended to be used in conjunction with source testing in Part 4b to estimate captured emissions from the shredder and its associated systems. Particulate




emissions testing (filterable and condensable) shall be conducted at the inlet and outlet of the existing PM abatement system. In addition, the owner/operator shall estimate the fugitive emission rates that are not captured by the existing shredder enclosure.

- b. Within 90 days of start-up of A-11 and A-12, the owner/operator shall conduct a District approved source test at stack P-15, while the S-6 Auto Shredder is operating at or near the maximum operating rate. The owner/operator shall record the shredder processing rate, the water application rates for the infeed conveyor and the shredder, the water flow rates and the pressure differential operating ranges at each venturi scrubber, and the ventilation fan amperage during the source test. The source test shall determine the hourly emission rate and the average emission factor (pounds of pollutant per ton of material processed by the shredder) for the following compounds: total POC, PM, benzene, tetrachloroethylene, trichloroethylene, hexavalent chromium, PCBs, cadmium, and lead, and shall determine the outlet grain loading to demonstrate compliance with Part 5. In addition, the owner/operator shall conduct PM testing at the inlet to the A-11 and A-12 Venturi Scrubbers to determine the PM removal efficiency achieved by A-11 and A-12. The owner/operator shall also establish the ventilation fan amperage range necessary to operate the venturi scrubbers within the effective pressure differential ranges determined above.
- c. The owner/operator shall submit a source test protocol for the post enclosure construction compliance test to the Air District's Source Test Section Manager and to the Permit Engineer at least 30 days prior to the scheduled test date. The owner/operator shall submit a source test protocol for the pre-demolition source test to the Air District's Source Test Section Manager and to the Permit Engineer as soon as possible.
- d. The owner/operator shall notify the Source Test Section Manager of the scheduled test date at least 7 days prior to the scheduled test date and shall obtain District approval for all source test procedures prior to conducting any testing.
- e. The owner/operator shall submit a copy of the source test report to the Source Test Section Manager within 60 days of the test date.

(Basis: Cumulative Increase and Regulation 2-5-302)

5. The owner/operator shall apply water sprays (A-6) at the shredder, S-6, and infeed conveyor, S-7, at a sufficient rate to ensure that non-metallic material exiting the sources is moist to the touch at all times of operation. The PM grain loading at the exhaust stack P-15 shall not exceed 0.01 gr/dscf. (Basis: Cumulative Increase, TBACT; and Regulation 2-5-302)
6. The owner/operator shall operate the Recycling Center in such a manner that particulate emissions into the atmosphere from any operation/equipment for a period or periods aggregating more than three minutes in any hour shall not cause a visible emission which is as dark or darker than No. 0.5 on the Ringelmann Chart, or of such opacity as to obscure an observer's view to an equivalent or greater degree or result in fallout on



adjacent property in such quantities as to cause public nuisance per District Regulation 1-301. (Basis: Regulations 1-301 and 6-1-301)

7. The owner/operator shall use water spray to minimize fugitive dust emissions from material/scrap handling and storage to comply with Part 6. The owner/operator shall operate the facility at all times in accordance with its approved Emissions Minimization Plan (EMP). (Basis: Regulations 1-301, 6-1-301, and 6-4-301)
8. The owner/operator shall not exceed a total of 26 ship calls and 63,875 truck calls per calendar year to haul in/out scrap/materials at the facility. (Basis: health risk assessment for CEQA review)
9. In order to demonstrate compliance with Part 1 and 8, the owner/operator shall keep records of monthly and yearly throughput of materials, ship and truck calls in a District approved log. The log shall be maintained for a period of at least 24 months from the date of data entry and shall be made available to the District staff for inspection upon request. (Basis: Regulations 2-1-301 and 2-5-302, Cumulative Increase, CEQA)

End of Conditions

THIS IS THE LAST PAGE OF THIS DOCUMENT

If you have any questions, please contact one of the following individuals by email or phone.

Name: Mr. Robert Odell
Title: Client Project Manager
Region: Northwest
Email: rodell@montrose-env.com
Phone: 925-642-2776

Name: Mr. Kevin Crosby
Title: Vice President, Technical
Region: Northwest
Email: kcrosby@montrose-env.com
Phone: 925-680-4337